

Baseline Soil Investigation Santa Fe Pacific Gold, Elkhorn Project Jefferson County, Montana



Prepared For:

Santa Fe Pacific Gold Corporation Albuquerque, New Mexico

Prepared By:

**Hydrometrics, Inc.**Consulting Scientists and Engineers

September 1994

OCT 0 4 1994

STAIL LANDS

# BASELINE SOIL INVESTIGATION ELKHORN PROJECT JEFFERSON COUNTY, MONTANA

Prepared for:

Denise Gallegos
SANTA FE PACIFIC GOLD CORPORATION
P.O. Box 27019
Albuquerque, NM 87125

Prepared by:

HYDROMETRICS, INC. 2727 Airport Road Helena, MT 59601

September 1994

ANALYTICAL RESULTS FOR WINDHAM SERIES DATE SAMPLED: 9/21/93

HORIZON INTERVAL (inches) SAMPLE NUMBER		Ap 0 - 7 SFS-9309-226	BK1 7 - 11 SFS-9309-227	Bk2 11 - 17 SFS-9309-228	BK3 17 - 60 SFS-9309-229
DADAMETED	STINIT				
PARAME I EN	(113)	6.2	7.7	6.7	
rid cottonitos	(%) (%)	39.8	34.3	35.6	28.7
Sacutation Conductivity	(mmhos/cm)	0.40	0.41		
Openic Condensity	(mea/l)	1.90	2.52		1.00
Macconi	(med/l)	0.88	0.83		
	(med/l)	0.16	0.17		
Sodium Adepration Ratio	( h	0.14			
Cotion Exchange Canacity	(mea/100a)	36,30	38.81	36.96	
Callon Exchange Capacity	(%)	58			
Salia	(%)	28	25		) 28
	(%)	14	22	26	
Clay	(2.)	<u>1</u> 2	SCI		าร -
Von Eine Sand	(%)	7.52	6.28	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	3.08
Dock Fracments	(%)	45		5 44	
Organic Matter	(%)	3.0		9 1.2	2 0.3
Nitrato Nitrato	(110/01)	1.1	₹	▼	₹ -
Ammonia	(B/B1)	1.5	1.3	3 1.1	
Coloima Carbonate Equivalent	(6 (%)	1.3	က	5 40.9	
Nontralization Potential	(1/1000t)	13			
Acid Defential	(t/1000t)	<b>∀</b>	₹	7	₹
Acid Dono Dotontial	(t/1000t)	13	335	5 409	9 244

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

## TABLE OF CONTENTS

				Page
LIST	ΓOF	FIGUR	ES	iii
LIST	r of 7	ΓABLE	S	iv
LIST	OF A	APPEN	DICES	v
LIST	OF E	EXHIBI	TTS	v
1.0	INI	RODU	CTION	1
	1.1		EVIOUS INVESTIGATIONS	4
	1.2		DJECT AREA PHYSICAL CHARACTERISTICS	4
		1.2.	l Climate	4
		1.2.2	Geology and Geomorphology	4
		1.2.3	Soils	5
2.0	MET	THODO	LOGY	7
	2.1	SOII	MAPPING	7
	2.2	DES ANA	CRIPTION, SAMPLING AND LYSIS OF SOILS	8
3.0	SOIL	INVE	NTORY RESULTS	11
	3.1		MAPPING UNIT LEGEND AND SOIL MAPS	11
	3.2		TECT AREA SOIL ASSOCIATIONS	11
		3.2.1	Cryic Soils Formed in Colluvium or Residuum from Quartz Monzonite or Diorite	11
·.	·	3.2.2	Cryic Soils Formed in Alluvium, Colluvium or Residuum from Volcanics, Shale, Argillite, Hornfels, Skarn, and Porphyry	10
		3.2.3	Cryic Soils Formed in Alluvium, Colluvium or Residuum from Carbonate Rocks	18
			residual from Cardonale Rocks	20

ANALYTICAL RESULTS FOR WHITECOW SERIES DATE SAMPLED: 9/21/93

HORIZON INTERVAL (inches) SAMPLE NUMBER	SS	A 1 - 3 SFS-9309-242 SFS	Bk1 3 - 7 SFS-9309-243 \$	Bk2 7 - 17 SFS-9309-244	Bk3 17 - 30 SFS-9309-245	SFS-97	Bk4 30 - 60 309-246
PARAMETER	UNITS		1				4
	(n's)	7.5	7.5				- 6
	(%)	39.6	41.9				20.9
Saturation	(vo)	0 69	0.82				0.46
Specific Conductivity	(101111105/50111)	3.03 4.03	4 11				1.45
Calcium	(meq/l)	1.5	3.75				2.54
Magnesium	(meq/I)	7.7	000				0.19
	(meq/I)	0.00	50.0				0.13
Sodium Adsorption Ratio		0.04	0.03				4.21
≥	(meq/100g)	37.32	52.04				61
	(%)	54	26				- נו
	(2/)	36	38				S.
	(%)	5 5	(C				4
	(%)	2 ਹ	ੇ ਹਾ				S
Texture		7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	3.52				5.20
Very Fine Sand	(%) (%)	+ 7 - 4	99				70
Rock Fragments	(%)	ر ا ا	2.4				0.7
Organic Matter	(%)	73.4	73.3				69.5
Calcium Carbonate Equivalent	(%)	734	733		0 756		695
Neutralization Potential	(V 1000t)	5 7	₹ 7				7
Acid Potential	(V1000t)	731	733	730			695

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

				Page
		3.2.4	Frigid Soils Formed in Alluvium or Colluvium from Igneous and Sedimentary Rocks	21
		3.2.5	Poorly Drained Soils Formed in Alluvium	25
	3.3	SOIL	PROFILE DESCRIPTIONS	26
	3.4	LABO	DRATORY ANALYTICAL RESULTS	83
4.0	USE .	and M	MANAGEMENT OF ELKHORN PROJECT SOILS	84
	4.1		ORS USED TO DETERMINE SOIL SALVAGE THS AND RECLAMATION SUITABILITY	84
		4.1.1	Interpretive Groups	86
		4.1.2	Soil Chemical, Physical and Morphological Factors	86
		4.1.3	Soil Capability and Erosion	87
		4.1.4	Hydrologic Features	88
		4.1.5	Slope	. 88
	4.2	RECO	OMMENDED SOIL SALVAGE DEPTHS	88
	4.3	LANI	ABILITY OF SOILS FOR  D APPLICATION DISPOSAL  XCESS PROJECT WATER	91
5.0	REFE	RENCI	ES	94
			LIST OF FIGURES	
FIGU	RE 1.	REGI	ONAL LOCATION MAP	2
FIGU	RE 2.	BASE	ELINE SOIL INVENTORY STUDY AREA	3

ANALYTICAL RESULTS FOR WARNEKE SERIES DATE SAMPLED: 9/21/93

HORIZON		∢	五
IN LEKVAL (inches) SAMPLE NUMBER		0 - 2 SFS-9309-239	2 - 12 SES_0300_240
		2000 0 10	
PARAMETER	PLINIT		
Ha	(113)	7.7	7.2
Saturation	(%) (%)	2.7	J. 7.
Specific Conductivity	(mmhos/cm)	0.74	44.3 0 65
Calcium	(mea/l)	6.72	
Magnesium	(meq/l)	0.62	0.22
Sodium	(mea/l)	0.14	0.07
Sodium Adsorption Ratio	•	0.07	0.0
Cation Exchange Capacity	(meg/100g)	60.46	41 73
Sand	(%)	58	50
Sit	(%)	32	34
Clay	(%)	10	16
Texture	-	SL	٠ ــا
Very Fine Sand	(%)	7.40	2.12
Rock Fragments	(%)	\$	5.5
Organic Matter	(%)	10.3	
Calcium Carbonate Equivalent	(%)	55.6	64.0
Neutralization Potential	(V1000t)	556	640
Acid Potential	(V1000t)	▽	} ₹
Acid-Base Potential	(t/1000t)	556	640

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

## LIST OF TABLES

		<u>Page</u>
TABLE 2-1	BASELINE SOIL INVESTIGATION - SOIL SAMPLING AND ANALYSIS MATRIX, SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA	10
TABLE 3-1.	SOIL MAPPING UNIT LEGEND, SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA	12
TABLE 3-2.	SOIL MAPPING UNIT COMPOSITION, SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA	
TABLE 4-1.	SOIL SUITABILITY INTERPRETATION DATA, SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA	14 85
TABLE 4-2.	SOIL SALVAGE DEPTHS AND RECLAMATION CONSTRAINTS, SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA	89
TABLE 4-3.	CHEMICAL, PHYSICAL AND HYDROLOGIC CHARACTERISTICS OF POTENTIAL LAD SOILS, SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT,	
	JEFFERSON COUNTY, MONTANA	93

ANALYTICAL RESULTS FOR TROPAL(2) SERIES DATE SAMPLED: 10/05/93

HORIZON		A 7.	BK 7 - 15
IN I EKVAL (inches) SAMPLE NUMBER		SFS-9309-313	SFS-9309-313 SFS-9309-314
PARAMETER	UNITS		
Ha	(s.u.)	7.4	7.6
Saturation	(%)	45.2	33.1
Specific Conductivity	(mmhos/cm)	0.68	
Calcium	(meq/l)	5.48	
Magnesium	(meq/l)	2.67	
Sodium	(meq/l)	0.08	0.10
Sodium Adsorption Ratio	•	0.04	
Cation Exchange Capacity	(meq/100g)	50.9	28.4
Sand	. (%)	58	
	<b>%</b>	39	27
Clav	(%)	c	က
Texture		S	S
Very Fine Sand	(%)	2	9
Rock Fragments	(%)	52	33
Organic Matter	(%)	3.4	
Calcium Carbonate Equivalent	(%)	16.1	•••
Neutralization Potential	(V1000t)	161	238
Acid Potential	(V1000t)	₹ .	₹
Acid-Base Potential	(t/1000t)	161	238

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

#### LIST OF APPENDICES

## APPENDIX A. LABORATORY ANALYTICAL RESULTS

## LIST OF EXHIBITS

EXHIBIT	1.	BASELINE SOIL INVENTORY MAP, SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA	MAP POCKET
EXHIBIT	2.	BASELINE SOIL INVENTORY MAP, SECTIONS 1-4, SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY MONTANA	MAP POCKET

ANALYTICAL RESULTS FOR TROPAL SERIES DATE SAMPLED: 10/05/93

INTERVAL (inches) SAMPLE NUMBER	-	0 - 4 SFS-9309-311	BA 4 - 15 SFS-9309-312
PARAMETER	UNITS		
Hd	(s.u.)	7.5	7.5
Saturation	(%)	52.3	56.8
Specific Conductivity	(mmhos/cm)	0.54	0.57
Calcium	(meq/l)	5.85	6.19
Magnesium	(meq/l)	0.52	0.49
Sodium	(meq/l)	0.00	0.21
Sodium Adsorption Ratio		0.03	0.11
Cation Exchange Capacity	(meq/100g)	51.5	67.2
Sand	(%)	42	42
Sit	(%)	45	39
Clay	(%)	13	19
Texture		L	
Very Fine Sand	(%)	8	5
Rock Fragments	(%)	62	56
Organic Matter	(%)	6.7	4.7
Calcium Carbonate Equivalent	(%)	29.8	42.2
Neutralization Potential	(V1000t)	298	422
Acid Potential	(V1000t)	⊽	<u>~</u>
Acid-Base Potential	(t/1000t)	298	422

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

## BASELINE SOIL INVESTIGATION ELKHORN PROJECT JEFFERSON COUNTY, MONTANA

#### 1.0 INTRODUCTION

Santa Fe Pacific Gold Corporation (Santa Fe) proposes to develop a gold mine and ore processing facility located in the southern Elkhorn mountains near the Elkhorn townsite in Jefferson County, Montana (Figure 1). The proposed project would be located on patented and unpatented mining claims, U.S. Forest Service, Bureau of Land Management and private lands in Sections 2, 3, 10, 11, 14, 15, 16, 22, 23, 26, 27, 34 and 36, Township 6 North, Range 3 West; and Sections 3, 4, 9, 10 and 11, Township 5 North, Range 3 West.


A detailed baseline soils investigation was conducted to inventory the quality and quantity of soils within the proposed mine project area (Figure 2) that may be salvaged and utilized for reclamation purposes. Soil morphological, chemical and physical data were collected to support an evaluation of construction, reclamation, and land application disposal (LAD) activities based on established Montana Department of State Lands (MDSL) guidelines. During the investigation, every effort was made to give the Elkhorn Project baseline soil inventory continuity with U.S. Soil Conservation Service (SCS) soil survey party work conducted elsewhere in Jefferson County.

ANALYTICAL RESULTS FOR TOLBERT SERIES DATE SAMPLED: 9/22/93

A Bt BC	0-5 5-9 9-11	SFS-9309-251 SFS-9309-252 SFS-9309-253	
		SFS-9309-	
HORIZON	INTERVAL (inches)	SAMPLE NUMBER	

PARAMETER	UNITS			
100	(s.u.)	7.1	7.6	7.5
Saturation	(%)	37.7	32.8	49.1
Specific Conductivity	(mmhos/cm)	06.0	0.56	0.61
Calcium	(mea/l)	7.26	4.45	4.51
Mannesium	(mea/l)	1.03	0.61	0.84
Sociem	(mea/l)	0.32	0.33	0.34
Sodium Adsorption Ratio		0.16	0.21	0.21
Cation Exchange Canacity	(mea/100a)	39.73	38.81	41.18
Sand	(%)	20	74	64
2 150	(%)	26	22	24
Zei C	(%)	4	4	12
Textire		SF	SL	SF
Very Fine Sand	(%)	₹	1.08	7
Rock Fragments	(%)	53	72	53
Organic Matter	(%)	3.9	1.7	2.2
Calcium Carbonate Equivalent	(%)	1.6	8.6	0.7
Neutralization Potential	(V1000t)	16	98	7
Acid Potential	(V1000t)		⊽	₹
Acid-Base Potential	(V1000t)	16	98	7

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay



Proj. No: SFES01 Dwg. No: 31394H03 Drawn By: GBH

Last Update: 9/22/94 GBH Ref. Dwg: 31394T

Hydrometrics, Inc.

## Figure 1


Regional Location Map Elkhorn Project, Jefferson County, Montana

Baseline Soil Investigation Santa Fe Pacific Gold Corporation

ANALYTICAL RESULTS FOR TIGERON(2) SERIES DATE SAMPLED: 9/29/93

HORIZON INTERVAL (inches) SAMPLE NUMBER	SS	E1 0 - 2 SFS-9309-276 SF	E2 2 - 8 SFS-9309-277 SF	E/Bt 8 - 13 SFS-9309-278 SF	BVE 13 - 22 SFS-9309-279 SF	Bt 22 - 60 SFS-9309-280 SF	2C 60+ SFS-9309-281
PARAMETER	STIND						
Hd	(s.u.)	6.1	5.8	5.7	5.8	6.0	6.9
Saturation	(%)	6.99	29.6	26.8	25.4	31.1	27.8
Specific Conductivity	(mmhos/cm)	0.51	0.27	0.26	0.28	0.20	0.29
Calcium	(meq/i)	3.30	1.44	1.50	1.60	1.18	1.28
Magnesium	(meq/l)	1.53	0.78	1.02	0.95	0.81	0.80
Sodium	(meq/l)	0.18	0.16	0.26	0.34	0.27	0.67
Sodium Adsorption Ratio		0.12	0.15	0.23	0.30	0.27	0.66
Cation Exchange Capacity	(meq/100g)	44.28	25.09	24.29	27.94	33.33	28.22
Sand	(%)	63	55	90	59	52	61
Siit	(%)	29	40	35	32	37	30
Clay	(%)	æ	5	5	6	7	O
Texture		S	SF	S	SF	_	S
Very Fine Sand	(%)	24.72	3.92	6.40	6.04	6.46	10.72
Rock Fragments	(%)	7	54	47	43	42	7
Organic Matter	(%)	11.2	1.4	0.9	0.7	0.5	0.3
Nitrate	(6/6n)	₹	₹	7	⊽	⊽	⊽
Ammonia	(b/bn)	10.2	10.8	1.8	₹	1.3	1.2
Calcium Carbonate Equivalent	(%)	0.7	0.3	0.5	0.7	1.2	0.7
Neutralization Potential	(V1000t)	7	က	5	7	12	7
Acid Potential	(t/1000t)	₹	⊽	⊽	⊽	₹	⊽
Acid-Base Potential	(t/1000t)	7	က	5	7	12	7
:							

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay



Proj. No: SFES01 Dwg. No: 31394H01 Drawn By: MAS

Last Update: 9/22/94 GBH Ref. Dwg: 31394T

Hydrometrics, Inc.

## Figure 2

Baseline Soil Inventory Study Area Elkhorn Project, Jefferson County, Montana

Baseline Soil Investigation Santa Fe Pacific Gold Corporation

ANALYTICAL RESULTS FOR TIGERON SERIES DATE SAMPLED: 9/20/93

HORIZON INTERVAL (inches) SAMPLE NUMBER	-	O 0 - 1 SFS-9309-219	E1 1 - 4 SFS-9309-220	E2 4 - 10 SFS-9309-221	E-Bt 10 - 16 SFS-9309-222	Bt-E 16 - 20 SFS-9309-223	Bt 20 - 42 SFS-9309-224	2C 42 - 60 SFS-9309-225
DADAMETED	STINITS							
ויין אויין איין א	(6.11)	5.4	5.8	6.4				[.]
	(30.5.)	55.7	49.0	35.3				23.2
	(w) (mmhoe(cm)	0.37	0.37	0.59				0.37
Specific Conductivity	(model)	2.09	1.93	3.44				1.62
Calcium	(mod/)	89.0	090	1.29				0.81
Magnesium	(medy)	0.00	0.29	0.60				0.58
Sodium	(wheati)	2.0	0.26	0.39				0.53
Sodium Adsorption Ratio	/2004/2007/	0.10	56.79	33.67				19.57
Cation Exchange Capacity	(med/100g)	50.59	46	56				82
Sand	(%) (%)	3, 6	38	30		35		12
155 T	(%)	5 5	16	4				9
Clay	(%)	<u> </u>	2 -	ं छ				ST
l exture	(%)	13.06	99.9	4.46	4.58		1.46	5.26
very rine sand	( <sub>0</sub> / <sub>0</sub> )	C>	\$	45				99
Kock Fragments	(0/)	10.01	7.6	3.2				0.3
Organic Marter	(%)	7.5.	0.5	0.5		4.0		6.0
Calcium Carbonate Equivalent	(4/1000#)		5				7	6
Neutralization Fotential	(4,1000t)		` ₹	₹			₹	⊽
Acid Posential	(0.1000t)	- 4	5				7	6
Acid-Dasa Loici iliai	(2)							

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

#### 1.1 PREVIOUS INVESTIGATIONS

The SCS has mapped soils in the southern portion of the project area up to the Deerlodge National Forest boundary. The U. S. Forest Service completed a preliminary Level III Land System Inventory (U.S.D.A. 1980) map of the Deerlodge National Forest based on geology, soils and landform. Until the Santa Fe investigation, no detailed mapping of soils on land located in the Deerlodge National Forest within the upper portion of the project area had been conducted. The surficial geology of the Elkhorn Project area has previously been mapped (Klepper et al. 1957 and Everson et al. 1989).

## 1.2 PROJECT AREA PHYSICAL CHARACTERISTICS

#### 1.2.1 Climate

The elevation of the project area is between 5,000 and 7,800 feet above mean sea level and the climate of the Elkhorn Project area is characterized by long cold winters and short cool summers. The area averages between 20 and 30 inches of precipitation per year and the mean temperature is 38.3 degrees Fahrenheit. The growing season ranges from 60 to 90 days in length.

## 1.2.2 Geology and Geomorphology

The geology of the Elkhorn Project area is comprised of a folded sequence of sedimentary rocks which have been metamorphosed and altered by igneous intrusions associated with the Boulder Batholith. Igneous rocks in the project area include the Boulder Batholith quartz monzonite, a quartz-feldspar-porphyry (Turnley Ridge Stock), and less extensive, more mafic diorite stocks (Black Butte, East Butte, and Cemetery Ridge). Volcanic rocks in the project area are mostly andesite and are exposed south of the Elkhorn townsite.

Sedimentary rocks which extend over most of the project area are exposed in a north to northeast plunging anticline, the western limb of which has been engulfed by the batholith. Eastern limb sediments dip at approximately 45 degrees. These rocks range in age from late Precambrian to Mississippian and include shale, sandstone, and limestone. Metamorphism has transformed the shale units to argillite and hornfels, sandstone to quartzite, limy shales to calc-silicate hornfels, and limestone to marble. Further local metasomatic alteration of the

ANALYTICAL RESULTS FOR TEPECREEK(2) SERIES DATE SAMPLED: 10/04/93

SAMPLE NUMBER		0 - 2 SFS-9309-302	SFS-9309-303 SI	SFS-9309-304	SFS-9309-305	SFS-9309-306
PARAMETER	UNITS					
Hd	(s.u.)	5.4	5.4	6.2	62	9
Saturation	(%)	39.7	31.7	17,9		3
Specific Conductivity	(mmhos/cm)	0.33	0.30	0.28	0.25	0.25
Calcium	(meq/l)	1.88	1.81	1.60		1.2
Magnesium	(meq/I)	0.69	0.65	0.55		0.4
Sodium	(meq/l)	0.21	0.20	0.25		0.20
Sodium Adsorption Ratio		0.19	0.18	0.24		0.23
Cation Exchange Capacity	(meq/100g)	37.0	35.4	21.1		21.8
Sand	(%)	64	09	89		22
	(%)	29	31	24		7
Clay	(%)	7	6	8		9
l exture		S	SF	SF	JS	
Very Fine Sand	(%)	5	4	3	က	, -
Rock Fragments	(%)	99	?	51	42	· V
Organic Matter	(%)	4.5	3.3	0.7	0.7	, C
Calcium Carbonate Equivalent	(%)	0.8	0.3	0.4	0.4	4.0
Neutralization Potential	(V1000t)	80	က	4	4	; 7
Acid Potential	(V1000t)	₹	₹	⊽	₹	V
Acid-Base Potential	(t/1000t)	<b>&amp;</b>	က	4	4	

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

calc-silicate sedimentary rocks (and igneous rocks which intrude them) has produced pyroxene/garnet rich skarn which host ore deposits in the area.

Elkhorn Project area landforms include alluvial fans, stream valleys, gently sloping lowlands, dissected uplands, low hills, glacial valleys, steep mountain slopes and highland rock outcrops. Elevations range from 5,000 feet above sea level in the southern portion of the project area south of the Deerlodge National Forest boundary to 7,800 feet above sea level in the northern part of the project area.

#### 1.2.3 **Soils**

The development and characteristics of soils in the Elkhorn Project area are a function of many factors including but not limited to temperature, slope, aspect, vegetation and geology. Soil temperature regimes for the project area are cryic, with a mean soil temperature between 32 and 46 degrees Fahrenheit, or frigid, with a mean temperature less than 46 degrees Fahrenheit but with summer temperatures higher than summer temperatures for the cryic regime. Cryic soils in the project area generally occur at elevations greater than 6,000 feet above sea level. Frigid soils generally occur at elevations below 6,000 feet above sea level. The elevation at which frigid and cryic soils occur can vary somewhat depending upon aspect (north, south, east or west exposure).

The majority of the soils in the Elkhorn Project area are classified at the great group level of the U.S Comprehensive Soil Classification System as Cryoborolls, Cryoboralfs, Cryochrepts, Argiborolls, and Ustochrepts. Soils classified as Cryoborolls, Cryoboralfs and Cryochrepts are cold soils that occur in mountainous areas of the project (elevations greater than 6,000 feet above sea level). The vegetative cover on these soils consists of conifers and mixed conifers with some open grassland areas. These soils can be deep (greater than 50 inches to bedrock) or lithic (less than 20 inches to bedrock) and most are skeletal (greater than 30 percent rock fragments in the soil profile). Soils classified as Argiborolls and Ustochrepts are semiarid and occur on more moderate slopes at lower elevations (less than 6,000 feet above sea level). These soils may also be deep or lithic and are also mostly skeletal. The vegetative cover on these soils consists of grassland with scattered conifers.

ANALYTICAL RESULTS FOR TEPECREEK SERIES DATE SAMPLED: 9/30/93

HORIZON INTERVAL (inches)		A 0 - 4 SES-9309-294	E 4 - 14 SFS-9309-295	Bt 14 - 28 SFS-9309-296	BC 28 - 36 SFS-9309-297	Cr 36 - 53 SFS-9309-298
SAINIFLE NOINBEN		2-22-200-0-10	22222			
PARAMETER	UNITS					
На	(s.u.)	6.1		7.2		
Saturation	· (%)	41.6		26.4		
Specific Conductivity	(mmhos/cm)	0.36		0.39		
Calcium	(mea/l)	1.79		1.22		
Magnesium	(med/l)	1.93		2.62		
Sodium	(meq/l)	0.14		0.30		
Sodium Adsorption Ratio	-	0.10		0.22		
Cation Exchange Capacity	(mea/100a)	32.99	23.65	25.95		22.21
Sand	(%)	09		70		
?: #S	(%)	33		23		
Ciav	(%)	7		7	6	
Texture	•	S		SF		
Very Fine Sand	(%)	6.54	4.88	6.56		7
Rock Fragments	<b>%</b>	56	62	52		
Organic Matter	(%)	6.8	1.0	0.5	0.3	0.3
Calcium Carbonate Equivalent	(%)	0.8	1.0	2.0		
Neutralization Potential	(t/1000t)	8	10	20		
Acid Potential	(t/1000t)	₹	₹	₹		
Acid-Base Potential	(V1000t)	80	10	20	18	31

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

The surficial geology (parent material) greatly influences the classification and characteristics of project area soils. Soils derived from quartz monzonite or diorite tend to be more coarse textured while soils derived from quartz-feldspar-porphyry, andesite and shale tend to have accumulations of clay (argilic horizons). Soils derived from limestone, calc-silicate hornfels and marble are calcareous (calcic horizons).

ANALYTICAL RESULTS FOR SILAS SERIES DATE SAMPLED: 10/07/93

HORIZON INTERVAL (inches)		A1	A2	) (C
SAMPLE NUMBER		SFS-9309-334	SFS-930	SFS-93
PARAMETER	UNITS			
Hd	(s.u.)	6.1	6.4	6.4
Saturation	(%)	37.4	27.0	24.5
Specific Conductivity	(muhos/cm)	0.34	0.27	0.24
Calcinm	(meq/l)	2.14	1.27	0.80
Magnesium	(meq/l)	0.82	0.51	0.50
Sodium	(meq/l)	0.30	0.27	0.16
Sodium Adsorption Ratio		0.25	0.29	
Cation Exchange Capacity	(meq/100g)	34.6	23.3	
Sand	(%)	62	64	59
	(%)	29	26	30
Clay	(%)	6	10	7
Texture	-	SF	S	JS.
Very Fine Sand	(%)	4	4	2
Rock Fragments	(%)	\$	<2	<b>~</b>
Organic Matter	(%)	3.1	1.4	0.7
Nitrate	(6/6n)	1.1	₹	₹
Ammonia	(6/6n)	1.9	1.3	1.3
Calcium Carbonate Equivalent	(%)	0.3	0.2	0.3
Neutralization Potential	(t/1000t)	က	2	က
Acid Potential	(t/1000t)	<b>∵</b>	₹	₹
Acid-Base Potential	(t/1000t)	က	2	က

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

#### 2.0 METHODOLOGY

The Elkhorn Project baseline soil investigation was conducted in accordance with National Cooperative Soil Survey Standards. Reference materials include the National Soils Handbook (Soil Survey Staff 1983), Soil Survey Manual (Soil Survey Staff 1984) and Keys to Soil Taxonomy (Soil Survey Staff 1988). The U. S. Soil Conservation Service field office staff in Whitehall and Helena, Montana provided valuable input and assistance in the development of the Elkhorn Project soil inventory. The SCS assisted with a preliminary soil reconnaissance of the Deerlodge National Forest (northern) portion of the project area. Soil classification reports, mapping unit descriptions, official series descriptions and soil interpretation reports for the soils previously mapped or most likely to be encountered in the project area were obtained from SCS field offices or from the SCS interactive data base (FAST) located in the SCS State Office in Bozeman, Montana.

#### 2.1 SOIL MAPPING

The objective of soil mapping in the project area was to characterize soils in sufficient detail to provide reliable estimates of the volume of soils that could be salvaged once mine plans identify areas to be disturbed. Prior to initiating field survey efforts, field maps of surficial geology were prepared using 1:6000, 40-foot contour interval topographic maps, or if available, 1:6000, 10-foot contour interval orthophotograph maps of the project area. The project area was traversed and soils were described and identified, with their locations noted on field maps. Existing roads provided good access throughout most of the project area to make numerous observations of exposed soil and to establish good relationships between the occurrence of soils and surficial geology (parent material), orientation, slope and vegetation. In addition to existing road cuts, pits were excavated with a backhoe or by hand to expose soils for identification.

After soils were identified and correlated in the field, soil mapping units were delineated on 1:6000 uncontrolled color aerial photographs, and 1:6000, 40-foot contour interval topographic maps. Soil mapping units consist primarily of complexes since soil complexes in the Elkhorn Project area generally contain two or more dominant soil series, so

ANALYTICAL RESULTS FOR SHAWMUT SERIES DATE SAMPLED: 9/20/93

HORIZON INTERVAL (inches) SAMPLE NUMBER	o	A 0 - 3 SFS-9309-213 SF	Bt1 3 - 7 SFS-9309-214	Bt2 7 - 12 SFS-9309-215 S	Btk 12 - 15 SFS-9309-216 S	BK1 15 - 30 SFS-9309-217 SI	Bk2 30 - 60 SFS-9309-218
DADAMETER	UNITS				1	1	7.7
randine i Li	(113)	6.9	6.8		9.7	0.7	7.7
Hd	(a.u.)	31.0	38.7		41.5	43.1	25.8
Saturation	(%)	2.5	0.53		0.53	0.36	0.55
Specific Conductivity	(mmnos/cm)	0.7	3.53		3.48	2.41	1.34
Calcium	(meq/l)	4.0.4 80.4	0.02		0.62	0.82	2.69
Magnesium	(meq/l)	07.1	0.0		0.23	0.24	1.34
Sodium	(meq/l)	0.53	0.21		0.50	0 10	0.94
Sodium Adsorption Ratio		0.30	0.18		0.10	2 0	
Sodium Adsorption I valid	(mod/100a)	38.81	47.04		49.41	46.25	28.00
Cation Exchange Capacity	(Bool /ball)	7.2			09	64	80
Sand	(%)	t 6	20		29	29	17
Sit	(%)	י מ	7 7		7	7	က
Clay	(%)	~ ;	2 -5		ਂ ਹਾ.	S	ST
Texture		ر ا	J. V.		86.9	3.54	7.14
Very Fine Sand	(%)	. ·	4. 4.	5.E.	47	41	56
Rock Fragments	(%)	7 ;	7 6		14	1.0	0.2
Organic Matter	(%)	3.5	7.7		- 6	0 00	3.2
Calairim Carbonate Eduivalent	(%)	1.0	0.0		73.0	6.62	i
Calcium Carbonate Equivalent	(#/1000t)	10	0		230	299	35
Neutralization Poternial	(4,1000)	₹ ₹	<u>~</u>	₹	⊽	⊽	⊽
Acid Potential	(V1000t)	10	∞	6	230	299	32
Acid-Base Poleinia	(2000)						

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

intermingled that it is not possible to show each series separately on a map (Exhibit 1). To the extent possible, mapping units used in this investigation were consistent with soil mapping units used by the SCS for mapping soils in similar settings in Jefferson County, Montana. In some cases, mapping units or complexes were developed for the project that contain different combinations or proportions of soil series than previously utilized by SCS to map soils in Jefferson County. However, no soil series were identified in the project area that were not previously included in the SCS Jefferson County soil survey.

A Second Order level of mapping was used in the more accessible areas and areas most likely to be impacted by mining-related activities. Second Order soil delineations varied in size from 0.5 to 10 acres. A Third Order level of mapping was used in the more remote and geologically less complex areas, and in areas least likely to be impacted. Third Order delineations covered areas up to 500 acres in size. Mapping conducted by the SCS within the project area south of the Deerlodge National Forest boundary, and mapping completed by Hydrometrics in the northern portion of the project area was entered into an AutoCAD data base. AutoCAD was used to create soil inventory maps on a 1:6000, 40-foot contour interval topographic base, and to calculate the area of soil mapping units within the project area. A soil inventory map (1:12000) of the Elkhorn Project comprises Exhibit 1. This project area soil inventory is presented on a larger scale (1:6000) in four maps as Exhibit 2.

## 2.2 DESCRIPTION, SAMPLING AND ANALYSIS OF SOILS

Soils were described and sampled from freshly exposed road cuts or from pits excavated with a backhoe or by hand, depending upon accessibility. Prior to collecting samples from a soil series, the soil profile was described in detail. Information recorded included but was not limited to, thickness, texture, structure, consistency, color, and abundance of coarse fragments and roots for each genetic horizon. In the event a project area soil was mapped but not sampled, the SCS official series description (OSD) was used. Profile descriptions for all project area soils are in Section 3.3 of this soil inventory report.

The objective of soil sampling and analysis was to supplement information in soil profile descriptions and to evaluate the suitability of project area soils for salvage and reclamation

ANALYTICAL RESULTS FOR REDFERN(2) SERIES DATE SAMPLED: 9/29/93

HORIZON		⋖	Ш	ă
INTERVAL (inches)		0 - 4	6 - 9	9 - 14
SAMPLE NUMBER		SFS-9309-282	SFS-9308-282 SFS-9309-282 SFS-9309-284	SI-S-9309-284
PARAMETER	UNITS			-
Hd	(s.u.)	5.8	5.8	0.9
Saturation	(%)	58.5	26.4	28.5
Specific Conductivity	(mmhos/cm)	0.29	0.24	0.23
Calcium	(meq/l)	2.08	1.55	1.51
Magnesium	(meq/l)	7.70	0.55	0.57
Sodium	(meq/l)	0.08	0.11	0.15
Sodium Adsorption Ratio		0.07	0.11	0.15
Cation Exchange Capacity	(meq/100g)	53.83	26.81	23.94
Sand	(%)	54	89	58
Sit	(%)	41	25	39
Clay	(%)	5	7	3
Texture		SF	S	SI
Very Fine Sand	(%)	4.72	10.76	6.54
Rock Fragments	(%)	<2	55	59
Organic Matter	(%)	14.9	1.6	1.2
Calcium Carbonate Equivalent	(%)	0.7	0.5	0.4
Neutralization Potential	(V1000t)	7	5	4
Acid Potential	(V1000t)	₹	₹	₹
Acid-Base Potential	(V1000t)	7	5	4

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

or other purposes relative to DSL criteria. Each major soil series in the project area was sampled from at least one location. Soils that occurred more extensively in the project area and most likely to be impacted by mining-related activities were sampled at two locations. Soils of limited areal extent and outside the area that potentially could be disturbed by mining activities were not sampled. Alluvial soils and hydric soils located in active drainage areas were not sampled in order to avoid disturbances (pits) in potential wetland areas. Additional soil sampling can be conducted on a site-specific basis as mine plans are further developed. Soil sampling locations are shown in Exhibits 1 and 2.

A stainless steel trowel was used to obtain 500 to 1000 grams of soil from each horizon. The samples were placed in Ziplock freezer bags and shipped under chain-of-custody to Energy Laboratories, Inc. in Billings, Montana for analysis. The samples were analyzed for the parameters and according to analytical methods specified in Table 2-1. Table 2-1 also shows DSL unsuitability criteria for parameters that were analyzed. Not all parameters analyzed have unsuitability criteria and not all unsuitability criteria are applicable to the Elkhorn Project area soils.

ANALYTICAL RESULTS FOR REDFERN SERIES DATE SAMPLED: 9/22/93

INTERVAL (inches)	SFS	SFS-9309-258 SFS-9309-259		SFS-9309-260
DAMIT LE NOMBLE N				
PARAMETER	UNITS	4	90	6.2
Hd	(s.u.)	53.0	49.2	49.8
Saturation	(%) (mmhos/cm)	0.59	0.48	0.40
Specific Conductivity		3.17	2.63	2.54
Calcium	(med/l)	1.01	0.78	0.75
Magnesium :	(med/l)	0.32	0.26	0.33
Sodium	(intern)	0.22	0.20	0.26
Sodium Adsorption Katio	(4004)	63.12 63.12	58.11	57.58
Cation Exchange Capacity	(fined/ lood)	37.00	28	1
Sand	(%)	r α	7.5	58
Sit	(%)	÷ ÷	7 0	3 %
Clav	(%)	18	<u>•</u>	ָּהָ נ
Tochiro			Sil	SICL
TEXIUIE CONT	(%)	5.58	3.54	1.00
very Fine Saind	(%)	<2	· ?>	<b>?</b>
Kock Fragments	(0/)	e C	3.5	1.9
Organic Matter	(%)	) C	8	0.6
Calcium Carbonate Equivalent	(%)	- I	9 (	
Neutralization Potential	(V1000t)	7	٥	ο ·
Acid Dotostiol	(t/1000t)	-	τ-	<b>∵</b>
Acid Potential	(#/1000t)	7	သ	5

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

TABLE 2-1

BASELINE SOIL INVESTIGATION - SOIL SAMPLING AND
ANALYSIS MATRIX, SANTA FE PACIFIC GOLD CORPORATION,
ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA

Analytical Parameters	Reference Methods	DSL Unsuitability Criteria
pH EC Satn. % OM %	U.S.D.A Handbook No. 60, Method 21a U.S.D.A Handbook No. 60, Method 3 U.S.D.A Handbook No. 60, Method 4 ASA Monograph No. 9, Method 29-3.5.2	<4.5; >8.5 >4mmhos/cm <25%; >90% <1%
CEC	ASA Monograph No. 9, Method 8-3	NA
SAR	U.S.D.A Handbook No. 60, Methods 2, 3 and 4	>11
Texture: % sand % silt % clay	U.S.D.A Handbook No. 18,pp 205-223 U.S.D.A Handbook No. 18,pp 205-223 U.S.D.A Handbook No. 18,pp 205-223	<15% >35%
% coarse frag.	U.S.D.A Handbook No. 18,pp 205-223	(>2mm) >50% by volume; >66% by weight
CaCO3 equiv.	U.S.D.A Handbook No. 60, Method 23C	NA
Acid Potential	R.M. Smith, 1974	
Acid Base Potential	Calculated from acid potential and neutralization potential	<0 tons/1000tons*
**If pH < 5.0:		
Al As Zn Mn Cu Pb Ni Cd	SSSA, Vol. 35 No. 4, pp 600-602 ASA Monograph No. 9, Method 24-5.1 SSSA, Vol. 35 No. 4, pp 600-602	2 ppm (pH<5) 5 ppm 70 ppm (pH <6) 70 ppm (pH <6) 30 ppm (pH <6) 140 ppm (pH <5) 20 ppm (pH <6) 5 ppm (pH <6)
For Potential LAD Soils:		
NO3-N NH4-N	ASA Monograph No. 9, Method 33-3.1 ASA Monograph No. 9, Method 33-3.1	

<sup>\*</sup>Proposed for Elkhorn Project

<sup>\*\*</sup>As per the work plan, samples are not analyzed for metals if pH is 5 or greater

ANALYTICAL RESULTS FOR NIEMAN SERIES DATE SAMPLED: 9/22/93

INTERVAL (inches) SAMPLE NUMBER		A 0 - 4 SFS-9309-254	Bt1 4 - 6 SFS-9309-255	Bt2 6 - 12 SFS-9309-256
PARAMETER	UNITS			
Ha	(s.u.)	9.9	6.4	6.4
Saturation	(%)	38.7	35.7	34.3
Specific Conductivity	(mmhos/cm)	0.81	0.66	0.50
Calcium	(meq/l)	5.87	4.01	2.48
Magnesium	(meq/l)	1.94	1.45	0.99
Sodium	(meq/l)	0.45	0.76	1.20
Sodium Adsorption Ratio		0.23	0.46	0.91
Cation Exchange Capacity	(meq/100g)	40.39	37.49	41.44
Sand	(%)	54	52	51
Sit Control	(%)	34	32	33
Ciay	(%)	12	16	16
l exture		S	ب	
very rine sand	(%)	2.74	1.38	₹
Kock Fragments	(%)	7	\$	<b>~</b>
Organic Matter	(%)	3.6	1.4	6.0
Calcium Carbonate Equivalent	(%)	1.	0.5	90
Neutralization Potential	(V1000t)	7	5	9 6
Acid Potential	(V1000t)	₹	` ▽	, ∧
Acid-Base Potential	(V1000t)	7	. 73	· (C

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

## 3.0 SOIL INVENTORY RESULTS

## 3.1 SOIL MAPPING UNIT LEGEND AND SOIL MAPS

A total of 78 mapping units which covers a total of 8,957 acres and includes 41 soil series were identified in the project area. A soil mapping unit legend for the project area is in Table 3-1 which provides the slope (percent), area (acres), and extent (percent of total project area) of each mapping unit. A soil inventory map of the project area is in Exhibit 1.

Most mapping units identified for the Elkhorn project area (Table 3-1) contain varied proportions of soil series, rock outcrop or rock rubbleland, and inclusions. There may be different phases of a given soil series in a mapping unit based on differences in surface texture or stoniness. Inclusions are small areas of soils which are similar to the dominate series in the mapping units. The composition of each mapping unit, or the percentages of these mapping unit components, is summarized in Table 3-2. These percentages are utilized to estimate the acreages and volumes of soil that may be salvaged. Once mine plans are developed, this information will be required for reclamation plans and soil balance calculations.

## 3.2 PROJECT AREA SOIL ASSOCIATIONS

An association of soils is considered a landscape with soils occurring in distinctive patterns and proportions. In addition to landscapes, soil associations for the Elkhorn Project soil inventory are organized according to parent material and temperature regime categories. This is done to help users of the inventory better understand when and where specific soil series will occur in the project area. A discussion of soil associations also provides a meaningful summary of the relationships and rationale used to delineate soil mapping units.

## 3.2.1 Cryic Soils Formed in Colluvium or Residuum From Quartz Monzonite and Diorite

These soils are developed in and are influenced by parent material derived from the Boulder Batholith including diorite (Caseypeak-Bobowic-Franconi association) and quartz monzonite (Caseypeak-Tepecreek-Rock Outcrop association). The temperature regime is cryic (mean

ANALYTICAL RESULTS FOR MARTINSDALE SERIES DATE SAMPLED: 9/20/93

HORIZON INTERVAL (inches) SAMPLE NUMBER		Ap 0 - 3 SFS-9309-206 SI	Bt1 3 - 6 SFS-9309-207 SF	B12 6 - 10 SFS-9309-208 S	Btk 10 - 12 SFS-9309-209 SF	BK1 12 - 34 SFS-9309-210 SF	BK2 34 - 50 SFS-9309-211 SI	BC 50 - 60 SFS-9309-212
DARAMETER	UNITS							
H	(ns)	6.4	6.7	6.8	7.5	8.0	8.6	8.0
Cottestion	(%)	52.5	38.7	40.9	38.8	38.9	35.2	32.0
Specific Conductivity	(mmhos/cm)	0.88	0.50	0.99	0.59	1.75	3.88	8.92
Opecino Conductivity	(mea/l)	4.71	2.00	5.17	3.37	1.58	1.17	4.52
Magnetim	(med/)	1.57	0.72	1.72	1.11	1.87	2.50	14.10
Waying and a second a second and a second an	(1.5)	0.25	0.19	0.35	0.46	11.0	30.9	71.7
Sodium Adepration Patio		0.14	0.16	0.19	0.31	8.41	22.8	23.5
Cotion Exchange Conscity	(med/100d)	41.67	36.29	38.29	38.52	35.30	34.53	33.45
Callott Excitating Capacity	(%)	40	56	48	46	34	43	99
Salid	(%) (%)	49	32	33	34	38	39	53
	(%)	7	12	19	20	28	18	5
Clay	(0)	-	당		1	겅	_	S.
Very Fine Sand	(%)	7.98	4.90	3.98	1.72	₹	3.84	4.24
Vely ring cand	(%)	\$	\$	<b>~</b>	36	7	<b>~</b>	43
Organic Matter	(%)	6.1	2.4	1.7	1.7	1.0	2.0	0.3
Nitrate Marie	(ma/a)	2.0	₹	₹	1.3	⊽	₹	₹
Ammonia	(B)(D)	2.8	2.0	1.5	2.2	1.0	1.9	7:
Calcium Carbonate Equivalent	(%)	0.8	0.7	1.5	14.1	26.0	19.1	6.6
Neutralization Potential	(#/1000th	80	7	15	141	260	191	66
Acid Potential	(1/1000t)	-	⊽	۲	⊽	⊽	₹	⊽
Acid-Base Potential	(t/1000t)	∞	7	15	141	260	191	66

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

SOIL MAPPING UNIT LEGEND SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA

TABLE 3-1

		SIOPF	ABEA	EXTENT
SYMBOL	MAP UNII DESCRIPTION	(bercent)	(acres)	(percent)
			14.6	0.16
m •	MINES/DOMPS	8-0	3.6	0.04
4 1	USTIC TORRION TIENTS TO LEGYNGOLING		32.3	0.36
ر عد	CRACO GRAVELY LOAM	2-8	8.1	0.09
) (K	CONCO CONTRACTOR TO THE CONTRA	2-8	3.0	0.03
9 7	CHANGE IT CRAVELLY LOAM	4-15	45.4	0.51
	CHANNING STANDARD AND INTERPRETATION HAP AND IN STANDING	0-15	191.1	2.15
		15-35	7.9	0.09
р ( П г	LIBEG VERT GRAVELL. LOOM LIBEG VERT GRAVELL. LOOM	15-35	329.1	3.70
121 121 121		35-60	50.8	0.57
T (2)	MADDEN-LAT-NOCK OUT OVER THE STANDARD OF THE S	4-15	142.2	1.60
127 D	MAIDEN-EAT-VIND AD WINDHAM COMPLEX	15-35	57.3	0.65
	MAIDENLY APANINDHAM COMPLEX	35-60	27.6	0.31
132 5	MAIDELY DOCK OFFICE AP COMPLEX	8-35	91.4	1.03
123 1	WAIDEN-POCK OUTCOOL AP COMPLEX	35-60	13.5	0.15
7 27	HANGON-DRANDING VARIANT COMPLEX	4-15	150.9	1.70
	NAMINIA POCK OFFICE OF VERY STONY COMPLEX	8-35	27.9	0.31
	WINDHAM GRAVELLY LOAM	4-15	47.3	0.53
	MAINTING CONTEST OF THE CONTEST OF T	15-35	18.3	0.21
		15-35	31.3	0.35
_		4-35	47.3	0.53
		15-35	14.6	0.16
		15-35	56.8	0.64
		35-70	42.1	0.47
_		2-8	10.9	0.12
	CRAGO-ROCK OUTCROP-PENSORE COMPLEX	4-25	3.3	0.04
	CRAGO GRAVELLY LOAM	4-15	2.3	0.03
	BROWNSHUT	15-45	76.5	0.86
	BROWNSHUT GRAVELLY LOAM	4	56.4	0.63
	SIEBEN, STONY-SIEBERELL, VERY STONY COMPLEX	2-15	6.5	0.07
297 F	SIEBEN, RUBBLY-SIEBEN, VERY STONY COMPLEX	15-60	ຕິຕິ	2.0
325 A	FAIRWAY-NESTLEY CLAY LOAM	7-0	2.6	5.0
581 E	WHITECOW, STONY-WARNEKE, VERY STONY-ROCK OUTCROP COMPLEX	8-35 6-35	2.622	2.30
584 F	WHITECOW-WHITECOW, STONY-WARNEKE COMPLEX	09-67	38.3	54.0
585 E	WHITECOW, BOULDERY-SHAWMUT, VERY BOULDERY-ROCK OUTCROP COMPLEX	15-45	128.7	1.45
645 E	VARNEY, STONY-SIEBEN, VERY STONY COMPLEX	15-35	80.5 50.5	0.11
	MARTINSDALE, STONY-MARTINSDALE-HILGFIR COMPLEX	2 8	70.3 70.3	0.46
732 D	MARTINSDALE-SHAWMUT, STONY-MAITINSDALE, BOULDERY COMPLEX	4-25	17.0	3 T
742 E		4-25	137.0	4C.1
	SHAWMUT, BOULDERY-SHAWMUT, STONY-TOLBERT, BOULDERY COMPLEX		503.0	3.00
745 E		15-43	03.0	0.70
746 E	SHAWMUT:TOLBERT COMPLEX	00-0	77.1.7	)

ANALYTICAL RESULTS FOR MAIDEN SERIES DATE SAMPLED: 9/21/93

HORIZON INTERVAL (inches) SAMPLE NUMBER		A1 A2 BK1 BK2 0 - 4 4 - 7 7 - 11 11 - 26 SFS-9309-247 SFS-9309-248 SFS-9309-250	A2 4 - 7 SFS-9309-248 S	BK1 7 - 11 SFS-9309-249	Bk2 11 - 26 SFS-9309-250
PARAMETER	UNITS				
Hd	(s.u.)	7.3	7.2	7.4	
Saturation	(%)	39.5	38.2	45.2	
Specific Conductivity	(mmhos/cm)	0.52	0.63	0.44	
Calcium	(meq/l)	5.58	5.62	3.50	
Magnesium	(meq/l)	0.64	0.65	0.62	
Sodium	(meq/l)	0.08	0.13	0.33	
Sodium Adsorption Ratio		0.05	0.07	0.23	
Cation Exchange Capacity	(meq/100g)	40.40	36.92	49.68	16.54
Sand	(%)	44	50	28	
Silt	(%)	44	36	56	
Clay	(%)	12	14	16	
Texture				Sil	
Very Fine Sand	(%)	V	₹	3.62	1.96
Rock Fragments	(%)	\$	\$	<2	
Organic Matter	(%)	3.4	2.6	2.4	1.4
Calcium Carbonate Equivalent	(%)	50.9	67.0	45.6	9
Neutralization Potential	(t/1000t)	209	670	456	
Acid Potential	(t/1000t)	⊽	₹	₹	
Acid-Base Potential	(t/1000t)	209	670	456	

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

TABLE 3-1 (Continued)

SOIL MAPPING UNIT LEGEND SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA

SYMBOL	MAP UNIT DESCRIPTION	SLOPE (percent)	AREA	EXTENT
943 F	TIGERON, STONY-TIGERON VERY STONY COMBLEY	,	(20.02)	(percent)
944 E		25-60	18.1	0.20
945 E	TIGERON, VERY BOULDERY-REDFERN, BOULDERY-BOCK OF ITCEDED COMPANY	15-45	952.5	10.72
947 F	TIGERON, VERY STONY-REDFERN, RUBRI Y-ROCK RITIRE EL AND COMPLEX	15-45	512.4	5.77
952 F	REDFERN BOUI DERY-ROCK OF ITCHOOL TICES BOUND COMPLEX	25-60	32.0	0.36
953 F	REDFERN RUBBI Y-ROCK BIJBBI ELAND COMPLEX	25-60	75.5	0.85
954 F	REDEFEN BIRD Y-BOCKPU IND COMPLEX	25-60	26.0	0.29
992 E	LIBEG. VERY BOLL DERY, LIBEG. BOLL DEBY MITMAN, BOLL DERY COMPLEX	35-70	87.4	0.98
1103 D	ADEL-LIBEG COMPLEX	15-45	2.0	0.02
1222 C	MARTINSDA F-MARTINSDA F STONY CHANAMIT COMP. TO	4-15	77.0	0.87
	MARTINSDALE-MARTINSDALE, STONY-SHAWMIT COMPLEX	2-8	83.0	0.93
	MARTINSDALE, STONY-SHAWMUT COMPLEX	15-35	2.0	0.02
	BEAVERELL, STONY-BEAVERELL, RUBBLY-SIEBERFII STONY COMPILEY	2-15	154.0	1.73
	WINDHAM VERY GRAVELLY LOAM COMPI EX	C1-7	7.9	0.09
1342 E	WINDHAM-LAP VERY COBBLY LOAM COMPI FX	2-15	28.3	0.32
	WINDHAM-JUDELL VERY COBBLY LOAM COMPLEX	15-45	62.1	0.70
1563 D	HILGER, RUBBLY-HILGER COMPIEX	4-15	27.2	0.31
1640 D	NIEMAN-ROCK OUTCEOP! IREM: STONY COMP. EX	8-25	169.2	1.90
1641 E	NIEMAN-ROCK OUTCROP-I IBEG COMPLEX	2-15	8.9	0.08
1642 F	NEMAN-ROCK OI TOROP. I BEG VED BOTH TO STATE TO	15-45	37.6	0.42
1643 E	NIEMAN, STONY-LIBEG COMPLEX	25.60	484.1	5.45
1643 F	NIEMAN, STONY-LIBEG-ROCK OI TOROP COMPILEY	15-35	170.0	1.91
1652 E	SAWBUCK-CLASOIL COMPLEX	15-35	34.55	0.39
1740 E	TROPAL BOULDERY-HANSON STONY BOCK OFFICE OF THE FOLLOWING TO THE PROPERTY FOR THE PROPERTY	8-35	16.5	0.19
1742 F	TROPAL-ROCK OUTCEROP COMPLEX	8-25	94.5	1.06
1743 E	DRYADINE-TROPAL-ROCK OLITICATION EX	25-60	254.4	2.86
1743 F	DRYADINE-TROPAL - ROCK OLITCADO COMPLEX	8-25	225.3	2.54
1851 D	SHOOK-SI OCI IM-SII AS EAMII VI OAMS	25-60	302.4	3.40
	FRANCONI-CASEYPEAK VERY BOLL DEBY COMPLEY	0 <b>-8</b>	129.4	1,46
2090 F	CASEYPEAK VERY BOLL DECK DOCKER CONTINUES	35-60	125.2	1.41
2091 E	CASEYPEAK-ROCK RIJBRIET AND EDANGONI COMMITTED	25-60	2.9	0.03
2484 F		8-35	38.1	0.43
		35-70	7.9	0.09
8102 E		25-70	59.0	0.66
		8-35	1005.0	11.31
8106 F	_	35-60	117.7	1.32
		15-35	267.2	3.01
		35-60	63.3	0.71
8124 E		15-60	15.3	0.17
	STORY OF THE STORY	15-25	146.1	1.64
		Total	8957.2	100.80

ANALYTICAL RESULTS FOR LIBEG SERIES DATE SAMPLED: 10/06/93

SAMPLE NÙMBER PARAMETER	R	SES_9309-315 SE		CEC 0300 317 C	SFS-9309-318 SI	SFS-9309-319
PARAMETER		11	SFS-9309-316 SF	- 1		
	UNITS					
	(S.U.)	6.7	6.7	6.9	7.4	7.9
Saturation	(%)	39.3	30.2	29.9	30.9	26.0
Specific Conductivity	(mmhos/cm)	0.33	0.44	0.99	0.77	0.57
Openic Condensity	(med/)	1.99	2.04	1.74	0.88	0.84
Magaging	(med/l)	0.87	0.91	2.22	0.56	0.37
Nagi residiri Osdirim	(med/l)	0.16	1.50	6.50	6.32	5.31
Sodium Adsorption Ratio	(.h)	0.13	1.24	4.62	7.45	6.83
Cotion Exchange Canacity	(mea/100a)	37.1	26.8	27.3	28.2	30.0
Cand	(%)	42	46	47	45	52
	(%)	47	45	4	46	4
אַכּוּר רַי	(%)	7	တ	12	6	7
Toxtire	(21)	ليـ		_	_	<b></b> J
Very Fine Sand	(%)	5	S	6	7	6
Pock Framents	(%)	52	38	<b>7</b>	27	<2
Organic Matter	(%)	2.9	0.7	0.5	0.5	0.3
Nitrate	(na/a)	1.2	⊽	₹	₹	₹
Ammonia	(a/a)	2.1	1.9	1.3	1.5	1.5
Calcium Carbonate Equivalent	(%)	0.8	0.7	0.7	1.5	1.8
Neutralization Potential	(t/1000t)	, α	7	7	15	18
Acid Potential	(#/1000t)	⊽	⊽	₹	⊽	▼
Acid-Base Potential	(V1000t)	80	_	7	15	18

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

TABLE 3-2 SOIL MAPPING UNIT COMPOSITION SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA

SYMBOL	SERIES IN MAPPING UNIT	SLOPE (percent)	PERCENT OF MAPPING UNIT	SYMBOL	SERIES IN MAPPING UNIT	SLOPE (percent)	PERCENT OF MAPPING UNIT
		· · · · · · · · · · · · · · · · · · ·			HANCON		En
3	MINES/DUMPS		100	174 D	HANSON	4-15	
					DRYADINE VARIANT	4-15	
4	USTIC TORRIORTHENTS	0-8	40		INCLUSIONS		20
	TYPIC FLUVAQUENTS	0-1	40				
	INCLUSIONS		20	201 E	WINDHAM	8-35	30
	INCESSIONS				ROCK OUTCROP		20
			400		LAP, VERY STONY	8-35	
7 ·	MINES/QUARRIES		100		·	8-55	35
					INCLUSIONS		35
26 C	CRAGO GRAVELLY LOAM	2-8	90				
	INCLUSIONS		10	203 D	WINDHAM GRAVELLY LOAM	4-15	85
					INCLUSIONS		15
26 D	CRAGO GRAVELLY LOAM	2-8	90				
20 0	INCLUSIONS		10	203 E	WINDHAM GRAVELLY LOAM	15-35	85
	INCLUSIONS			200 2	INCLUSIONS		15
					INCLUSIONS		10
74 D	SHAWMUT GRAVELLY LOAM	4-15		_			
	INCLUSIONS		15	204 E	WINDHAM, STONY	15-35	
					MAIDEN, VERY STONY	15-35	20
92 D	FLUVAQUENTIC HAPLAQUOLLS	0-4	40		LAP, VERY STONY	15-35	20
	CUMULLIC HAPLAQUOLLS	0-2	30		INCLUSIONS		20
		0-15					
	TYPIC HAPLOBOROLLS	0-15		205 E	WINDHAM VERY COBBLY LOAM	4-35	85
	INCLUSIONS		10	205 E		+-55	
					INCLUSIONS		15
99 E	LIBEG VERY GRAVELLY LOAM	15-35	85				
	INCLUSIONS		15	206 E	WINDHAM	15-35	60
					WINDHAM, STONY	15-35	30
121 E	MAIDEN	15-35	45		INCLUSIONS		10
121 E		15-35					
	LAP	15-55		207 E	WINDHAM, STONY	15-35	45
	ROCK OUTCROP		20	207 €			
	INCLUSIONS		5		LAP, VERY STONY	15-35	
					ROCK OUTCROP		20
121 F	MAIDEN	35-60	40		INCLUSIONS		10
	LAP	35-60	30				
	ROCK OUTCROP		25	207 F	WINDHAM, STONY	35-70	35
			5		LAP, VERY STONY	35-70	25
	INCLUSIONS		3		ROCK OUTCROP		25
	·						15
122 D	MAIDEN	4-15			INCLUSIONS		15
	LAP	4-15	25				
	WINDHAM	4-15	20	209 C	WINDHAM COBBLY LOAM	2-8	60
	INCLUSIONS		15		JUDELL COBBLY LOAM	2-8	25
	111025010110				INCLUSIONS		15
	A A A I TO POAT	45 25	35		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		
122 E	MAIDEN	15-35		nea D	CRAGO	4-15	30
	LAP	15-35		263 D		7-13	25
	WINDHAM	15-35			ROCK OUTCROP		
	INCLUSIONS		20		PENSORE	4-25	
					INCLUSIONS		20
122 F	MAIDEN	35-60	40				
166	LAP	35-60		265 D	CRAGO GRAVELLY LOAM	4-15	90
					INCLUSIONS		10
	WINDHAM	35-60			,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		
	INCLUSIONS		- 15			40.00	. 40
				274 E	BROWNSHUT GRVL	15-45	
123 E	MAIDEN	8-15	45		BROWNSHUT CBVL	15-45	
	ROCK OUTCROP		20		BROWNSHUT, VERY STONY	15-45	20
	LAP	8-35			INCLUSIONS		10
		2.30	20				
	INCLUSIONS			275 A	BROWNSHUT GRAVELLY LOAM	1-4	90
			40	2137	INCLUSIONS	• •	10
123 F	MAIDEN	35-60			INCLUSIONS		10
	ROCK OUTCROP		25				
	LAP	35-60	20	294 C	SIEBEN, STONY	2-15	
			15		SIEBERELL, VERY STONY	2-15	35
	INCLUSIONS				,,		

ANALYTICAL RESULTS FOR LAP SERIES DATE SAMPLED: 9/21/93

INTERVAL (inches) SAMPLE NUMBER		A 0 - 5 SFS-9309-230	Bk1 5 - 9 SFS-9309-231	Bk2 9 - 19 SFS-9309-232
PARAMETER	UNITS			
Hd	(s.u.)	6.8	7.5	7.8
Saturation	(%)	33.8	47.5	52.9
Specific Conductivity	(mmhos/cm)	1.31	0.50	0.33
Calcium	(meq/l)	8.08	3.80	2.20
Magnesium	(meq/l)	2.42	0.84	
Sodium	(meq/l)	0.20	0.19	
Sodium Adsorption Ratio		0.00	0.12	
Cation Exchange Capacity	(meq/100g)	37.99	44.01	38.93
Sand	(%)	09	37	19
Silt	(%)	30	47	57
Clay	(%)	10	16	24
Texture		S		SiL
Very Fine Sand	(%)	3.16	5.58	₹
Rock Fragments	(%)	09	42	<2
Organic Matter	(%)	2.2	2.4	1.7
Nitrate	(a/gn)	▼	1.4	1.2
Ammonia	(6/6n)	5.0	3.2	2.5
Calcium Carbonate Equivalent	(%)	3.3	29.7	34.3
Neutralization Potential	(V1000t)	33	297	343
Acid Potential	(t/1000t)	₹	_	₹
Acid-Base Potential	(V1000t)	32	296	343

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

TABLE 3-2 SOIL MAPPING UNIT COMPOSITION

(Continued) SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA

731 C	SIEBEN, RUBBLY SIEBEN, VERY STONY INCLUSIONS  FAIRWAY CLAY LOAM NESTLEY CLAY LOAM INCLUSIONS  WHITECOW, STONY WARNEKE, VERY STONY ROCK OUTCROP INCLUSIONS  WHITECOW WHITECOW WHITECOW, STONY WARNEKE INCLUSIONS  WHITECOW, STONY WARNEKE INCLUSIONS  WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	(percent)  15-60 15-60  0-2 0-2 8-35 8-35  25-60 25-60 25-60	35 10 60 30 10 35 30 15 20 50 25	943 F 944 E 945 E	MAPPING UNIT  TIGERON, STONY TIGERON, VERY STONY INCLUSIONS  TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP INCLUSIONS  TIGERON, VERY BOULDERY REDFERN, BOULDERY REDFERN, BOULDERY REDFERN, BOULDERY ROCK OUTCROP INCLUSIONS	(percent)  25-60  25-60  15-45  15-45  15-45	30 10 55 20 15 10 50 25 15
325 A 581 E 584 F 585 E 645 E	SIEBEN, VERY STONY INCLUSIONS  FAIRWAY CLAY LOAM NESTLEY CLAY LOAM INCLUSIONS  WHITECOW, STONY WARNEKE, VERY STONY ROCK OUTCROP INCLUSIONS  WHITECOW WHITECOW, STONY WARNEKE INCLUSIONS  WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	15-60 0-2 0-2 8-35 8-35 25-60 25-60	35 10 60 30 10 35 30 15 20 50 25	944 E 945 E	TIGERON, VERY STONY INCLUSIONS  TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP INCLUSIONS  TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP	25-60 15-45 15-45 15-45	50 30 10 55 20 15 10 50 25
581 E 584 F 585 E 645 E	SIEBEN, VERY STONY INCLUSIONS  FAIRWAY CLAY LOAM NESTLEY CLAY LOAM INCLUSIONS  WHITECOW, STONY WARNEKE, VERY STONY ROCK OUTCROP INCLUSIONS  WHITECOW WHITECOW, STONY WARNEKE INCLUSIONS  WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	15-60 0-2 0-2 8-35 8-35 25-60 25-60	35 10 60 30 10 35 30 15 20 50 25	944 E 945 E	TIGERON, VERY STONY INCLUSIONS  TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP INCLUSIONS  TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP	25-60 15-45 15-45 15-45	30 10 55 20 15 10 50 25 15
581 E 584 F 585 E 645 E	FAIRWAY CLAY LOAM NESTLEY CLAY LOAM NESTLEY CLAY LOAM INCLUSIONS  WHITECOW, STONY WARNEKE, VERY STONY ROCK OUTCROP INCLUSIONS  WHITECOW WHITECOW, STONY WARNEKE INCLUSIONS  WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	0-2 0-2 8-35 8-35 8-35 25-60 25-60	10 60 30 10 35 30 15 20 50 25 15	945 E	INCLUSIONS  TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP INCLUSIONS  TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP	15-45 15-45 15-45	10 55 20 15 10 50 25
581 E 584 F 585 E 645 E	NESTLEY CLAY LOAM INCLUSIONS  WHITECOW, STONY WARNEKE, VERY STONY ROCK OUTCROP INCLUSIONS  WHITECOW WHITECOW, STONY WARNEKE INCLUSIONS  WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	25-60 25-60 25-60	60 30 10 35 30 15 20 50 25	945 E	TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP INCLUSIONS TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP	15-45 15-45	55 20 15 10 50 25
581 E 584 F 585 E 645 E	NESTLEY CLAY LOAM INCLUSIONS  WHITECOW, STONY WARNEKE, VERY STONY ROCK OUTCROP INCLUSIONS  WHITECOW WHITECOW, STONY WARNEKE INCLUSIONS  WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	25-60 25-60 25-60	30 10 35 30 15 20 50 25	945 E	REDFERN, BOULDERY ROCK OUTCROP INCLUSIONS TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP	15-45 15-45	20 15 10 50 25 15
584 F 585 E 645 E 731 C	INCLUSIONS  WHITECOW, STONY WARNEKE, VERY STONY ROCK OUTCROP INCLUSIONS  WHITECOW WHITECOW, STONY WARNEKE INCLUSIONS  WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	8-35 8-35 25-60 25-60 25-60	30 10 35 30 15 20 50 25	945 E	REDFERN, BOULDERY ROCK OUTCROP INCLUSIONS TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP	15-45 15-45	20 15 10 50 25 15
584 F 585 E 645 E 731 C	WHITECOW, STONY WARNEKE, VERY STONY ROCK OUTCROP INCLUSIONS  WHITECOW WHITECOW, STONY WARNEKE INCLUSIONS  WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	8-35 25-60 25-60 25-60	10 35 30 15 20 50 25		ROCK OUTCROP INCLUSIONS TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP	15-45	15 10 50 25 15
584 F 585 E 645 E 731 C	WARNEKE, VERY STONY ROCK OUTCROP INCLUSIONS  WHITECOW WHITECOW, STONY WARNEKE INCLUSIONS  WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	8-35 25-60 25-60 25-60	35 30 15 20 50 25		INCLUSIONS TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP		10 50 25 15
584 F 585 E 645 E 731 C	WARNEKE, VERY STONY ROCK OUTCROP INCLUSIONS  WHITECOW WHITECOW, STONY WARNEKE INCLUSIONS  WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	8-35 25-60 25-60 25-60	30 15 20 50 25 15		TIGERON, VERY BOULDERY REDFERN, BOULDERY ROCK OUTCROP		50 25 15
585 E 645 E 731 C	ROCK OUTCROP INCLUSIONS  WHITECOW WHITECOW, STONY WARNEKE INCLUSIONS  WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	25-60 25-60 25-60	15 20 50 25 15		REDFERN, BOULDERY ROCK OUTCROP		25 15
585 E 645 E 731 C	INCLUSIONS  WHITECOW WHITECOW, STONY WARNEKE INCLUSIONS  WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	25-60 25-60	20 50 25 15		REDFERN, BOULDERY ROCK OUTCROP		25 15
585 E 645 E 731 C	WHITECOW WHITECOW, STONY WARNEKE INCLUSIONS WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	25-60 25-60	50 25 15		ROCK OUTCROP	10-45	15
585 E 645 E 731 C	WHITECOW, STONY WARNEKE INCLUSIONS WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	25-60 25-60	25 15		_	_	
585 E 645 E 731 C	WHITECOW, STONY WARNEKE INCLUSIONS WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	25-60 25-60	25 15				
645 E 731 C	WARNEKE INCLUSIONS WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP	25-60	15		/		10
645 E 731 C	INCLUSIONS WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP		1	947 F	TIGERON, VERY STONY	25-60	45
645 E 731 C	WHITECOW, BOULDERY SHAWMUT, VERY BOULDERY ROCK OUTCROP				REDFERN, RUBBLY	25-60 25-60	45
645 E 731 C	SHAWMUT, VERY BOULDERY ROCK OUTCROP		10		ROCK RUBBLELAND	25-60	30 20
645 E 731 C	SHAWMUT, VERY BOULDERY ROCK OUTCROP				INCLUSIONS		20 5
731 C	ROCK OUTCROP	15-45	45				3
731 C		15-45	25	952 F	REDFERN, BOULDERY	25-60	40
731 C			15		ROCK OUTCROP	20.00	25
731 C	INCLUSIONS		15		TIGERON, VERY BOULDERY	25-60	25
731 C	VARMEN OFFICE		į		INCLUSIONS	20-00	10
731 C	VARNEY, STONY	15-35	60				10
731 C	SIEBEN, VERY STONY	15-35	30	953 F	REDFERN, RUBBLY	25-60	50
	INCLUSIONS		10		ROCK RUBBLELAND		30
	MARTINEDALE STORY				INCLUSIONS		20
	MARTINSDALE, STONY MARTINSDALE	2-8	35				
	HILGER	2-8	25	954 F	REDFERN, RUBBLY	35-70	40
	INCLUSIONS	2-5	25		ROCK RUBBLELAND		25
732 D			15		TIGERON, VERY BOULDERY	35-70	20
	MARTINSDALE	4-15			INCLUSIONS		15
	SHAWMUT, STONY	4-15	40				
	MARTINSDALE, BOULDERY	4-25 4-25	25	992 E	LIBEG, VERY BOULDERY	15-45	40
	INCLUSIONS	4-23	20 15		LIBEG, BOULDERY	15-45	30
			19		NIEMAN, BOULDERY	15-45	25
742 E S	SHAWMUT, STONY	15-25	60		INCLUSIONS		5
	MARTINSDALE, VERY STONY	4-15	30	4400 D			
	INCLUSIONS	7-10	10	1103 D	ADEL	4-15	50
			10		LIBEG	4-15	30
744 E S	SHAWMUT, BOULDERY	15-35	45		INCLUSIONS		20
S	SHAWMUT, STONY	15-35	20	1222 C	MARTINORALE		
Т	TOLBERT, BOULDERY	15-35	20	1222 0	MARTINSDALE STORY	2-8	40
11	NCLUSIONS		15		MARTINSDALE, STONY	2-8	20
			, ,		SHAWMUT	2-8	20
745 E S	SHAWMUT, BOULDERY	15-45	50		INCLUSIONS		20
	SHAWMUT, VERY BOULDERY		25	1222 E	MARTINSDALE		
	OLBERT, BOULDERY		20		MARTINSDALE, STONY	15-35	40
	NCLUSIONS		5		SHAWMUT	15-35	30
			-		INCLUSIONS	15-35	20
746 E SI	SHAWMUT	15-35	60		HOLOSIONS		10
TO		8-35	25	1223 D	MARTINSDALE, STONY	A	
. IN	OLBERT		15		SHAWMUT	2-15	40
					INCLUSIONS	2-15	25 35

the second of

ANALYTICAL RESULTS FOR HILGER SERIES DATE SAMPLED: 9/20/93

PARAMETER UNITS  PH Saturation (%) Specific Conductivity (meq/l) Magnesium (meq/l)							
uctivity	ر د						3
onductivity		5.9	6.1	7.0	9.7	7.7	ç. <i>)</i>
onductivity		42.1	38.9	45.9	41.4	34.2	41.4
	(mo/oo)	0.40	0.54	1.14	0.50	99.0	1.66
	(Os/Citt)	0.70	3.01	6.57	2.54	2.54	2.53
	€ €	200.7	1 14	2.41	1.39	1.96	3.15
	£ €	0.73	0.33	0.45	0.67	1.37	7.72
Sodium (meq//)	(v	0.50	0.0	0.21	0.48	0.91	4.58
Sodium Adsorption Ratio		0.23	0.20	57.87	45 54	37.91	63.68
Cation Exchange Capacity (med/	(meq/100g)	45.55	20.00	20.10	62	62	56
Sand (%)		<del>5</del> 5	† c	<u>ج</u> :	19	25	19
		42	66		19	13	25
Clay (%)		<u>o</u> -	3 ر	2 -	ਲ ਲ	SF	SCL
Texture		ې د	3 7	, ,	\ ∇	⊽	3.92
Very Fine Sand (%)		<del>-</del> !	7 9	, ,	- YC	, S	35
Rock Fragments (%)		35	7	? ;	2 6	, ,	000
Organic Matter (%)		3.2	1.2	1.2	7.0		7.0
		4.3	1.0	₹	⊽	<u>`</u>	<b>▽</b> ;
	s :	· κ.	5.2	2.5	1.4	4.1	2.0
Ammonia (ug/g)	-	9 9		2.4	6.9	5.6	3.3
JIValent	(+00		; -	24	69	26	33
Neutralization Potential	(00t)	, <u>f</u>	· <del>-</del>	⊽	₹	⊽	⊽
Acid Potential (v.1000t)	()()()	<del>,</del> ယ	· <del>(-</del>	24	69	56	33

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

TABLE 3-2 SOIL MAPPING UNIT COMPOSITION
(Continued) SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA

SYMBOL	SERIES IN MAPPING UNIT	SLOPE (percent)	PERCENT OF MAPPING UNIT	SYMBOL	SERIES IN MAPPING UNIT	SLOPE (percent)	PERCENT OF MAPPING UNIT
		(F - : : : : / .					
1322 D	BEAVERELL, STONY	2-15	30	1851 D	SHOOK	0-8	40
	BEAVERELL, RUBBLY	2-15	30		SLOCUM	8-0	20
	SIEBERELL, STONY	2-15	20		SILAS	0-8	20
• •	INCLUSIONS		20		INCLUSIONS		20
1341 D	WINDHAM VERY GRAVELLY LOAM	2-15	85	1951 E	FRANCONI	35-60	45
	INCLUSIONS		15		CASEYPEAK, VERY BOULDERY	35-60	35
					INCLUSIONS		20
1342 E	WINDHAM VERY COBBLY LOAM	15-45					
	WINDHAM VERY COBBLY LOAM	15-45		2090 F	CASEYPEAK, VERY BOULDERY	25-60	
	INCLUSIONS		5		ROCK RUBBLELAND FRANÇONI, VERY BOULDERY	25-60	20 15
			20		•	25-00	20
1343 D	WINDHAM VERY COBBLY LOAM	4-15			INCLUSIONS		20
	JUDELL VERY COBBLY LOAM	4-15			0.4057/0541/	5.25	45
	INCLUSIONS		10	2091 E	CASEYPEAK	8-35	45
					ROCK RUBBLELAND		20
1563 D	HILGER, RUBBLY	8-25			FRANCONI	8-35	20
	HILGER	8-25			INCLUSIONS		15
	INCLUSIONS		15	_			
			•	2484 F	ROCK RUBBLELAND		60
1640 D	NIEMAN	2-15	35		REDFERN, RUBBLY	35-70	20
	ROCK OUTCROP		30		HELMVILLE, RUBBLY	35-70	15
	LIBEG, STONY	2-15	15		INCLUSIONS		5
	INCLUSIONS		20				
				2485 F	ROCK RUBBLELAND		45
1641 E	NIEMAN	15-45	50		REDFERN, RUBBLY	25-70	25
	ROCK OUTCROP		25		TIGERON, VERY BOULDERY	25-50	20
	LIBEG	15-45	20		INCLUSIONS		10
	INCLUSIONS		5				
			ĺ	8102 E	TEPECREEK, BOULDERY	8-35	40
1642 F	NIEMAN	25-60	50		CASEYPEAK, VERY BOULDERY	8-35	35
	ROCK OUTCROP		25		ROCK RUBBLELAND		15
	LIBEG, VERY BOULDERY	25-60	25		INCLUSIONS		10
1643 E	NIEMAN, STONY	15-35	40	8102 F	TEPECREEK, BOULDERY	35-60	40
	LIBEG	15-35	35		CASEYPEAK, VERY BOULDERY	35-60	35
	INCLUSIONS		25		ROCK RUBBLELAND		15 10
	0.44.501.014	0.25	50		INCLUSIONS		10
1652 E	SAWBUCK	8-35	50	8106 E	TERECREEK VERY BOUR DERY	15-35	45
	CLASOIL	8-35	25	\$105 E	TEPECREEK, VERY BOULDERY	15-35	30
	INCLUSIONS		25		CASEYPEAK, VERY BOULDERY ROCK RUBBLELAND	15-55	20
	TROPAL BOULDERY	0.05	25		INCLUSIONS		5
1740 E	TROPAL, BOULDERY	8-25			INCLUSIONS		_
	HANSON, STONY	8-15		0406 E	TEPECREEK, VERY BOULDERY	35-60	35
	ROCK OUTCROP		20	8106 F	•	35-60	25
	INCLUSIONS		25		CASEYPEAK, VERY BOULDERY	33-00	25
		05.00			ROCK RUBBLELAND		15
1742 F	TROPAL	25-60			INCLUSIONS		13
	ROCK OUTCROP		30	8107 F	DOOK BURBLELAND		50
	INCLUSIONS		10 .	8107 F	ROCK RUBBLELAND CASEYPEAK, VERY BOULDERY	15-60	35
	DDV/ADINE		25			13-00	. 15
1743 E	DRYADINE	8-25			INCLUSIONS		- 15
	TROPAL	8-25	25	0404 5	DODOMAC	45.05	40
	ROCK OUTCROP		15	8124 E	BOBOWC	15-25	30
	INCLUSIONS		25		CASEYPEAK, BOULDERY ROCK RUBBLELAND	15-25	30 15
1743 F	DRYADINE	25-60	35		INCLUSIONS		15
1170 1	TROPAL	25-60	25				
	ROCK OUTCROP	20.00	30				
	INCLUSIONS		10				
	INCLUDIONO						

ANALYTICAL RESULTS FOR HELMVILLE SERIES DATE SAMPLED: 10/07/93

INTERVAL (inches) SAMPLE NUMBER		E Bt1 0 - 10 0 - 10	Bt1 10 - 18 SFS-9309-331	Bt2 18 - 38 SFS-9309-332	BK 38 - 60 SFS-9309-333
PARAMETER	UNITS				
Hd	(s.u.)	6.5	6.4	6.7	7.5
Saturation	(%)	22.7	27.7	25.1	21.7
Specific Conductivity	(mmhos/cm)	0.86	0.59	0.56	1.50
Calcium	(meq/l)	6.20	3.47	3.38	-
Magnesium	(meq/l)	1.96	1.43	1.31	
Sodium	(meq/l)	0.44	0.30	0.33	0.50
Sodium Adsorption Ratio		0.22	0.19	0.22	
Cation Exchange Capacity	(meq/100g)	20.0	31.0	25.6	
Sand	(%)	58	56	62	
Silt	(%)	35	29	27	29
Clay	(%)	7	15	7	
Texture		S	S	S	<u>~</u>
Very Fine Sand	(%)	4	4	80	7
Rock Fragments	(%)	54	46	<b>~</b>	51
Organic Matter	(%)	1.2	0.7	0.5	0.3
Calcium Carbonate Equivalent	(%)	0.7	0.7	0.8	60
Neutralization Potential	(V1000t)	7	7	· σ	
Acid Potential	(V1000t)	٧	⊽	, ∿	, ∴
Acid-Base Potential	(V1000t)	7	7	· cc	- «*

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

annual soil temperature between 32 and 46 degrees Fahrenheit) and, with the exception of the soil association present in alluvial landscapes (Shook-Slocum-Silas), slopes are generally greater than 25 percent. The mountain soils are usually present with rock outcrop in both forested and open landscapes.

# Casevpeak-Bobowic-Franconi association

This association consists of very steep to moderately sloping soils on mountain tops and slopes. These soils are formed in colluvium and residuum derived from diorite in the northern portion of the project area. Rock outcrop and rubble can be included in the association.

Caseypeak soil is shallow, well-drained and is present on 25 to 60 percent slopes. Below the surface organic (O) horizon is approximately 5 inches of light brownish-gray gravelly coarse sandy loam underlain by brown very gravelly coarse sandy loam. Bedrock is at approximately 19 inches. Caseypeak soil is also present in association with Tepecreek soil.

Bobowic soil is moderately deep, well-drained and is present on 25 to 60 percent slopes. The surface layer typically is grayish-brown very gravelly coarse sandy loam about 2 inches thick underlain by brown gravelly coarse sandy loam. Bedrock is at a depth of approximately 35 inches.

Franconi soil is moderately deep and well-drained and is also present on 25 to 60 percent slopes. The surface layer typically is a brown gravelly sandy clay loam approximately 4 inches thick. This is underlain by brown to yellowish brown gravelly sandy clay loam with bedrock at approximately 34 inches.

# Tepecreek-Casevpeak-Rock Outcrop association

This association consists of very steep to moderately sloping soils on mountain tops and slopes. These soils are associated with colluvium or residuum derived from quartz monzonite of the Boulder Batholith and cover an extensive area in the northeast portion of the project area. A brief and general description of Caseypeak soil is in the previous section.

ANALYTICAL RESULTS FOR HANSON SERIES DATE SAMPLED: 10/07/93

HORIZON		A1	A2		
INTERVAL (inches) SAMPLE NUMBER		0 - 8 SFS-9309-326	SFS-93(	14 - 21 SFS-9309-328	21 - 43 SFS-9309-329
PARAMETER	UNITS				
Ha	(s.u.)	6.5	7.0		
Saturation	· (%)	56.8	35.8		
Specific Conductivity	(mmhos/cm)	1.10	0.81		7 0.53
Coloim	(med/l)	8.87			
Magnetium	(mea/l)	2.30			
Coding	(med/l)	0.47			
Sodium Adsorption Ratio	(a.t.)	0.20	90.0	0.09	
Cotion Exchange Canacity	(mea/100a)	65.7			
Callon Exchange Capacity	(%)	32			
oand Mar	(%)	51	49	33	
	(%)	17	15		8
Ciay	(21)	Sil	_	S	
Very Fine Sand	(%)	5	7	•	_
Pock Fragments	(%)	\$	44		1 68
Organic Matter	(%)	7.1		3 1.6	
Nitrate	(110/0)	2.5	2.4		
Ammonia	(6/6n)	5.0			
Calcium Carbonate Equivalent	(%)	7.5	24.9	9 52.9	
Neutralization Potential	(t/1000t)	75		9 529	9 533
Acid Dotential	(1/1000t)	₹	₹	<del>-</del>	
Acid Boss Defential	(t/1000t)	75	249	9 529	9 533

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

Tepecreek soil is moderately deep, well-drained and occurs on 25-60 percent slopes. Below the O horizon, the surface layer typically is a grayish-brown gravelly sandy clay loam about 2 inches thick. This is underlain by brown to yellowish-brown gravelly sandy clay loam with bedrock at approximately 52 inches.

#### Shook-Slocum-Silas association

This association consists of mostly nearly level and gently sloping soils on low terraces of streams in mountain valley landscapes. This association is made up of 40 percent Shook soil, 20 percent Slocum soil, 20 percent Silas soil with up to 20 percent inclusions.

Shook soil is moderately deep, well-drained and is present on terrace edges and drainageways on granitic uplands and sideslopes. Slopes range from 8 to 25 percent and the surface horizon is a dark grayish brown loam about 7 inches thick. Subsurface soil is yellowish brown to dark grayish brown sandy loam with bedrock at approximately 26 inches.

Slocum soil is deep, somewhat poorly drained soil on terraces and floodplains with 0-4 percent slopes. The surface horizon typically is dark gray loam about 10 to 15 inches thick underlain by gray to brownish gray sandy to clay loam.

Silas soil is very deep, moderately well-drained soil also on terraces and floodplains. The surface horizon typically is a very dark grayish brown loam about 10 inches thick underlain by dark grayish brown to brown loam.

# 3.2.2 Cryic Soils Formed in Alluvium, Colluvium or Residuum from Volcanics, Shale, Argillite, Hornfels, Skarn, and Porphyry

These soils are cryic and are present on mountain sides, hilltops, footslopes, fans, and terraces from a variety of parent materials. These soils are shallow to very deep, well-drained and are present on 4-60 percent slopes.

ANALYTICAL RESULTS FOR FRANCONI(2) SERIES DATE SAMPLED: 10/06/93

HORIZON INTERVAL (inches) SAMPLE NUMBER		E 0 - 8 SFS-9309-320	E/Bt 8 - 14 SFS-9309-321	Bt/E 14 - 19 SFS-9309-322	Bt1 19 - 30 SFS-9309-323	Bt2 30 - 41 SFS-9309-324	Cr 41+ SFS-9309-325
PARAMETER	UNITS						
Hd	(s.u.)	6.1		9.9	6.7	9.9	6 9
Saturation	(%)	32.1		24.8	27.5	29.2	
Specific Conductivity	(mmhos/cm)	0.29		0.23	0.18	0.18	
Calcium	(meq/l)	2.03		1.44	1.04	0.99	
Magnesium	(meq/l)	0.72		0.59	0.54	0.59	
Sodium	(meq/l)	0.14		0.20	0.13	0.19	
Sodium Adsorption Ratio		0.12		0.20	0.15	0.21	
Cation Exchange Capacity	(med/100g)	18.3		25.4	28.5	30.4	
Sand	(%)	58	09	64	55	25	74
<b>慧</b>	(%)	40		36	43	40	
Clay =	(%)	2		0	2	က	
Texture		S		S	SF	ี้เร	
Very Fine Sand	(%)	5		5	z.	7	
Rock Fragments	(%)	51	<b>~</b>	<b>^</b>	<b>%</b>	48	
Organic Matter	(%)	2.2		0.7	0.5	0.5	
Calcium Carbonate Equivalent	(%)	0.5		0.7	0.8	10	. <del></del>
Neutralization Potential	(V1000t)	5		7	80	10	
Acid Potential	(V1000t)	₹	₹	₹	⊽	: ₹	? ₹
Acid-Base Potential	(t/1000t)	5	9	7	8	10	15

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

# Libeg-Nieman-Adel association

This association consists of gently sloping to moderately steep soils on alluvial fans, slopes and mountain tops and can contain up to 5 percent other soils. Soils in this association are formed in alluvium and volcanic colluvium and residuum. Rock outcrop can be included in this association.

Libeg soil is very deep, well-drained, and occurs on 15-45 percent slopes. The surface layer is a dark gray very gravelly loam about 10 inches thick underlain by brown to light yellowish brown gravelly, cobbly clay loam. The parent material is dominantly colluvium derived from igneous rocks. Libeg soil also occurs as an exclusive association on alluvial fans. In this setting, Libeg soil is a very gravelly loam on 15-35 percent slopes and can contain up to 15 percent inclusions.

Nieman soil is shallow, well-drained and is present on 15-60 percent slopes. The surface layer is 4-6 inches thick and consists of grayish brown very cobbly loam. The subsoil is brown extremely cobbly clay loam and volcanic bedrock is 15-16 inches below the surface.

Adel soil is formed in alluvium and is present on fans, terraces, slopes and upland swales. Adel soil is very deep, well-drained, and occurs on 4-15 percent slopes. The surface layer is 8-14 inches thick and consists of dark gray loam underlain by dark brown loam.

# <u>Tigeron - Redfern - Rock Outcrop association</u>

This association consists of strongly sloping to very steep, well-drained soils on mountain sideslopes and can contain up to 10 percent other soils as inclusions. This association is formed in alluvium or colluvium from igneous or siliceous sedimentary parent material. Rock outcrop makes up 15 percent of this association.

Tigeron soil is very deep, well-drained and is present on 15-45 percent slopes. Below the surface organic (O) horizon, the surface layer is 2-3 inches thick and consists of grayish brown very cobbly loam. The subsoil is grayish brown to yellowish brown very cobbly sandy clay loam.

ANALYTICAL RESULTS FOR FRANCONI SERIES DATE SAMPLED: 9/29/93

HORIZON INTERVAL (inches)	S	E 0 - 6 SFS-9309-289 SFS	E/Bt 6 - 11 SFS-9309-285 SF	Bt/E 11 - 17 SFS-9309-290	Bt1 17 - 24 SFS-9309-291	Bt2 24 - 32 SFS-9309-292	Cr 32+ SFS-9309-293
	O LINII						
PAKAMETEK	CIND (FIR)	6.3	6.7	6.9	6.7		7.2
nd acitarita	(a.u.)	33.0	34.4	28.8	30.5	29.8	25.0
Saturation	(mmhos/cm)	0.24	0.31	0.24	0.22		0.11
	2	1.50	1.81	1.29	1.02		0.56
Magagains	(mea/i)	1.21	1.42	1.40	1.09		0.85
Magnesian:	(med/l)	0.17	0.21	0.22	0.23		0.16
Sodium Adsorption Ratio	(idealli)	0.15	0.17	0.19	0.22		0.19
Cation Exchange Capacity	(mea/100a)	35.58	34.14	30.69	30.98		25.09
Canon Lydnange Capacity	(%)	77	74	73	74		88
	(%)	20	19	20	21		=
	(%)	က	7	7	5		-
Ciay	(2)	, <u>v</u>	ร	S	S		တ
Very Fine Sand	(%)	4.08	9.22	11.30	4.04		96.9
Pock Fragments	(%)	\$	41	56	42		7
Organic Matter	(%)	3.0	1.2	1.0	0.7		<0.1 1.0
Nitrate	(110/01)	1.	₹	7	₹		₹
Ammonia	(B,B,2)	1.4	1.2	⊽	₹		₹
Calcium Carbonate Equivalent	(%)	4.	4.1	1.4	1.5		1.7
Neutralization Potential	(t/1000t)	4	14	14	15		17
Acid Potential	(t/1000t)	⊽	₹	₹	₹		₹
Acid-Base Potential	(t/1000t)	41	14	14	15		16

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

Redfern soil is shallow, well-drained and is present on 15-45 percent slopes. The surface layer is 3 inches thick below the O horizon and consists of light brownish gray very cobbly loam. The subsoil is light gray to yellowish brown gravelly loam to gravelly clay loam. Helmville soil is also associated with Redfern soil.

3.2.3 Cryic Soils Formed in Alluvium, Colluvium or Residuum from Carbonate Rocks
The following soils are cryic and are located mainly on mountains, hills and slopes in areas
dominated by carbonate (limestone) rock types. These soils are shallow to very deep, welldrained, and occur on 2-60 percent slopes.

#### **Dryadine-Tropal-Hanson association**

This association consists of moderately sloping to very steep, well-drained soils on mountains and side slopes. These soils are formed in colluvium and residuum from carbonate (limestone) rock types. Rock outcrop can be included and all three soils need not be represented in the association.

Dryadine soil is effervescent, moderately deep, well-drained and is present on 2-45 percent slopes. The surface soil is dark grayish brown gravelly loam about 4 inches thick and is underlain by yellow to brown, violently effervescent cobbly loam. Limestone bedrock is at 36 inches. Dryadine soil can be present in association with Whitore soil.

Tropal soil is violently effervescent, shallow, well-drained and is present on 25-60 percent slopes. The soil is brown to light gray very gravelly loam with limestone bedrock at approximately 16 inches. Tropal soil can be present in association with Whitore soil.

Hanson soil is strongly effervescent, very deep and well-drained. This soil is formed in till in mountain valley landscapes and is present on 8-15 percent slopes. The surface soil is very dark grayish brown loam approximately 6 inches thick and is underlain by violently effervescent, grayish brown loam to cobbly loam.

ANALYTICAL RESULTS FOR DRYADINE(2) SERIES DATE SAMPLED: 9/28/93

HORIZON INTERVAL (inches) SAMPLE NUMBER		E 0 - 4 SFS-9309-266	E/Bk 4 - 7 SFS-9309-267	Bk/E 7 - 11 SFS-9309-268	Bk 11 - 16 SFS-9309-269	Ck 16 - 24 SFS-9309-270	Cr 24 - 60 SFS-9309-271
PARAMETER	UNITS						
Hd	(s.u.)	7.3	7.6	7.5	7.7	8.0	8.7
Saturation	(%)	56.4	42.8	40.5	35.1	30.8	29.8
Specific Conductivity	(mmhos/cm)	1.14	0.78	0.73	0.53	0.39	0.51
Calcium	(meq/l)	7.56	4.28	3.87	3.30	2.41	1.40
Magnesium	(meq/l)	6.34	6.20	5.37	3.80	2.49	5,35
Sodium	(meq/l)	0.13	0.18	0.15	0.12	0.13	0.35
Sodium Adsorption Ratio		0.05	0.08	0.07	0.06	0.08	0.19
Cation Exchange Capacity	(meq/100g)	60.99	40.12	34.35	24.22	16.70	10.34
Sand	(%)	55	89	72	72	69	02
	· (%)	39	29	23	25	22	30
Clay <del>T</del>	(%)	9	က	5	က	6	Y/N
l exture	,	SL	SF	S	SF	SL	S
Very Fine Sand	(%)	6.64	4.32	6.80	6.24	4.16	9.50
Kock Fragments	(%)	47	A/N	55	61	51	71
Organic Matter	(%)	7.7	4.2	3.7	2.1	0.5	0.3
Calcium Carbonate Equivalent	(%)	14.8	33.0	35.6	40.3	45.8	68.7
Neutralization Potential	(t/1000t)	148	330	356	403	458	289
Acid Potential	(t/1000t)	₹	⊽	^	₹	٧	₹
Acid-Base Potential	(V1000t)	148	330	356	403	458	687

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

#### Helmville soil

This soil occurs on moderately sloping to very steep mountain sideslopes and is formed in alluvium and colluvium derived from limestone, argillite, and igneous rocks. Helmville soil is effervescent, very deep, well-drained and is present on 15-45 percent slopes. The surface layer is light brownish gray cobbly loam approximately 10 inches thick underlain by yellowish brown very cobbly clay loam which is violently effervescent in its deeper horizons.

# 3.2.4 Frigid Soils Formed in Alluvium or Colluvium from Igneous and Sedimentary Rocks

The following soils are mainly on raised benches, alluvial fans, foothills, ridges, and drainageways and are formed in alluvium or colluvium from a variety of source rocks. These soils are shallow to very deep, well-drained and are present in the frigid temperature regime (mean annual temperature is less than 46 degrees Fahrenheit and summer temperature is higher than summer temperature for cryic regime).

#### Brownshut association

This association is on gently sloping alluvial fans and raised benches and can contain up to 10 percent other soils. Brownshut soil is deep, well-drained and occurs on 1-4 percent slopes. The surface layer is 2 inches thick and consists of dark grayish brown gravelly loam which is underlain by effervescent gravelly to cobbly loam.

# Crago-Rock Outcrop-Pensore association

This association consists of gently sloping, well-drained soils on foothills and dissected uplands and can contain up to 10 percent other soils as inclusions. This association is formed in alluvium and colluvium from carbonate (limestone) rock types. Rock outcrop can make up 25 percent of the association and not all components need be represented for the association to be complete.

Crago soil is violently effervescent, very deep, well-drained and is present on 2-15 percent slopes. The surface layer is 4 inches thick and is composed of brown gravelly loam. The subsoil is yellowish to pale brown gravelly loam.

ANALYTICAL RESULTS FOR DRYADINE SERIES DATE SAMPLED: 10/05/93

HORIZON		0 - 6	БW 6 - 16		29 - 40
INTERVAL (IIGNES) SAMPLE NUMBER	R		SFS-9309-308 S	SFS-9309-309	SFS-9309-310
	STINI				
PAKAMETER	01110	7.5	7.6	7.8	7.8
Ha.	(s.u.)	14.2	19.3	33.6	28.5
Saturation	( 70) (mmhoc/cm)	0 72	0.49	0.38	0.35
Specific Conductivity	(magall)	7 04	4.64	3.63	3.38
Calcium	(medu)	1.53	0.87	0.63	0.51
Magnesium	(medy)	- 55	0.11	0.19	0.16
Sodium	(meq/l)	2 .0	0.07	0.13	0.11
Sodium Adsorption Ratio		0.0	42.5	26.3	13.4
Cation Exchange Capacity	(med/100g)	4.4.	2.5	57	72
Sand	(%) 8)		45	38	25
Silt	(%) (%)	7	7	5	
Clay	(%)	<u>t</u> –	•	ร	าร
Texture	(70)	1 4	' ⊽	2	
Very Fine Sand	(%) (%)	, F	69	99	=
Rock Fragments	(%)	8 6	2.9	2.1	
Organic Matter	(%)	25.0	34.9	52.8	59.1
Calcium Carbonate Equivalent	(%)	350	349	528	
Neutralization Potential	(0,0001,0)	g /	\$ \footnote{\chi_{\text{\chi}}}	`	
Acid Potential	(10001/1)	350	349	528	591

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

Pensore soil is shallow, well-drained, violently effervescent and is present on 2-15 percent slopes. The surface layer is 4 inches thick and is composed of a grayish brown gravelly loam. The subsoil is light gray very gravelly loam and hard limestone bedrock is within 16 inches of the surface.

# Maiden - Lap - Windham association

This association consists of gently sloping to very steep, well-drained soils on hilltops, slopes, uplands and lowlands and can contain up to 15 percent other soils as inclusions. This association is formed in colluvium and residuum from carbonate (limestone) rock types. This association is variable in that rock outcrop can be included and all three soil types need not be represented.

Maiden soil is effervescent, moderately deep, well-drained and is present on 4-60 percent slopes. The surface layer is 3-6 inches thick and consists of dark grayish brown gravelly loam underlain by light gray to light brown gravelly to cobbly loam.

Lap soil is effervescent, shallow, well-drained and is present on 4-60 percent slopes. The surface layer is 4-7 inches thick and is typically a dark grayish brown very gravelly loam. The subsurface soil is light brownish gray to brown extremely gravelly loam. Limestone bedrock is at a depth of about 18 inches.

Windham soil is very deep, effervescent, well-drained and is present on 4-60 percent slopes. The surface layer is 2-8 inches thick and consists of dark grayish brown gravelly loam which is typically underlain by pale brown, violently effervescent very gravelly loam. It should be noted that Windham soil can form an exclusive association.

#### Judell soil

This soil is formed in calcareous alluvium and is present on terraces and fans. Judell soil is very deep, well-drained, and occurs on 2-15 percent slopes. The surface layer is 5 inches thick and consists of grayish brown very cobbly loam. The subsoil is white to brown,

ANALYTICAL RESULTS FOR CASEY PEAK(2) SERIES DATE SAMPLED: 9/29/93

INTERVAL (inches) SAMPLE NUMBER		E 0 - 5 SFS-9309-286	Bw 5 - 14 SFS-9309-287	Cr 14 - 18 SFS-9309-288
PARAMETER	UNITS			
Hd	(s.u.)	7.0	7.7	7.7
Saturation	(%)	59.2	36.8	37.6
Specific Conductivity	(mmhos/cm)	0.36	0.42	0.33
Caicium	(meq/l)	1.04	1.01	0.88
Magnesium	(meq/l)	3.89	3.34	2.69
Sodium	(meq/l)	90.0	0.14	0.10
Sodium Adsorption Ratio		0.04	0.00	0.07
Cation Exchange Capacity	(meq/100g)	51.90	31.84	40.90
Sand	(%)	64	74	202
<b>読</b>	(%)	33	26	27
Clay	(%)	က	<b>AN</b>	i "
l exture		SL	SI	S
Very Fine Sand	(%)	10.26	11.30	9.16
Rock Fragments	(%)	32	09	32
Organic Matter	(%)	4.4	1.0	1.0
Calcium Carbonate Equivalent	(%)	2.5	4.1	3.4
Neutralization Potential	(V1000t)	25	41	34
Acid Potential	(V1000t)	-	_	\
Acid-Base Potential	(t/1000t)	24	41	34

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

violently effervescent very cobbly to very gravelly clay loam. Judell soil is present in association with Windham soil.

#### Martinsdale soil

This soil is formed in alluvium and is present on foothill slopes and drainageways, alluvial fans, and stream terraces. Martinsdale soil is very deep, well-drained, and occurs on 2-35 percent slopes. The surface layer is 5-8 inches thick and consists of dark grayish brown loam to cobbly sandy clay loam. The underlying material has a variable color (white, yellowish brown, light gray, or brown) and texture (gravelly, gravelly clay, clay loam, loam, or gravelly sandy clay loam). Martinsdale soil is present in association with Hilger soil and with Shawmut soil.

#### Hilger soil

This soil is present on low foothills and is formed in alluvium or colluvium from an igneous source. Hilger soil is deep, well-drained and occurs on 2-25 percent slopes. The surface layer is 5-8 inches thick and consists of dark grayish brown very cobbly loam. The subsoil is a brown to yellowish brown cobbly to cobbly clay loam which effervesces. Hilger soil is present as an exclusive association and in association with Martinsdale soil.

#### Shawmut soil

This soil is formed in alluvium or colluvium from igneous parent material and is present on low hills and slopes. Shawmut soil is very deep, well-drained, and occurs on 4- 45 percent slopes. The surface layer is 5-7 inches thick and consists of grayish brown gravelly loam to gravelly sandy clay loam which is underlain by gray to yellowish brown gravelly sandy clay loam which effervesces. Shawmut soil is present as an exclusive association and in association with both Martinsdale soil and Tolbert soil.

#### Tolbert soil

This soil is formed in colluvium from igneous parent material and is present on hills and slopes. Tolbert soil is shallow, well-drained and is present on 8-45 percent slopes. The surface layer is 4-7 inches thick and consists of grayish brown cobbly loam underlain by

ANALYTICAL RESULTS FOR CASEY PEAK SERIES DATE SAMPLED: 9/23/93

HORIZON INTERVAL (inches) SAMPLE NUMBER	·	E 0 - 4 SFS-9309-262	Bw 4 - 9 SFS-9309-263	E Bw BC 0-4 4-9 9-12 SFS-9309-263 SFS-9309-264	12 - 17 12 - 17 SFS-9309-265
DADAMETED	SLINITS				
PARAIME I EN	(118)	5.2	5.0		6.5
	(%)	39.2	27.7		
	(w) (mmpoe/cm)	0.32	0.26		
Specific Conductivity	(med/)	1.84	1.49		
	(med)	0.75	0.51		
Magnesium	(med/)	0.12	0.24		
		0.11	0.24		
Sodium Adsorption Ratio	(mod/100a)	33.92	24.07	22.	•
Cation Exchange Capacity	(Soot /boill)	63	•		
Sand	(%)	3 8	27		
	(%)	; c			3 N/A
Ciay = .	(o/)	ੇ ਯ.	รร	ST	
l exture	(%)	1.58	2	4 6.30	0 11.56
Very File Salid	(%)	<2	ν	``	2 42
Rock Fraginents	(%)	4.3		3.4	4 <0.1
Organic Matter	(%)	0.0	7.0	7 1.3	
Calcium Caroorate Equivalent	(4/1000#)			7	က
Neutralization Potential	(0.1000t)	' ₹	v	V	τ-
Acid Potential	(V 1000t)	9	- 10	7	3

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

brown cobbly clay loam. Bedrock is 11-12 inches below the surface. Tolbert soil is found associated with Shawmut soil.

# Whitecow-Warneke-Rock Outcrop association

This association consists of strongly sloping to very steep, well-drained soils on mountain sideslopes and can contain up to 20 percent other soils. This association is formed in colluvium and residuum from carbonate (limestone) rock types. Rock outcrop can be included in this association.

Whitecow soil is very deep, well-drained and is present on 8-60 percent slopes. Below the O horizon, the surface layer is about 5 inches thick and consists of dark grayish brown gravelly loam. The subsoil is strongly effervescent light gray to brown very gravelly loam. Whitecow soil can also be associated with Shawmut soil.

Warneke soil is shallow, well-drained and is present on 8-60 percent slopes. This soil also has an O horizon and the surface soil underneath is about 4 inches thick and consists of violently effervescent very stony loam. Limestone bedrock is about 11-12 inches from the surface.

### Sieben-Varney-Sieberell association

This association consists of gently sloping, well-drained soils on alluvial fans and stream terraces. These soils, the deeper horizons of which are effervescent, are formed in alluvium from a variety of rock sources. All soil types need not be represented for the association to be complete.

Sieben soil is very deep, well-drained and is present on foothills and alluvial fans with 2-15 percent slopes. The surface layer typically is dark grayish brown, cobbly loam about 3 inches thick. The underlying soil is grayish brown to brown cobbly clay loam to very gravelly clay loam.

Varney soil is very deep, well-drained, and occurs on alluvial fans, terraces, and hills with 15-25 percent slopes. The surface layer is typically a dark grayish brown loam about

ANALYTICAL RESULTS FOR BROWNSHUT SERIES DATE SAMPLED: 9/21/93

HORIZON INTERVAL (inches)		∢ 6	BK1	Bk2	BK3	Bk4	BC
SAMPLE NUMBER		0 - 2 SFS-9309-233	2 - 8 SFS-9309-234	8 - 15 SFS-9309-235	15 - 26 SFS-9309-236	26 - 35 SFS-9309-237	SFS-90
PARAMETER	UNITS						
Hd	(s.u.)	7.2	7.5	7.9	8.1	8.5	8.4
Saturation	(%)	45.1	44.6	32.6	26.8	20.2	25.4
Specific Conductivity	(mmhos/cm)	1.15	0.55	0.32	0.50	0.63	0.85
Calcium	(meq/l)	8.98	3.83	1.88	1.06	0.64	0.66
Magnesium	(meq/l)	2.12	1.19	1.36	2.86	3.61	4.26
Sodium	(meq/l)	0.10	0.10	0.21	0.66	1.78	3.29
Sodium Adsorption Ratio		0.04	90.0	0.16	0.47	1.22	2.10
Cation Exchange Capacity	(meq/100g)	40.66	39.46	28.76	29.29	14.31	20.20
Sand	(%)	58	40	53	99	72	28
₩	(%)	34	41	34	26	24	32
Clay	(%)	∞	19	13	8	4	<u> </u>
Texture		ร	1	SI	SF	S	? v:
Very Fine Sand	(%)	10.96	7	₹	23.10	3.58	6.88
Rock Fragments	(%)	\$	7	09	61	79	66
Organic Matter	(%)	6.8	3.1	1.2	1.4	0.3	0.7
Nitrate	(b/bn)	5.8	1.4	1.2	₹	⊽	₹
Ammonia	(g/gn)	3.4	1.3	₹	⊽	₹	. ₹
Calcium Carbonate Equivalent	(%)	41.7	57.3	70.8	72.7	73.6	47.7
Neutralization Potential	(t/1000t)	417	573	708	727	736	477
Acid Potential	(t/1000t)	⊽	_	-	⊽	₹	⊽
Acid-Base Potential	(V1000t)	417	572	707	727	736	477

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

7 inches thick and is underlain by yellowish brown to light gray, strongly effervescent clay loam.

Sieberell soil is very deep, well-drained and is present on stream terraces and alluvial fans. The surface layer is typically a grayish brown extremely gravelly loam about 6 inches thick. The subsoil is a yellowish brown to olive brown gravelly clay loam to cobbly loamy sand.

#### Beaverell soil

This soil is very deep, well-drained and is formed in alluvium on stream terraces and alluvial fans with 2-15 percent slopes. The surface layer is typically a dark grayish brown stony to cobbly sandy clay loam from 5-7 inches thick. The subsoil is brown cobbly sandy loam.

# 3.2.5 Poorly Drained Soils Formed in Alluvium

The following soils occur mainly on stream terraces, flood plains, alluvial fans, and are formed in alluvium. These soils are very deep, somewhat poorly to well-drained, gravelly loams, fine sandy loams, silt loams, and silty clay loams. It should be noted that some mapping units in this category are not described as associated series but rather soil subgroups (i.e. Typic Haploborolls, Fluvaquentic Haplaquolls, Cumullic Haplaquolls, Ustic Torriorthents and Typic Fluvaquents). These soil subgroups occur on narrow, nearly level, undulating or gently sloping low terraces and flood plains of Elkhorn Creek and Turnley Creek. These soils typically have a black, organic rich surface layer underlain by black to gray (gleyed), mottled, subsurface horizons of organic rich, very fine loamy sand or finer material. The water table is generally very near the surface as soils in these subgroups are mainly near streams on floodplains or wet areas.

#### Fairway-Nestley association

This association consists of mostly nearly level and gently sloping soils on floodplains and low terraces. This association is made up of 60 percent Fairway soils, 30 percent Nestley soils, and 10 percent other soils.

ANALYTICAL RESULTS FOR BOBOWIC(2) SERIES DATE SAMPLED: 9/30/93

Bw Cr	5 - 28 28 - 53	SFS-9309-299 SFS-9309-300 SFS-9309-301
'n	0 - 2	SFS-9309-299 S
HORIZON	INTERVAL (inches)	SAMPLE NUMBER

PARAMETER	UNITS			
Ha	(s.u.)	5.9	0.9	6.3
Saturation	· (%)	42.9	26.8	26.1
Specific Conductivity	(mmhos/cm)	0.30	0.28	0.30
Calcium	(meq/l)	2.38	2.34	2.01
Magnesium	(meq/l)	0.81	0.59	0.64
Sodium	(med/l)	0.16	0.21	0.23
Sodium Adsorption Ratio		0.13	0.17	0.20
Cation Exchange Capacity	(meg/100g)	41.76	33.71	30.55
Sand	. (%)	58	99	73
: #S	(%)	33	23	24
Clav	(%)	6	11	က
Texture		S	SF	Sľ
Very Fine Sand	(%)	3.30	5.22	5.78
Rock Fragments	(%)	<b>?</b>	39	45
Organic Matter	(%)	5.0	1.4	0.7
Calcium Carbonate Equivalent	(%)	1.4	1.8	3.0
Neutralization Potential	(V1000t)	14	18	30
Acid Potential	(V1000t)	₹	-	7
Acid-Base Potential	(t/1000t)	14	17	28

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

Fairway soils are very deep, somewhat poorly drained soils on floodplains with 0-2 percent slopes. The surface layer typically is dark grayish brown, slightly effervescent clay loam about 7 inches thick. It is underlain by dark grayish brown silty clay loam to silt loam.

Nestley soils are very deep, somewhat poorly drained soils on floodplains and low terraces with 0-2 percent slopes. The surface layer typically is dark grayish brown clay loam about 6 inches thick and is underlain by dark grayish brown coarse sand and clay loam.

#### 3.3 SOIL PROFILE DESCRIPTIONS

This section describes each soil series in detail. Each layer or genetic horizon in the profile is described from the surface down to bedrock or other underlying layers to a depth of 60 inches. The profile descriptions provide information on the morphology of each series and is used to evaluate the suitability of project area soils for salvage and reclamation purposes.

The soil profile descriptions are organized in alphabetical order. Series which have a "description location" were described and sampled within the Elkhorn Project area.

Series with a "type location" were described by the SCS and are included in project area mapping units but were not sampled (Figure 2).

ANALYTICAL RESULTS FOR BOBOWIC SERIES DATE SAMPLED: 9/28/93

INTERVAL (inches) SAMPLE NUMBER	-	0 - 4 SFS-9309-272	E 4 - 11 SFS-9309-273	BW 11 - 21 SFS-9309-274	21 - 53 SFS-9309-275
PARAMETER	UNITS				
Hd	(s.u.)	6.4	5.9	6.4	6.3
Saturation	(%)	37.3	31.9	26.7	
Specific Conductivity	(mmhos/cm)	0.61	0.29	0.33	0.21
Calcium	(meq/l)	4.60	1.92	2.41	
Magnesium	(meq/l)	1.55	0.68	0.72	
Sodium	(meq/l)	0.13	0.15	0.46	
Sodium Adsorption Ratio		0.07	0.13	0.37	
Cation Exchange Capacity	(meq/100g)	30.56	29.98	15.83	18.89
Sand	(%)	69	89	72	70
i dit	(%)	28	32	25	30
Clay	(%)	က	A/N	က	A/N
Texture		S	S	S	S
Very Fine Sand	(%)	4.96	4.06	3.88	2.88
Rock Fragments	(%)	<b>%</b>	<2	49	25
Organic Matter	(%)	2.9	2.2	0.0	0.5
Calcium Carbonate Equivalent	(%)	0.7	0.5	0.7	0.8
Neutralization Potential	(t/1000t)	7	5	7	80
Acid Potential	(V1000t)	₹	⊽	₹	V
Acid-Base Potential	(V1000t)	7	ß	7	· 00

TEXTURE: S = Sand; Si = Silt; L = Loam; C = Clay

#### ADEL SERIES

The Adel series consists of deep, well-drained soils that formed in alluvium or colluvium from a variety of rock sources. These soils are on fans, terraces, smooth to concave foot slopes and side slopes, and in upland swales. Slopes are 0 to 65 percent. Mean annual precipitation is about 25 inches. Mean annual temperature is about 40° F.

TAXONOMIC CLASS: Fine-loamy, mixed Pachic Cryoborolls

TYPICAL PEDON: Adel silt loam, grassland (colors are for dry soil unless otherwise noted).

- A1 -- 0 to 13 inches; dark gray (10YR 4/1) loam, black (10YR 2/1) moist; moderate medium and fine granular structure; slightly hard, very friable, slightly sticky and slightly plastic; many fine and very fine roots; many very interstitial pores; many worm casts; slightly acid (pH 6.1); gradual wavy boundary. (8 to 14 inches thick)
- A2 -- 13 to 31 inches; dark grayish brown (10YR 4/2) loam, very dark brown (10YR 2/2) moist; weak medium and fine subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; many fine and very fine roots; many very fine and fine pores; many worm casts; slightly acid (pH 6.1); diffuse wavy boundary. (8 to 20 inches thick)
- A3 -- 31 to 38 inches; grayish brown (10YR 5/2) loam, very dark grayish brown (10YR 3/2) moist; weak medium subangular blocky structure parting to moderate fine and very fine subangular blocky; slightly hard, very friable, slightly sticky and slightly plastic; common fine and very fine roots; many fine and very fine pores; neutral (pH 7.0); gradual wavy boundary. (4 to 16 inches thick)
- Bw -- 38 to 60 inches; brown (10YR 5/3) channery loam, dark brown (10YR 3/3) moist; weak medium subangular blocky structure parting to moderate very fine subangular blocky; slightly hard, friable, slightly sticky and slightly plastic; common very fine and fine roots; many very fine pores; 20 percent angular pebbles and 5 percent angular cobbles; neutral (pH 7.0);

TYPE LOCATION: Lake County, Montana; 1,050 feet west and 450 feet south of the NE corner of Section 9, T. 13N, R. 18E.

# APPENDIX A. LABORATORY ANALYTICAL RESULTS

#### BEAVERELL SERIES

The Beaverell series consists of very deep, well-drained soils that formed in alluvium that is 10 to 20 inches deep over very gravelly loamy sand or very gravelly sand. These soils are on stream terraces, outwash terraces, and alluvial fans. Slopes are 0 to 25 percent. Mean annual precipitation is about 12 inches. Mean annual air temperature is about 41° F.

**TAXONOMIC CLASS:** Loamy-skeletal over sandy or sandy-skeletal, mixed Aridic Argiborolls.

**TYPICAL PEDON:** Beaverell gravelly loam, grassland (colors are for dry soil unless otherwise noted).

- A -- 0 to 3 inches; brown (10YR 5/3) gravelly loam, dark brown (10YR 3/3) moist; weak very fine granular structure; slightly hard, very friable, slightly sticky and nonplastic; many fine and very fine roots; many fine and medium pores; 15 percent pebbles; neutral (pH 6.6); clear smooth boundary. (2 to 6 inches thick)
- Bt1 -- 3 to 9 inches; brown (10YR 5/3) very gravelly clay loam, dark brown (10YR 3/3) moist; moderate medium prismatic structure parting to moderate medium and fine blocky; hard, friable, sticky and slightly plastic; many fine and very fine roots; many fine and very fine pores; many faint clay films on faces of peds; 35 percent pebbles; neutral (pH 6.6); clear smooth boundary. (5 to 7 inches thick)
- Bt2 -- 9 to 11 inches; brown (10YR 5/3) very gravelly sandy clay loam, dark brown (10YR 3/3) moist; moderate fine blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; common fine and very fine roots; many medium and fine pores; many faint clay films on faces of peds; 50 percent pebbles; lime coatings on underside of larger pebbles; neutral (pH 6.8); clear wavy boundary. (3 to 12 inches thick)
- 2Bk1 -- 11 to 17 inches; brown (10YR 5/3) very gravelly loamy sand, dark brown (10YR 4/3) moist; single grain; loose, very friable, nonsticky and nonplastic; common very fine roots; 60 percent pebbles; continuous distinct lime coatings on underside of smaller pebbles and lime casts on underside of larger pebbles; disseminated lime; strongly effervescent; mildly alkaline (pH 7.8); gradual wavy boundary. (4 to 25 inches thick)
- 2Bk2 -- 17 to 60 inches; brown (10YR 5/3) very gravelly sand, dark brown (10YR 4/3) moist; single grain; loose, soft and very friable; 60 percent pebbles; common faint lime coating on underside of pebbles; disseminated lime; strongly effervescent; mildly alkaline (pH 7.8).

TYPE LOCATION: Blaine County, Montana; 30 feet north and 1,000 feet west of the SE corner of Sec. 15, T. 33N., R. 23 E.

* *		
•		

#### **BOBOWIC SERIES**

The Bobowic series consists of moderately deep, well-drained soils that formed in colluvium or residuum derived from granite bedrock. These soils are on dissected bedrock floored plains, hills, and mountains. Slopes are 15 to 70 percent. Mean annual precipitation is about 18 inches, and mean annual air temperature is about 38°F.

TAXONOMIC CLASS: Coarse-loamy, mixed Typic Cryochrepts

**TYPICAL PEDON:** Bobowic gravelly loam, very bouldery, forested, colors are for dry soil unless otherwise noted.

- Oi -- 1 to 0 inches; partially decomposed needles, twigs and leaves. Can range from 1/2 to 3 inches thick.
- A -- 0 to 4 inches; very dark gray (10YR 3/1) gravelly loam, (10YR 2/1) moist; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine and few fine roots; many very fine and few medium pores; 20 percent pebbles; slightly acid (pH 6.4); clear smooth boundary. Can range from 0 to 5 inches thick.
- E -- 4 to 11 inches; very dark gray (10YR 3/1) gravelly coarse sandy loam, (10YR 2/1) moist; moderate coarse platy structure parting to weak fine angular blocky; soft, very friable, slightly sticky and nonplastic; many very fine and few fine and medium roots; many very fine and few fine interstitial and tubular pores; 25 percent pebbles; moderately acid (pH 5.9); clear wavy boundary. Can range from 2 to 8 inches thick.
- Bw -- 11 to 21 inches; dark grayish brown (10YR 4/2) gravelly coarse sandy loam, very dark brown (10YR 2/2) moist; fine subangular blocky structure; slightly hard, friable, slightly sticky and nonplastic; many very fine and few fine and medium roots; many very fine and few fine interstitial and tubular pores; 15 percent pebbles; 10 percent cobbles; slightly acid (pH 6.4); clear wavy boundary. Can range from 9 to 25 inches thick.
- Cr -- 21 to 53 inches; grayish brown (10YR 5/2) decomposed granite bedrock (grus) that crushes to gravelly loamy coarse sand; very dark grayish brown (10YR 3/2) moist massive; 5 percent cobbles; slightly acid (pH 6.4); gradual wavy boundary.
  - R -- 53 inches; hard granite bedrock.

**DESCRIPTION LOCATION**: Jefferson County, Montana; 2,500 feet south and 1,700 feet west of the NE corner of Section 14, T. 6N, R. 3W.

#### 5.0 REFERENCES

- Coppinger, K.D., P.R. Ogle, and D. McGirr. 1993. Using Organic Matter to Select Optimum Topsoil Salvage Depths: A Strategy to Improve Topsoil Quality and Reduce Salvage Depths. Planning, Rehabilitation and Treatment of Disturbed Lands. Billings Symposium Proceedings. pp. 253-261.
- Everson, and others. 1989. Geology and Gold Skarn Deposits of the Elkhorn District, Jefferson County, Montana. Gold Fields, 49 pp.
- Hydrometrics, 1993. Baseline Soil Inventory Work Plan for Santa Fe Pacific Gold Corporation, Elkhorn Project, Jefferson County, Montana. September.
- Klepper and others. 1957. Geology of the Southern Elkhorn Mountains Jefferson and Broadwater Counties, MT. Geological Survey Professional Paper 292. 82 pp.
- Montana Department of State Lands. 1983. Proposed Soil and Overburden Guidelines.
- Schroeder, P.R., R.L. Peyton, B.M. McEnroe and J.W. Sjostrum, 1988. The Hydrologic Evaluation of Landfill Performance (HELP) Model: Volume III. User's Guide for Version 2, Internal Working Document EL-92-1, Report 1, USAE Waterways Experiment Station, Vicksburg, Mississippi. 87 pp.
- Soil Survey Staff, 1988. Keys to Soil Taxonomy: U.S. Dept. Agri. SMSS Tech. Monograph No. 6. 288 pp.
- Soil Survey Staff, 1984. Soil Survey Manual: U.S. Dept. Agri. Soil Cons. Service. 430-V-SSM, May 1984.
- Soil Survey Staff, 1983. National Soils Handbook: U.S. Dept. Soil Cons. Service. 430-VI-NSH, July 1983.
- U.S.D.A., U.S.F.S., 1980. Landtype Inventory Deerlodge National Forest, Butte, Montana.

#### **BOBOWIC (2) SERIES**

The Bobowic (2) series consists of moderately deep, well-drained soils that formed in colluvium or residuum derived from granite bedrock. These soils are on dissected bedrock floored plains, hills, and mountains. Slopes are 15 to 70 percent. Mean annual precipitation is about 18 inches, and mean annual air temperature is about 38°F.

TAXONOMIC CLASS: Coarse-loamy, mixed Typic Cryochrepts

**TYPICAL PEDON:** Bobowic (2) gravelly loam, very bouldery, forested, colors are for dry soil unless otherwise noted.

Oi - 1/2 to 0 inches; partially decomposed needles, twigs and leaves. Can range from 1/2 to 3 inches thick.

E -- 0 to 5 inches; very dark grayish brown (10YR 3/2) gravelly coarse sandy loam, (10YR 2/1) moist; moderate coarse platy structure parting to weak fine angular blocky; soft, very friable, slightly sticky and nonplastic; many very fine and few fine and medium roots; many very fine and few fine interstitial and tubular pores; 25 percent pebbles; moderately acid (pH 5.9); clear wavy boundary. Can range from 2 to 8 inches thick.

Bw -- 5 to 28 inches; dark grayish brown (10YR 4/2) gravelly coarse sandy loam, very dark brown (10YR 2/2) moist; fine subangular blocky structure; slightly hard, friable, slightly sticky and nonplastic; many very fine and few fine and medium roots; many very fine and few fine interstitial and tubular pores; 15 percent pebbles; 10 percent cobbles; moderately acid (pH 6.0); clear wavy boundary. Can range from 9 to 25 inches thick.

Cr -- 21 to 34 inches; dark grayish brown (10YR 4/2) decomposed granite bedrock (grus) that crushes to gravelly loamy coarse sand; very dark brown (10YR 2/2) moist; slightly acid (pH 6.3); gradual wavy boundary.

R -- 34+ inches; hard granite bedrock.

**DESCRIPTION LOCATION**: Jefferson County, Montana; 1,900 feet north and 700 feet east of the SW corner of Section 11, T. 6N, R. 3W.

SFPG-P\4G-SFP.WB1\KL

CHEMICAL, PHYSICAL AND HYDROLOGIC CHARACTERISTICS OF POTENTIAL LAD SOILS SANTA FE PACIFIC GOLD CORPORATION, ELKHORN MINE PROJECT, JEFFERSON COUNTY, MONTANA TABLE 4-3

21-Sep-94

SERIES NAME	SLOPE RANGE (%)	Ave. CEC (meq/100g)	Ave. Clay (%)	Ave. OM (%)	Ave. CaCO3 Equiv. (%)	Ave. NO3 (ppm)	Ave. NH4 (ppm)	Est. Porosity (% by vol.)	Est. Field Capacity (% by vol.)	Est. Wilting Point (% by vol.)	Est. Saturated K
BROWNSHUT	09 - 0	25.41	10.3	2.3	9.09	1.7	1.1	45.5	16.5	9.0	0.00066
HANSON	0 - 35	38.80	12.3	3.2	34.7	1.8	2.5	46.8	22.4	10.5	0.00050
HILGER	8 - 25	50.71	21.5	1.2	3.2	1.2	2.7	44.9	23.3	12.1	0.00039
LIBEG	2 - 45	29.88	9.6	1.0	1.7	9.0	1.7	46.3	23.2	11.6	0.00037
MARTINSDALE	0 - 35	36.86	16.1	2.0	10.3	0.8	4.8	46.0	23.1	11.7	0.00043
SILAS	8 - 0	25.93	10.0	1.7	0.3	0.7	1.5	45.3	19.0	8.5	0.00072
WINDHAM	0 - 85	35.05	20.0	1.6	25.0	0.7	1.3	44.2	21.4	10.6	0.00048

# **BROWNSHUT SERIES**

The Brownshut series consists of very deep, well-drained soils that formed in alluvium and Tertiary fill material. These soils are on terraces, alluvial fans and hills. Slopes are 0 to 60 percent. Mean annual precipitation is about 12 inches. Mean annual air temperature is about 42° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed frigid Calciorthidic Ustochrepts

**TYPICAL PEDON:** Brownshut gravelly loam, in rangeland (colors are for dry soil unless otherwise noted).

A -- 0 to 2 inches; grayish brown (10YR 5/2) gravelly loam, dark brown (10YR 3/3) moist; weak medium granular structure; slightly hard, friable, slightly sticky and slightly plastic; common fine and very fine roots; many fine and very fine pores; 15 percent pebbles; slightly effervescent; neutral (pH 7.2); clear wavy boundary. Can range from 2 to 6 inches thick.

Bk1 -- 2 to 8 inches; pale brown (10YR 6/3) gravelly loam, brown (10YR 5/3) moist; moderate medium subangular blocky structure; hard, friable, slightly sticky and slightly plastic; common fine and very fine roots; many fine and very fine pores; 25 percent pebbles; disseminated lime with few fine soft masses and threads of lime, common faint lime coatings on undersides of pebbles; strongly effervescent; mildly alkaline (pH 7.5); clear wavy boundary. Can range from 5 to 13 inches thick.

Bk2 -- 8 to 15 inches; very pale brown (10YR 7/3) gravelly loam, pale brown (10YR 6/3) moist; weak coarse prismatic structure parting to moderate medium subangular blocky; hard, friable, sticky and slightly plastic; few fine and very fine roots; common fine and very fine pores; 30 percent pebbles; disseminated lime with common fine soft masses and threads of lime, common distinct lime coatings on pebbles; violently effervescent; mildly alkaline (pH 7.9); clear wavy boundary. Can range from 7 to 22 inches thick.

Bk3 -- 15 to 26 inches; pale brown (10YR 6/3) very gravelly sandy loam, brown (10YR 5/3) moist; weak coarse prismatic structure; slightly hard, very friable, slightly sticky and nonplastic; few very fine roots; common very fine pores; 45 percent pebbles; disseminated lime with common fine masses and threads of lime, common distinct lime coatings on underside of pebbles; violently effervescent; moderately alkaline (pH 8.1); clear wavy boundary. Can range from 10 to 15 inches thick.

Bk4 -- 26 to 35 inches; pale brown (10YR 6/3) very gravelly sandy loam, yellowish brown (10YR 5/4) moist; weak coarse prismatic structure; slightly hard, very friable, nonsticky and nonplastic; 45 percent pebbles; disseminated lime with few faint lime coatings on undersides of pebbles; violently effervescent; strongly alkaline (pH 8.5); gradual wavy boundary. Can range from 10 to 15 inches thick.

Hydrologic parameters considered for LAD soils include porosity, field capacity, wilting point and saturated hydraulic conductivity. These parameters were estimated for each potential LAD soils using Hydrologic Evaluation of Landfill Performance (HELP) model documentation (Schroeder 1988). Estimates of these properties are based on soil texture relationships. They are used to assess the water holding capacity, permeability and hydrologic conductivity characteristics of potential LAD soils and to evaluate application rates and surface area requirements for LAD systems.

The chemical, physical and hydrologic characteristics of LAD soils, averaged over genetic horizons for 5-foot deep profiles, are summarized in Table 4-3.

# BROWNSHUT SERIES (Continued)

BC -- 35 to 60 inches; brown (10YR 5/3) very gravelly loamy sand, dark brown (10YR 3/3) moist; single grain; loose, nonsticky and nonplastic; 40 percent pebbles; few faint lime coatings on undersides of pebbles; strongly effervescent; moderately alkaline (pH 8.4).

**DESCRIPTION LOCATION**: Jefferson County, Montana; 1,200 feet west and 1,800 feet south of the NE corner of Section 10, T. 5N, R. 3W.

inches to optimize soil quality. The minimum depth of salvage was six inches which is the minimum amount of soil that equipment can remove with any degree of accuracy and the depth at which first lift quality was optimal for certain soils. From soil mapping unit composition information in Table 3-3, the area and extent of each series was calculated. The area and extent of each series is also included in Table 4-2. Rock outcrop and rock rubbleland, which account for approximately 1,110 acres or 12 percent of the total project area (8,957 acres) were not considered for salvage.

# 4.3 SUITABILITY OF SOILS FOR LAND APPLICATION DISPOSAL OF EXCESS PROJECT WATER

One of the objectives of the Elkhorn Mine Project soil inventory is to screen potential soils and sites suitable for land application disposal (LAD) of pit waters or process waters. Criteria used to identify potential LAD soils during field investigations included extent (surface area), soil depth, slope, texture, proximity to surface water and depth to groundwater. Soil series names identified include Brownshut, Hanson, Hilger, Libeg, Martinsdale, Silas and Windham. In the Elkhorn Project area, these soils are generally present on terraces, alluvial fans, mountain valleys, terraces and glacial till. They are suitable for LAD because they are deep, well-drained and usually occur on relatively level slopes.

Samples collected from soils identified in the field as having LAD potential were analyzed for nitrate and ammonium in addition to the other parameters specified in Table 2-1. These parameters were analyzed to establish native soil nitrogen concentrations present in potential LAD soil profiles. This information may be required to evaluate nitrate and ammonium assimilation capacities and the potential for leachate once pit water quantities and nitrogen inputs are known. Soil chemical and physical parameters used to further characterize LAD soils include cation exchange capacity, clay content, organic matter and calcium carbonate equivalent (Appendix A). These parameters provide an indication of the capacity of the soil profile to attenuate cations such as ammonium or metals that may be present in pit waters or process waters.

#### CASEYPEAK SERIES

The Caseypeak series consists of shallow, well-drained soils that formed in residuum derived from granite and other coarse-grained igneous rocks. These soils are on mountains and hills. Slopes are 25 to 60 percent. Mean annual precipitation is about 18 inches. Mean annual temperature is about 38° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Lithic Cryocrepts

**TYPICAL PEDON:** Caseypeak gravelly coarse sandy loam, bouldery, forested (colors are for dry soil unless otherwise noted).

Oi -- 1-1/2 to 0 inches; partially decomposed needles, twigs and leaves. Can range from 1/2 to 3 inches thick.

E -- 0 to 4 inches; light brownish gray (10YR 6/2) gravelly coarse sandy loam, brown (10YR 5/3) moist; moderate medium granular structure; slightly hard, very friable, nonsticky and nonplastic; many very fine and fine and common medium roots; many very fine and fine and few medium pores; 20 percent pebbles; strongly acid (pH 5.2); clear wavy boundary. Can range from 4 to 6 inches thick.

Bw -- 4 to 9 inches; brown (10YR 5/3) very gravelly coarse sandy loam, brown (10YR 4/3) moist; moderate medium subangular blocky structure; slightly hard, very friable, nonsticky and nonplastic; many very fine and fine and common medium roots; many very fine and few fine tubular and interstitial pores; 40 percent pebbles; very strongly acid (pH 5.0); gradual wavy boundary. Can range from 5 to 8 inches thick.

BC -- 9 to 12 inches; pale brown (10YR 6/3) very gravelly coarse sandy loam, brown (10YR 5/3) moist; weak medium subangular blocky structure; soft, very friable, nonsticky and nonplastic; many very fine, common fine and few medium roots; many very fine and few fine tubular and interstitial pores; 40 percent pebbles; moderately acid (pH 5.9); clear wavy boundary. Can range from 4 to 6 inches thick.

Cr -- 12 to 17 inches; light yellowish brown (2.5Y 6/4) decomposed granite bedrock (grus) that crushes to very gravelly loamy coarse sand; slightly acid (pH 6.5).

R -- 17+ inches; hard granite bedrock.

**DESCRIPTION LOCATION:** Jefferson County, Montana; 2,200 feet north and 550 feet east of the SW corner of Section 15, T. 6N, R. 3W.

SOIL SALVAGE DEPTHS AND RECLAMATION CONSTRAINTS SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA

TABLE 4-2 (continued)

		AVERAGE DE	AVERAGE DEPTH OF SALVAGE			ļ	
INTERPRETIVE	SERIES	First Lift	Second Lift	Total	DECLAMATION CONSTRAINTS	AREA (acres)	(percent)
GROUP	NAME	(inches)	(inches)	(incnes)		1	(
			9	č	Excessive coarse fragments and sand content for second lift if salavaged below 24 inches.	64.7	0.72
Graceland Soils	SHOOK	12	72	<b>5</b> 7	Excessive data of regiments for second lift is alayaded below 18 inches.	13.5	0.15
Classian Comp	NHH	9	12	9	Excessive coarse tragments to second min council and the property of inches.	5.5	90.0
	CIEBEREII	9	12	18	Excessive coarse fragments to section in it is an average above 36 inch depth	32.4	0.36
	SILDCINELE	12	24	36	No limitations other than second int quality (CM, CLC) is positive account.	32.4	0.36
		! c	c	0	This soil is hydric and direct impacts would probably be avoided.	8 700	2.29
	SLOCUM	> (		ď	Lithic soil with excessive coarse fragments below a depth of 6 inches.	204.0	2.7
	TOLBERT	g.	<b>&gt;</b> (	, (	This soil is in drainage bottoms and intermingled with hydric soils.	42.5	0.47
	TYPIC HAPLOBOROLLS	0	•	>	and interest of the state of th	6.5	0.07
9	WADNEY	12	24	36	Deep soli of illitied extert, no illitiations.	356.8	3.98
0	VARINET	! œ	12	18	Excessive coarse fragments if second lift is salvaged below to incress.		
	WINDHAM	•				0	7.7 0
			(	č	Grant layer occurs at a depth of 21 inches and may be excessively sandy.	0.00	: ! : i
Forest Soils	BOBOWIC	24	0	<b>5</b> 7 !	Course layer occurred to depth of 12 to 14 inches and may be excessively sandy.	0.799	7.45
	CASEYPEAK	12	0	12	Grus layer occurs at a capital in a change a death of 24 inches.	279.7	3.12
	DOSE II CIII	12	0	12	Excessive coarse fragments in single in savaged before a coperation of the conduction of the conductio	79.9	0.89
		Ę.	0	36	Grus layer occurs at a depth of 32 to 40 inches and may be excessively sainty.	· ·	0.01
	FRANCOIN	9 6	c	18	Excessive coarse fragments if single lift salvaged below a behin of 10 money.	4727	20. 7
	HELMVILLE	<u>o</u> (	•	<u>.</u>	I ithic soil with excessive coarse fragments below a depth of 6 inches.	1.0.1	67.0
	REDFERN	9	•	> 7	Expensive coarse framments if single lift salvaged below a depth of 24 inches.	543.2	9.00
	TEDECREEK	54	0	57	Excessive coase against a second second and a second second as a second	954.8	10.66
		70	0	24	Excessive coarse fragments if single lift salvayed below a deprine the coarse fragments if single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments in single lift salvayed below a deprine the coarse fragments and the coarse fragme	360.7	4 03
	IIGERON	្លែ		9	Lithic soil with excessive coarse fragments below a depth of a miches.	2	20.
	TROPAL	<b>-</b> !		ţ	tithic soil hedrock encountered at an average depth of 12 inches.	32.3	3 3
	WARNEKE	12	>	7 !	remove framents it simila lift salvaned helow a depth of 12 inches.	200.6	2.24
	WHITECOW	12	0	12	EXCESSIVE CORISE HAGITIETIES II SHIYIG III SON OBOG BOOM I COLLEGE		

90

## CASEYPEAK (2) SERIES

The Caseypeak (2) series consists of shallow, well-drained soils that formed in residuum derived from granite and other coarse-grained igneous rocks. These soils are on mountains and hills. Slopes are 25 to 60 percent. Mean annual precipitation is about 18 inches. Mean annual temperature is about 38° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Lithic Cryocrepts

**TYPICAL PEDON:** Caseypeak gravelly coarse sandy loam, bouldery, forested (colors are for dry soil unless otherwise noted).

Oi -- 2 to 0 inches; partially decomposed needles, twigs and leaves. Can range from 1/2 to 3 inches thick.

E -- 0 to 5 inches; very dark grayish brown (10YR 3/2) gravelly coarse sandy loam, black (10YR 2/1) moist; moderate medium granular structure; slightly hard, very friable, nonsticky and nonplastic; many very fine and fine and common medium roots; many very fine and fine and few medium pores; 20 percent pebbles; neutral (pH 7.0); clear wavy boundary. Can range from 4 to 6 inches thick.

Bw -- 5 to 14 inches; dark grayish brown (10YR 4/2) very gravelly coarse sandy loam, very dark grayish brown (10YR 3/2) moist; moderate medium subangular blocky structure; slightly hard, very friable, nonsticky and nonplastic; many very fine and fine and common medium roots; many very fine and few fine tubular and interstitial pores; 40 percent pebbles; mildly alkaline (pH 7.7); gradual wavy boundary. Can range from 5 to 8 inches thick.

Cr -- 14 to 18 inches; brown (10YR 4/3) decomposed diorite bedrock (grus) that cruses to very gravelly loamy coarse sand; mildly alkaline (pH 7.7).

R -- 18+ inches; hard granite bedrock.

**DESCRIPTION LOCATION**: Jefferson County, Montana; 1,500 feet south and 600 feet east of the NW corner of Section 11, T. 6N, R. 3W.

TABLE 4-2

SOIL SALVAGE DEPTHS AND RECLAMATION CONSTRAINTS SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA

		AVERAGE U	AVERAGE DEPTH OF SALVAGE				
INTERPRETIVE GROUP	SERIES NAME	First Lift (inches)	Second Lift (inches)	Total (inches)	RECLAMATION CONSTRAINTS	AREA	EXTENT
Grassland Soils	ADEL	12	24	36	Deep soil with no limitations except location in drainage bottoms.	48.1	Parenty Parenty
	BROWNSHIT	ω ;	တ (	12	Excessive coarse fragments for second lift if salvaged below 12 inches.	5.0	0.04
	CLASOIL	ž Ç	2 2	24	Excessive coarse fragments for second lift if salvaged below 24 inches.	127.3	1.42
	CRAGO		÷ +	လို ဗို	Ueep soil of limited extent, no limitations.	5.5	90.0
	CUMULIC HAPLAQUOLLS	) C	<u>v</u> c	<u>°</u> c	Excessive coarse fragments for second lift if salavaged below 18 inches.	24.4	0.27
	FAIRWAY	, 2	, Ç	> ?	This soil is hydric and direct impacts would probably be avoided.	63.7	0.71
	FLUVACUENTIC HAPI ACITOR IS	! c	<u>v</u> c	÷ 0	Groundwater occurs at 30 inches, this soil is of limited extent.	2.1	0.02
	HANSON	> <del>C</del>	> 0	<b>&gt;</b>	I his soil is intermingled with hydric soils in drainage bottoms.	84.9	0.95
	HILGER	<u>1</u> 9	o. (c	ž t	Excessive coarse fragments below a depth of 6 inches prohibit salvage of second lift.	119.5	1.33
39	JUDELL	2 2	5 0	7 2	Excessive coarse fragments for second lift if salvaged below 12 inches.	187.7	2.10
	LAP		; u	S <del>(</del>	To imitations other than second lift quality (structure, OM) is better above 36 inch depth.	12.3	0.14
	LIBEG	. 2	2 2	7 96	Excessive coarse fragments for second lift if salvaged below 12 inches.	255.8	2.86
	MAIDEN	! <b>u</b>	; c	3 4	ry minimations other than second lift quality (structure, OM, CEC) is better above 36 inch dep	286.9	3.20
	MARTINSDALE	. 2	> 5	ຸ	excessive coarse iragments below a depth of 12 inches prohibit salvage of second lift.	348.3	3.89
	NESTLEY	<u>;</u>	£ ¢	8 8	Excessive sodium (SAK 23) and elevated pH (8.6) below a depth of 36 inches	245.2	2.74
	NEMAN	י ני	<u>v</u> c	47 (	Excessive sand content for second lift if salvaged below 12 inches.	Ξ:	0.01
	PENSORE	, <b>c</b>	, c	D (	Excessive coarse fragments below a depth of 6 inches prohibit salvage of second lift.	436.7	4.88
	SAWBUCK	, 2	2 2	ຸ	Litting soil with excessive coarse fragments below a depth of 6 inches prohibit second lift.	1.0	0.01
	SHAWMUT	ی ا	; ;	20	reep soil of imited extent, no limitations.	11.0	0.12
		•	7	<u>o</u>	excessive coarse tragments for second lift if salavaged below 18 inches.	863.2	9 64

## **CLASOIL SERIES**

The Clasoil series consists of very deep, well-drained soils that formed in alluvium derived from granitic and other coarse-grained igneous rocks. These soils are on alluvial fans and terraces. Slopes are 2 to 35 percent. Mean annual precipitation is about 17 inches. Mean annual air temperature is about 40° F.

TAXONOMIC CLASS: Fine-loamy, mixed Typic Argiborolls

TYPICAL PEDON: Clasoil gravelly loam, bouldery in rangeland (colors are for dry soil unless otherwise noted).

- A1 -- 0 to 5 inches; very dark grayish brown (10YR 3/2) gravelly loam, black (10YR 2/1) moist; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine and few fine and medium roots; many very fine and fine interstitial pores; 5 percent cobbles, 10 percent pebbles; slightly acid (pH 6.2); clear smooth boundary.
- A2 -- 5 to 13 inches; dark grayish brown (10YR 4/2) gravelly loam, very dark gray (10YR 3/1) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, sticky and slightly plastic; many very fine and few fine and medium roots; many very fine and common fine pores; 5 percent cobbles, 25 percent pebbles; slightly acid (pH 6.2); clear smooth boundary. (Combined thickness of A horizons is 7 to 15 inches)
- Bt1 -- 13 to 24 inches; light yellowish brown (10YR 6/4) gravelly sandy clay loam, yellowish brown (10YR 5/4) moist; moderate medium prismatic structure parting to moderate medium subangular blocky; hard, friable, sticky and plastic; common very fine and few fine and medium roots; common very fine and fine pores; common thin clay films on faces of peds and bridging between sand grains; 5 percent cobbles; 15 percent pebbles; neutral (pH 6.7); clear smooth boundary.
- Bt2 -- 24 to 34 inches; light yellowish brown (2.5Y 6/4) cobbly sandy clay loam, yellowish brown (10YR 5/4) moist; moderate medium subangular blocky structure; slightly hard, friable, sticky and slightly plastic; common very fine and few fine and medium roots; common very fine and few fine pores; common thin clay films on faces of peds and bridging between sand grains; 20 percent cobbles; 10 percent pebbles; neutral (pH 6.7); clear smooth boundary. (Combined thickness of Bt horizons is 8 to 24 inches).
- BC -- 34 to 60 inches; light yellowish brown (10YR 6/4) very cobbly loam, dark yellowish brown (10YR 4/4) moist; weak medium subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; few very fine roots; 25 percent cobbles; 15 percent pebbles; neutral (pH 6.6).

TYPE LOCATION: Jefferson County, Montana; 500 feet north and 1,000 feet east of the SW corner of Sec. 13, T. 9N., R. 2 W.

## 4.1.4 Hydrologic Features

Hydrologic features are also used to assess the suitability of project area soils for reclamation or other purposes. Available water capacity (AWC) for example, is a measure (inches of water per foot of soil) of the capacity of the soil to store and release plant available water. AWC and drainage class are also important factors used to evaluate the suitability of soils for waste water disposal. The suitability of soils for Land Application Disposal (LAD) will be addressed in greater detail under Section 4.2 of this report. The Hydrologic Group relates soil texture and surface conditions (vegetative cover) and groups soils according to runoff potential, and is used in equations to calculate runoff. Hydrologic groups are used in the design of surface water control structures at mining facilities. Soils identified as hydric or closely associated with hydric soils in the project area will most likely be avoided and protected from mining impacts. The sensitive nature of hydric soil sites, combined with significant site operational constraints, would preclude consideration for disturbance. Therefore, no salvage or salvage depth considerations are recommended for these soils.

## 4.1.5 Slope

Although slope does not necessarily limit the quality of soils for a specific use, it may limit the salvageability of soils from an operational standpoint. The DSL suggests that soils on slopes greater than 50 percent may be unsuitable for salvage. For the baseline soils investigation report, slope is not specifically considered a limiting factor. Once mine plans identify specific areas of disturbance and the types of equipment that will be available for soil salvage operations, the effect of slope on soil salvage can be more appropriately evaluated.

# 4.2 RECOMMENDED SOIL SALVAGE DEPTHS

Utilizing the criteria, factors and guidelines discussed in the previous sections, the depth of soil salvage, for each soil series in the Elkhorn Project area was determined. In Table 4-2, project area soils are organized according to grassland or forest land interpretation groups and the depth of salvage specified for each lift (first, second or single). Following salvage depth recommendations is a brief description of the factor or factors (reclamation constraints) that limited the depth of salvage. The total depth of salvage for any given soil was limited to 36

#### CRAGO SERIES

The Crago series consists of very deep, well-drained soils that formed in alluvium or colluvium derived mainly from limestone or basal conglomerate. These soils are on alluvial fans, stream terraces, and hills. Slopes are 0 to 75 percent. Mean annual precipitation is about 12 inches. Mean annual temperature is about 43° F.

TAXONOMIC CLASS: Loamy-skeletal, carbonatic Borollic Calciorthids

**TYPICAL PEDON:** Crago gravelly loam, in grassland (colors are for dry soil unless otherwise noted).

A -- 0 to 5 inches; grayish brown (10YR 5/2) gravelly heavy loam, dark grayish brown (10YR 4/2) moist; moderate fine and medium granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine roots; many fine pores; 20 percent pebbles; slightly effervescent; moderately alkaline (pH 8.0); clear boundary. (2 to 5 inches thick)

Bk1 -- 4 to 9 inches; light brownish gray (2.5Y 6/2) gravelly heavy loam, dark grayish brown (2.5Y 4/2) moist; weak medium subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; common very fine roots; few fine pores; 25 percent pebbles; continuous prominent lime crusts on undersides of pebbles; disseminated lime in soil matrix; violently effervescent; moderately alkaline (pH 8.4); clear wavy boundary. (2 to 6 inches thick)

Bk2 -- 9 to 14 inches; white (2.5Y 8/2) gravelly clay loam, light yellowish brown (2.5Y 6/4) moist; weak medium subangular blocky structure; hard, very friable, slightly sticky and slightly plastic; few fine roots; few fine pores; 35 percent pebbles; disseminated lime in soil matrix; many fine masses of lime; continuous prominent lime crusts on underside of pebbles; violently effervescent; moderately alkaline (pH 8.4); diffuse boundary. (0 to 6 inches thick)

Bk3 -- 14 to 26 inches; white (2.5Y 8/2) extremely gravelly clay loam, light yellowish brown (2.5Y 6/4) moist; massive; hard, very friable, slightly sticky and slightly plastic; few roots; 5 percent cobbles, 55 percent pebbles; disseminated lime in soil matrix; many fine masses of lime; continuous prominent lime crusts on pebbles with some lime cementation between some pebbles; violently effervescent; moderately alkaline (pH 8.4); diffuse wavy boundary. (10 to 16 inches thick)

Bk4 -- 26 to 50 inches; pale yellow (2.5Y 7/4) extremely gravelly loam, light olive brown (2.5Y 5/4) moist; massive; slightly hard, very friable, slightly sticky and nonplastic; few fine roots; about 65 percent pebbles; disseminated lime in soil matrix; continuous distinct lime crusts on pebbles; some lime cementation between individual pebbles; violently effervescent; moderately alkaline (pH 8.4); diffuse boundary. (20 to 30 inches thick)

There are no salvage limitations due to soil pH and many of the soils in the project area contain an abundance of carbonates. The acid base account for Elkhorn Project soils suitable for salvage ranges from 7 to 732 tons of calcium carbonate per 1,000 tons of soil. This is desirable from a reclamation stand point as these soils will provide suitable cover for potentially acid forming waste rock materials that may be produced during mining operations.

Other chemical, physical and morphological factors considered when determining the depth of salvage and quality of soil include soil structure, texture, and cation exchange capacity. If coarse fragments or depth to bedrock did not limit the depth of salvage, particularly for the deeper non-skeletal soils, structure and cation exchange capacity were considered. Subsoil materials with structure have better reclamation qualities than subsoil materials with massive structure because they are less susceptible to compaction and erosion. Cation exchange capacity tends to decrease with depth in project area soils and is a quality criterion (soil fertility) for the suitability of soil materials used as a plant growth medium. In soils derived from diorite or quartz monzonite, excessive sand was sometimes encountered in the Cr horizon overlying bedrock and this limited the depth of salvage.

#### 4.1.3 Soil Capability and Erosion

Capability classes indicate the suitability of the soil for dryland or irrigated crop production, and identify certain limitations to productivity such as slope and erodibility (Table 4-1). Erosion factors (Table 4-1) include the soil erodibility factor (K), soil loss tolerance (T factor), and the wind erodibility group (WEG). The K factor is a measure of the susceptibility of the soil to particle detachment and transport by rainfall. The T factor is the maximum rate of annual soil erosion (measured in tons per acre) that will permit crop productivity to be economically sustained. The K and T factors are used in the Universal Soil Loss Equation (USLE) to predict soil losses. The WEG is a collection of soils with similar properties effecting resistance to wind erosion and the wind erodibility index (I) provides an estimate of the potential loss of soil by wind (measured in tons per acre per year). Erosion factors are used to identify potential limitations or special management considerations for soils that may be utilized for reclamation. Erosion factors are also used in the design and evaluation of surface water control structures at mine facilities.

# **CRAGO SERIES (Continued)**

2C -- 50 to 60 inches; pale yellow (2.5Y 7/4) extremely gravelly loamy sand, light olive brown (2.5Y 5/4) moist; massive; hard, very friable, nonsticky and nonplastic; 60 to 70 percent pebbles; disseminated lime; strongly effervescent; moderately alkaline (pH 8.4);

**TYPE LOCATION**: Musselshell County, Montana; 100 feet north and 1,000 feet west of the SW corner of Section 12, T. 9N, R. 25E.

# 4.1.1 Interpretive Groups

Interpretive groups identify the range site or habitat type for each soil. For the Elkhorn Project soil inventory, range site and habitat type are used to determine which soils will be evaluated for two lift versus single lift salvage. In Table 4-1, a simplification of SCS range site and habitat type interpretive data identify grassland soils versus forest soils.

The reclamation of rangeland or grassland will be more successful if grassland soils are salvaged in two lifts. This concentrates organic matter, microorganisms and seeds and reduces rock fragments in the topsoil, conditions more conducive to the establishment of grasses. By contrast, coniferous tree species generally favor a skeletal, well-drained soil and do not tolerate competition from grasses during establishment. Therefore a single lift salvage is more desirable for the forest soils.

# 4.1.2 Soil Chemical, Physical and Morphological Factors

Skeletal and lithic soils occur extensively throughout the Elkhorn Project area. The coarse fragment content of soils is a primary limiting factor in the depth of soil salvage. Coarse fragment content estimates made from profile descriptions were considered more reliable than laboratory measurements because it was often difficult to obtain a representative sample size from genetic horizons. A coarse fragment content of 50 percent by volume or 66 percent by weight (Table 2-2) were limiting criteria used to determine appropriate depths of salvage for two lift and single lift scenarios. Rock outcrop and rock rubbleland, which are a significant component of soils mapped in the project area are not considered for salvage or reclamation purposes.

Organic matter (OM) content was the primary parameter used to determine the optimal depth to salvage the first lift for grassland soils. Organic matter is a recognized soil quality criterion (Coppinger et al. 1993) used to evaluate the optimal salvage depth for topsoil. For Elkhorn Project soils, genetic horizons with an OM content less than 1 to 1.5 percent were not included in the first lift.

#### DRYADINE SERIES

The Dryadine series consists of moderately deep, well-drained soils that formed in residuum derived from limestone. These soils are on mountaintops. Slopes are 2 to 25 percent. Mean annual precipitation is about 35 inches, and mean annual air temperature is about 36°F.

TAXONOMIC CLASS: Loamy-skeletal, carbonatic Typic Cryochrepts

**TYPICAL PEDON:** Dryadine flaggy silt loam, forested, colors are for dry soil unless otherwise noted.

Oi -- 1 to 0 inches; pine needles, twigs and cones.

A -- 0 to 6 inches; very dark gray (10YR 3/1) flaggy silt loam (10YR 2/1) moist; moderate very fine granular structure; soft, very friable, slightly sticky and plastic; many fine and very fine roots and common medium and coarse roots; 15 percent angular cobbles and 10 percent flat angular pebbles; mildly alkaline (pH 7.5); abrupt wavy boundary. Can range from 2 to 5 inches thick.

Bw -- 6 to 16 inches; dark gray (10YR 4/1) extremely flaggy silt loam, black (10YR 2/1) moist; moderate very fine subangular blocky structure parting to moderate very fine granular; soft, very friable, slightly sticky and slightly plastic; many coarse, medium, fine, and very fine roots; 35 percent flat angular pebbles and 30 percent angular cobbles; strongly effervescent; mildly alkaline (pH 7.6); gradual wavy boundary. Can range from 3 to 10 inches thick.

Bk -- 16 to 29 inches; grayish brown (10YR 5/2) extremely flaggy silt loam, dark grayish brown (10YR 4/2) moist; moderate very fine subangular blocky structure parting to weak very fine granular; soft, very friable, slightly sticky and slightly plastic; common fine and very fine roots and few coarse and medium roots; many fine and very fine pores and common medium pores; 50 percent flagstones and 35 percent flat angular pebbles; strongly effervescent; mildly alkaline (pH 7.8); diffuse irregular boundary. Can range from 10 to 15 inches thick.

C -- 29 to 40 inches; grayish brown (10YR 5/2) extremely flaggy silt loam, dark grayish brown (10YR 4/2) moist; weak very fine granular structure; soft, very friable, slightly sticky and slightly plastic; few fine and very fine roots; 65 percent flagstones and 30 percent flat angular pebbles; strongly effervescent; mildly alkaline (pH 7.8); abrupt wavy boundary. Can range from 9 to 18 inches thick.

R -- 40 inches; very hard fractured limestone. (fracture intervals exceed 8 inches)

**DESCRIPTION LOCATION**: Jefferson County, Montana; about 400 feet west and 1,300 feet south of the NE corner of Section 11, T. 6N, R. 3W.

SOIL SUITABILITY INTERPRETATION DATA SANTA FE PACIFIC GOLD CORPORATION, ELKHORN PROJECT, JEFFERSON COUNTY, MONTANA TABLE 4-1

٠.														
		Average	Average	Capability Class*	Erosion Factors	actors			Erosion Est					
		Depth to	Depth to		Water		Wind			Total				
SERIES		Bedrock	50% C.F.	Dryland/		<b>-</b>		_		Available	Drainage	Hydrologic	Flood	
NAME		(inches)	(inches)	Irrigated	×	(Vacre)	WEG	(Vacre/yr)	Wind/Water	H2O(inches	Class	Group	Hazard	Hydric
ADEL	Grassland	+09	+09	eg/eg	0.28	ıc	œ	48	moderate/eliaht	7.5	lon	۵	į.	1
BEAVERELL	Grassland	+09	=	75/75	0.05	2	9	84	moderate/moderate	5.0		οα	D 000	2 2
BOBOWIC	Forest	43	43	7e/-	0 10	ı et	4	2 8	moderateleavere	o u	i To	0 0	notice	2
BROWNSHUT	Grassland	90	90	45/45	0.74	om	₹ ₹	8 8	envera/eliaht	C. A	Meil Meil Meil Meil Meil Meil Meil Meil	<b>o</b> o	none	2
CASEYPEAK	Forest	£	8 2	797	80.0	· •	ļ a	3 6	severe/sugin		i ≪	p (	none	2
CLASOIL	Grassland	9	9	5 /d	0.00	- <b>ư</b>	<b>.</b>	- <del>c</del>	moderate/energ	) - -	M T	ם נ	none	2
CRAGO	Grassland	9	<u> </u>	46/46	200	» «	۰ <del>ج</del>	0 0	modelais/sevele	0.5	Mel	0 0	none	2
CUMULIC HAPLAQUOLLS	Grassland	+09	+09	5w/5w	0.43	) e	ی ب	8 8	pone/elials	0.0	Well	ם נ	none	2
DRYADINE	Forest	40	y us	7e/-	0.15	, 0	, <del>4</del>	9 8	coveralence	2.6	וליי וליי	) د	occasional	)es
FAIRWAY	Grassland	90	90	3w/3w	0.32	i. <b>4</b> 0	ی !	48	moderate/eliabl	9 6	i do	ى د	a ioi	2 1
FLUVAQUENTIC HAPLAQUOLLS	_	+09	+09	6w/6w	0.32	4	ď	48	eliaht/moderate	o o	900	ى د	9 1	2 ;
FRANCONI		36	98	7e/7e	0.51		ο α	? c	pope/eavera	0.6	i lond	ء د	rare	2
HANSON	Grassland	+09	7	46/46	0 17	ic	٠ =		none process	, u	# T	0 0	none	6
HELMVILLE	Forest	+09	. <del>c</del>	7e/-	; c	. "	ļα	3 c	severe/severe	0.0	Mell Mell	<b>2</b> 0 (	none	2
HILGER	Grassland	+09	2 σ	79/7	, c		•		ione/severe		Me:	י כי	none	2
JUDELL	Grassland	+09	. 2	9//0/	2 .	, u	> =	<b>-</b>	illouerate/severe	4. (	weii	20 (	none	2
IAP	Graceland	ş <b>ş</b>	ţu	7077	0.24	o <del>-</del>	₹ =	8 8	severe/moderate	3.5	we.	<b>1</b> 00	none	2
I BEG	Graceland	2 0	0	2/2/	0.0	- ,	ት ,	99 9	severe/moderate	1.0	we	۵	none	2
MACIN	Crassland	<b>5</b> %	<b>.</b>	-ie-	0.13	n (	တ :	84	moderate/severe	4.0	well	Ω.	попе	2
MADTINEDALE	Grassland	9 7	4 6	99/99	0.15	N :	4.	86	severe/severe	2.5	well	ပ	none	٤
MAKINSUALE	Grassland	+09	+09	4e/4e	0.37	S	မှ	48	moderate/moderate	8.0	well	œ	none	2
NEOLLET	Grassland	+09	÷09	4w/4w	0.32	7	5	26	moderate/slight	4.0	poor	60	rare	2
NEMAN	Grassland	12	0	-/ə/	0.15	-	ဖ	48	moderate/severe	1.0	well	۵	none	2
PENSORE	Grassland	5	4	7s/7s	0.20	-	4	86	severe/moderate	2.0	well	٥	none	2
KEUFEKN	Forest	5	<b>o</b> !	7e/-	0.05	-	9	48	moderate/severe	1.0	well	٥	none	٤
SAVOUS CONTRACTOR	Grassland	+09	15	7e/7e	0.15		2	26	moderate/severe	4.0	well	æ	none	2
SHAWMUI	Grassland	÷09	15	/e/-	0.20	က	ဖ	48	moderate/severe	6.0	well	80	none	2
SHOOK	Grassland	36+	28	e9/e9	0.32	7	ĸ	26	moderate/moderate	3.0	well	ပ	none	2
	Grassland	+09	17	4s/4s	0.15	6	ł.	26	moderate/severe	5.0	well	æ	none	2
SIEBEKELL	Grassland	+09	=	es/es	0.15	<b>ب</b>	9	48	slight/moderate	2.5	well	æ	none	2
SICAS	Grassland	+09	+09	6w/6w	0.37	s.	S	99	moderate/moderate	8.0	poor	ပ	none	2
SLOCUM	Grassland	÷09	÷09	6w/6w	0.37	7	5	56	moderate/moderate	6.5	000	· O	9000	200
TEPECREEK	Forest	25	28	7e/-	0.10	က	۵	0	none/severe	2.5	well	α	9000	} {
TIGERON	Forest	+09	20	-/e/-	0.10	ဗ	9	48	moderate/severe	3.5	lew lew	o cc	9000	2 2
TOLBERT	Grassland	12	ı,	7e/-	0.15	-	ဖ	48	moderate/severe	1.0	we li	ے د	200	2 2
TROPAL	Forest	15	4	7e/7e	0.15	-	4L	86	severe/severe	10	i ex	ے د	9000	2 2
TYPIC HAPLOBOROLLS	Grassland	+09	+09	4e/4e	0.32	က	9	48	severe/severe	8.0	- N	) α	9000	2 6
VARNEY	Grassland	+09	÷09	-/a9	0.32	2	9	48	moderate/severe	· œ	llow	a	9000	2 6
WARNEKE	Forest	12	12	7e/-	0.10	-	4	86	severe/severe	0	law.	o C		2 8
WHITECOW	Forest	+09	7	7e/-	0.15	9	4	98	severe/severe	. 4	ileys.	) α	9101	2 2
WINDHAM	Grassland/Forest	÷09	=	-/e9	0.24	2	4	86	Severe/severe		10	0 0	9 10 1	2 ¦

Capability Class designated 1 (few commercial crop limitations) through 7 (unsuitable for commercial crops, limited to recreation/wildlife/habitat)

Type of Limitation: e = ersosion, w = wetness, s = shallow, stony, droughty

SFPG-PME-SFP.WB11KL

### DRYADINE (2) SERIES

The Dryadine (2) series consists of moderately deep, well-drained soils that formed in residuum derived from limestone. These soils are on mountaintops. Slopes are 2 to 25 percent. Mean annual precipitation is about 35 inches, and mean annual air temperature is about 36°F.

TAXONOMIC CLASS: Loamy-skeletal, carbonatic Typic Cryochrepts

**TYPICAL PEDON:** Dryadine flaggy silt loam, forested, colors are for dry soil unless otherwise noted.

- Oi -- 2 inches to 1-inch; pine needles, twigs and cones.
- Oe -- 1 to 0-inch; partly weathered organic matter.
- A -- 0 to 4 inches; very dark grayish brown (10YR 3/2) flaggy silt loam, black (10YR 2/1) moist; fine platy parting; moderate very fine granular structure; soft, very friable, slightly sticky and plastic; many fine and very fine roots; 15 percent angular cobbles and 15 percent pebbles; neutral (pH 7.3); abrupt wavy boundary. Can range from 2 to 5 inches thick.
- Bw -- 4 to 11 inches; grayish brown (10YR 5/2) extremely flaggy silt loam, very dark grayish brown (10YR 3/2) moist; very fine weak subangular blocky structure parting; soft, very friable, slightly sticky and slightly plastic; many fine and very fine roots; 25 percent flat angular pebbles and 30 percent angular cobbles; strongly effervescent; mildly alkaline (pH 7.6); gradual wavy boundary. Can range from 3 to 10 inches thick.
- Bk -- 11 to 24 inches; very pale brown (10YR 7/3) extremely flaggy silt loam, very pale brown (10YR 7/3) moist; moderate very fine subangular blocky structure parting; soft, very friable, slightly sticky and slightly plastic; common fine and very fine roots; many fine and very fine pores and common medium pores; 40 percent flagstones and 20 percent angular cobbles; violently effervescent; moderately alkaline (pH 7.9); diffuse irregular boundary. Can range from 10 to 15 inches thick.
- C -- 24 to 40 inches; very pale brown (10YR 7/3) extremely flaggy silt loam, very pale brown (10YR 7/3) moist; massive; soft, very friable, slightly sticky and slightly plastic; few fine and very fine roots; 3-5 percent pebbles, 50 percent flagstones and 30 percent angular cobbles; violently effervescent; strongly alkaline (pH 8.7); abrupt wavy boundary. Can range from 9 to 18 inches thick.
  - R -- 40+ inches; very hard fractured limestone (Jefferson dolomite)

**DESCRIPTION LOCATION**: Jefferson County, Montana; about 2,350 feet south and 2,200 feet east of the NW corner of Section 14, T. 6N, R. 3W.

# 4.0 USE AND MANAGEMENT OF ELKHORN PROJECT SOILS

Elkhorn Project area soils will be subject to multiple uses. In areas of the project where mining-related activities result in a disturbance of the land, soils will be salvaged and utilized for reclamation purposes. The construction of mine facilities (roads, buildings, diversions, tailings impoundments, etc.), and open pit mining are examples of disturbances which will require the salvage of soils. Some areas within the project may be utilized for the disposal of excess mine water. Much of the land in the project area may not be disturbed and will probably be managed as rangeland or wildlife habitat. This section of the baseline soil report provides information needed to determine the suitability of the Elkhorn Project soils for a given use.

# 4.1 FACTORS USED TO DETERMINE SOIL SALVAGE DEPTHS AND RECLAMATION SUITABILITY

Information on the morphology of soils obtained from detailed profile descriptions (Section 3.3) and the results of chemical and physical laboratory analysis performed on genetic soil horizons (Appendix A) are the primary data used to evaluate soil salvage depths and reclamation suitability. Structure, thickness of genetic horizons, depth and abundance of roots, abundance of rock fragments, and depth to bedrock are important morphological factors used to determine the depth of salvage. Soil pH, organic matter content and texture are the primary chemical and physical parameters used to evaluate the quality of salvageable soil. Other soil factors used to evaluate the depth of salvage and the suitability of project area soils for reclamation and other purposes were obtained from the SCS (soil interpretation data). Interpretations for Elkhorn Project area soils are summarized in Table 4-1. In Table 4-1, information is organized according to four categories including interpretive groups (range site and habitat type), soil morphology, capability and erosion (dryland/irrigated capability and K, T, WEG and I factors), and hydrologic features (WHC, drainage, hydrologic group, flood hazard and hydric). All relevant morphological, chemical and physical data were evaluated relative to DSL unsuitability criteria (Table 2-2) or other guidelines (DSL 1983).

#### **FAIRWAY SERIES**

The Fairway series consists of very deep, somewhat poorly drained soils that formed in alluvium. These soils are on flood plains. Slopes are 0 to 4 percent. Mean annual precipitation is about 12 inches. Mean annual temperature is about 43° F.

**TAXONOMIC CLASS:** Fine-loamy, mixed Fluvaquentic Haploborolls

**TYPICAL PEDON:** Fairway silt loam, cultivated (colors are for dry soil unless otherwise noted).

- A1 -- 0 to 8 inches; grayish brown (10YR 5/2) silt loam, very dark grayish brown (10YR 3/2) moist; moderate very fine and fine granular structure; slightly hard, friable, sticky and slightly plastic; common very fine, medium, and coarse roots; disseminated lime; strongly effervescent; mildly alkaline (pH 7.6); clear smooth boundary. (5 to 8 inches thick)
- A2 -- 8 to 15 inches; grayish brown (2.5Y 5/2) loam, very dark grayish brown (2.5Y 3/2) moist; weak medium prismatic structure parting to weak medium subangular blocky; slightly hard, friable, sticky and slightly plastic; common very fine, medium, and coarse roots; common very fine tubular and interstitial pores; disseminated lime; strongly effervescent; mildly alkaline (pH 7.8); clear smooth boundary. (5 to 10 inches thick)
- Bk -- 15 to 30 inches; light brownish gray (2.5Y 6/2) silt loam, dark grayish brown (2.5Y 4/2) moist; weak medium prismatic structure parting to weak coarse subangular blocky; hard, friable, sticky and slightly plastic; common very fine, medium, and coarse roots; common very fine tubular and interstitial pores; few thin grayish brown (2.5Y 5/2) layers of soil, very dark grayish brown (2.5Y 3/2) moist; few fine seams and masses of lime; strongly effervescent; mildly alkaline (pH 7.8); clear smooth boundary. (10 to 20 inches thick)
- Bg -- 30 to 45 inches; light brownish gray (2.5Y 6/2) silty clay loam, dark grayish brown (2.5Y 4/2) moist; many fine and medium prominent reddish brown (5YR 4/4) mottles, moist; massive; friable, sticky and plastic; disseminated lime; slightly effervescent; neutral (pH 7.2); gradual smooth boundary. (10 to 24 inches thick)
- 2Cg -- 45 to 60 inches; light brownish gray (2.5Y 6/2) sand, dark grayish brown (2.5Y 4/2) moist; few fine and medium prominent dark brown (7.5YR 4/4) mottles, moist; single grain; loose, nonsticky and nonplastic; neutral (pH 7.2); (0 to 20 inches thick)

TYPE LOCATION: Lewis and Clark County, Montana; about 2,100 feet north and 2,400 feet east of the SW corner of Section 15, T. 10N, R. 3W.

#### 3.4 LABORATORY ANALYTICAL RESULTS

The results of laboratory analyses performed on genetic horizons of the soil series sampled in the project area are in Appendix A. A total of 137 samples from 31 soil series were analyzed. The results of chemical and physical analysis performed on project area soils are used in conjunction with morphological information provided in the detailed soil profile descriptions to determine salvage depths and the suitability of soils for reclamation, and other uses. The pH of project area soils ranged from 5.0 to 8.6. Arsenic and metals were not analyzed or considered in the evaluation of salvage and reclamation suitability since pH values for all soil horizons were above 5 (Hydrometrics, 1993). Samples were analyzed for all other parameters listed in Table 2-2. The interpretation of chemical and physical analysis results is discussed in Section 4.1.2.

## FRANCONI SERIES

The Franconi series consists of moderately deep, well-drained soils that formed in colluvium or residuum derived from granite bedrock. These soils are on dissected bedrock floored plains, hills and mountains. Slopes are 4 to 60 percent. Mean annual precipitation is about 22 inches. Mean annual air temperature is about 38° F.

TAXONOMIC CLASS: Fine-loamy, mixed Glossic Cryoboralfs

**TYPICAL PEDON:** Franconi gravelly sandy clay loam, stony, forested (colors are for dry soil unless otherwise noted).

 $\mathrm{Oi}$  -- 1 to 0 inches; partially decomposed needles, twigs and leaves. Can range from 1/2 to 3 inches thick.

E -- 0 to 6 inches; very dark grayish brown (10YR 3/2) gravelly sandy clay loam, very dark gray (10YR 3/1) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine and fine few medium roots; many very fine and fine and medium pores; 5 percent cobbles and 15 percent pebbles; slightly acid (pH 6.3); clear smooth boundary. Can range from 3 to 8 inches thick.

E/Bt -- 6 to 11 inches; very dark grayish brown (10YR 3/2) gravelly sandy clay loam, very dark gray (10YR 3/1) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine and fine and few medium roots; many very fine and few fine interstitial and tubular pores; few faint clay films bridging sand grains in Bt part; 20 percent pebbles; neutral (pH 6.7); clear smooth boundary. Can range from 0 to 8 inches thick.

Bt/E -- 11 to 17 inches; dark brown (10YR 3/3) gravelly sandy clay loam, very dark brown (10YR 2/2) moist; moderate medium and coarse prismatic structure parting to moderate fine and medium subangular blocky; slightly hard, friable, slightly sticky and slightly plastic; many very fine and few fine and medium roots; many very fine and few fine interstitial and tubular pores; many faint clay films on faces of peds and bridging sand grains in Bt part; 20 percent pebbles; neutral (pH 6.7); clear wavy boundary. Can range from 6 to 10 inches thick.

Bt1 -- 17 to 24 inches; dark yellowish brown (10YR 4/4) gravelly clay loam, brown (10YR 4/3) moist; moderate medium and coarse prismatic structure parting to strong fine and medium subangular blocky; hard, firm, sticky and slightly plastic; common very fine and few fine and medium roots; many very fine and few fine interstitial and tubular pores; many faint clay films on faces of peds and bridging sand grains; 5 percent cobbles and 25 percent pebbles; neutral (pH 6.7); clear wavy boundary.

# WINDHAM SERIES

The Windham series consists of very deep, well-drained soils that formed in very gravelly alluvium and colluvium derived mainly from limestone. These soils are on alluvial fans, stream terraces, escarpments, and mountains. Slopes are 0 to 85 percent. Mean annual precipitation is about 16 inches. Mean annual air temperature is about 41° F.

TAXONOMIC CLASS: Loamy-skeletal, carbonatic, Typic Calciborolls

**TYPICAL PEDON:** Windham gravelly clay loam, cultivated (colors are for dry soil unless otherwise noted).

- A -- 0 to 7 inches; dark grayish brown (10YR 4/2) gravelly clay loam, very dark grayish brown (10YR 3/2) moist; moderate fine granular structure; slightly hard, friable, slightly sticky and slightly plastic; 15 percent limestone pebbles; continuous distinct lime casts on underside of pebbles; slightly effervescent; slightly acid (pH 6.2); clear wavy boundary. Can range from 5 to 10 inches thick.
- Bk1 -- 7 to 11 inches; pale brown (10YR 6/3) gravelly clay loam, brown (10YR 5/3) moist; moderate fine and very fine subangular blocky structure; hard, very friable, slightly sticky and slightly plastic; many fine and very fine roots; many fine and very fine pores; 20 percent limestone pebbles; continuous prominent casts and pendants on underside of pebbles; disseminated lime; violently effervescent; mildly alkaline (pH 7.7); clear wavy boundary. Can range from 2 to 7 inches thick.
- Bk2 -- 11 to 17 inches; white (10YR 8/2) extremely gravelly loam, very pale brown (10YR 7/3) moist; massive; hard, friable, slightly sticky and nonplastic; many fine and very fine roots; many fine and very fine pores; 55 percent limestone pebbles; 5 percent limestone cobbles; common fine masses of lime; continuous prominent lime casts and pendants on underside of pebbles and cobbles; disseminated lime; violently effervescent; moderately alkaline (pH 7.9); diffuse wavy boundary. Can range from 13 to 26 inches thick.
- Bk3 -- 17 to 60 inches; very pale brown (10YR 7/4) extremely gravelly loam, light yellowish brown (10YR 6/4) moist; massive; slightly hard, friable, slightly sticky and nonplastic; common fine and very fine roots; common to few fine and very fine pores; 60 percent limestone pebbles, 10 percent cobbles; common fine masses of lime; continuous distinct lime casts and pendants on underside of pebbles and cobbles; disseminated lime; violently effervescent; moderately alkaline (pH 8.3).

**DESCRIPTION LOCATION:** Jefferson County, Montana; 1,900 feet north and 450 feet west of the SE corner of Section 10, T. 5N, R. 3W.

# FRANCONI SERIES (Continued)

Bt2 -- 24 to 32 inches; brown (10YR 4/3) gravelly clay loam, dark brown (1.0YR 3/3) moist; weak coarse prismatic structure parting to moderate fine and medium subangular blocky; slightly hard, friable, slightly sticky and slightly plastic; few very fine roots; common very fine and few fine interstitial and tubular pores; common faint clay films on faces of peds and bridging sand grains; 20 percent pebbles; neutral (pH 6.7); clear smooth boundary. Combined thickness of Bt horizons can range from 13 to 25 inches.

Cr -- 32+ inches; olive brown (2.5Y 4/3) decomposed diorite bedrock (grus) that crushes to very gravelly coarse sand; neutral (pH 7.2); gradual wavy boundary.

**DESCRIPTION LOCATION:** Jefferson County, Montana; 1,800 feet north and 100 feet west of the SE corner of Section 10, T. 6N, R. 3W.

#### WHITECOW SERIES

The Whitecow series consists of very deep, well-drained soils that formed in alluvium and colluvium from limestone. These soils are on mountains, hills, and alluvial fans. Slopes are 0 to 80 percent. Mean annual precipitation is about 20 inches. Mean annual air temperature is about 41° F.

TAXONOMIC CLASS: Loamy-skeletal, carbonatic, frigid Typic Ustochrepts

**TYPICAL PEDON:** Whitecow gravelly loam, woodland (colors are for dry soil unless otherwise noted).

- O -- 1 inch to 0; undecomposed forest litter of needles and twigs.
- A -- 0 to 3 inches; dark grayish brown (10YR 4/2) gravelly loam, very dark grayish brown (10YR 3/2) moist; weak medium and fine granular structure; soft, very friable, slightly sticky and slightly plastic; common fine roots and few medium roots; 25 percent subrounded pebbles; slightly effervescent; mildly alkaline (pH 7.5); clear smooth boundary. Can range from 2 to 4 inches thick.
- Bk1 -- 3 to 7 inches; grayish brown (10YR 5/2) very gravelly loam, dark grayish brown (10YR 4/2) moist; weak fine angular structure; soft, very friable, slightly sticky and slightly plastic; common fine roots; common fine pores; 40 percent angular pebbles; 5 percent angular cobbles; continuous faint lime crusts on undersides of rock fragments; violently effervescent; mildly alkaline (pH 7.5); clear boundary. Can range from 3 to 15 inches thick.
- Bk2 -- 7 to 17 inches; light brownish gray (2.5Y 6/2) very gravelly heavy loam, light olive brown (2.5Y 5/4) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, sticky and slightly plastic; few or common fine roots; common fine pores; 60 percent angular pebbles; 5 percent angular cobbles; continuous distinct lime coats on rock fragments; disseminated lime; violently effervescent; mildly alkaline (pH 7.8); gradual boundary. Can range from 6 to 20 inches thick.
- Bk3 -- 17 to 30 inches; light brownish gray (2.5Y 6/2) extremely gravelly loam, light olive brown (2.5Y 5/4) moist; weak fine and medium subangular blocky structure; slightly hard, friable, sticky and slightly plastic; few fine roots; few fine pores; 70 percent angular pebbles, 5 percent angular cobbles; continuous distinct lime coats on rock fragments; violently effervescent; moderately alkaline (pH 8.2); gradual boundary. Can range from 15 to 25 inches thick.
- Bk4 -- 30 to 60 inches; light brownish gray (2.5Y 6/2) extremely gravelly loam, light olive brown (2.5Y 5/4) moist; massive; slightly hard, friable, sticky and slightly plastic; few fine roots; few fine pores; 70 percent angular pebbles, 5 percent angular cobbles; violently effervescent; moderately alkaline (pH 8.1).

**DESCRIPTION LOCATION**: Jefferson County, Montana; 700 feet east and 100 feet north of the SW corner of Section 2, T. 5N, R. 3W.

## FRANCONI (2) SERIES

The Franconi (2) series consists of moderately deep, well-drained soils that formed in colluvium or residuum derived from granite bedrock. These soils are on dissected bedrock floored plains, hills and mountains. Slopes are 4 to 60 percent. Mean annual precipitation is about 22 inches. Mean annual air temperature is about 38° F.

TAXONOMIC CLASS: Fine-loamy, mixed Glossic Cryoboralfs

**TYPICAL PEDON:** Franconi gravelly sandy clay loam, stony, forested (colors are for dry soil unless otherwise noted).

Oi -- 1 to 0 inches; partially decomposed needles, twigs and leaves. Can range from 1/2 to 3 inches thick.

E -- 0 to 8 inches; grayish brown (10YR 5/2) gravelly sandy clay loam, very dark grayish brown (10YR 3/2) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine and fine few medium roots; many very fine and fine and medium pores; 5 percent cobbles and 15 percent pebbles; slightly acid (pH 6.1); clear smooth boundary. Can range from 3 to 8 inches thick.

E/Bt -- 8 to 14 inches; grayish brown (10YR 5/2) gravelly sandy clay loam, very dark brown (10YR 3/3) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine and fine and few medium roots; many very fine and few fine interstitial and tubular pores; few faint clay films bridging sand grains in Bt part; 5 percent cobbles, 20 percent pebbles; slightly acid (pH 6.4); clear smooth boundary. Can range from 0 to 8 inches thick.

Bt/E -- 14 to 19 inches; grayish brown (10YR 5/2) gravelly sandy clay loam, brown (10YR 4/3) moist; moderate medium and coarse prismatic structure parting to moderate fine and medium subangular blocky; slightly hard, friable, slightly sticky and slightly plastic; many very fine and few fine and medium roots; many very fine and few fine interstitial and tubular pores; many faint clay films on faces of peds and bridging sand grains in Bt part; 5 percent cobbles, 20 percent pebbles; neutral (pH 6.6); clear wavy boundary. Can range from 6 to 10 inches thick.

Bt1 -- 19 to 30 inches; grayish brown (10YR 5/2) gravelly clay loam, brown (10YR 4/3) moist; moderate medium and coarse prismatic structure parting to strong fine and medium subangular blocky; hard, firm, sticky and slightly plastic; common very fine and few fine and medium roots; many very fine and few fine interstitial and tubular pores; many faint clay films on faces of peds and bridging sand grains; 5 percent cobbles and 25 percent pebbles; neutral (pH 6.7); clear wavy boundary.

#### WARNEKE SERIES

The Warneke series consists of shallow, well-drained soils that formed in residuum or colluvium weathered from limestone. These soils are on hills, mountains, and bedrockfloored plains. Slopes are 0 to 70 percent. Mean annual precipitation is about 18 inches. Mean annual air temperature is about 42° F.

TAXONOMIC CLASS: Loamy-skeletal, carbonatic, frigid Lithic Ustochrepts

TYPICAL PEDON: Warneke gravelly loam, grassland (colors are for dry soil unless otherwise noted).

A -- 0 to 2 inches; brown (10YR 5/3) gravelly loam, dark brown (10YR 3/3) moist; moderate fine granular structure; soft, very friable, slightly sticky and slightly plastic; common fine and medium roots; 20 percent pebbles, 5 percent cobbles; disseminated lime; strongly effervescent; neutral (pH 7.2); clear wavy boundary. Can range from 1 to 4 inches thick.

Bk -- 2 to 12 inches; very pale brown (10YR 7/3) very channery loam, pale brown (10YR 6/3) moist; moderate fine subangular blocky structure; hard, friable, sticky and slightly plastic; few fine and medium roots; common fine and very fine pores; 25 percent channers; 15 percent flagstone; disseminated lime; continuous distinct lime casts on underside of fragments; violently effervescent; neutral (pH 7.3); clear wavy boundary. Can range from 9 to 18 inches thick.

R -- 12+ inches; limestone, with few fractures.

**DESCRIPTION LOCATION**: Jefferson County, Montana; about 1,400 feet south and 1,450 feet west of the NE corner of Section 11, T. 5N, R. 3W.

# FRANCONI (2) SERIES (Continued)

Bt2 -- 30 to 41 inches; grayish brown (10YR 5/2) gravelly clay loam, brown (10YR 4/3) moist; weak coarse prismatic structure parting to moderate fine and medium subangular blocky; slightly hard, friable, slightly sticky and slightly plastic; few very fine roots; common very fine and few fine interstitial and tubular pores; common faint clay films on faces of peds and bridging sand grains; 5 percent cobbles, 20 percent pebbles; neutral (pH 6.6); clear smooth boundary. Combined thickness of Bt horizons can range from 13 to 25 inches.

Cr -- 41+ inches; grayish brown (2.5Y 5/2) decomposed diorite bedrock (grus) that crushes to very gravelly coarse sand; neutral (pH 6.9); gradual wavy boundary.

**DESCRIPTION LOCATION**: Jefferson County, Montana; 1,050 feet south and 1,700 feet west of the NE corner of Section 14, T. 6N, R. 3W.

#### VARNEY SERIES

The Varney series consists of very deep, well-drained soils that formed in alluvium. These soils are on alluvial fans, stream terraces, and hills. Slopes are 0 to 50 percent. Mean annual precipitation is about 13 inches, and mean annual air temperature is about 40°F.

TAXONOMIC CLASS: Fine-loamy, mixed Aridic Argiborolls

TYPICAL PEDON: Varney clay loam, cultivated, colors are for dry soil unless otherwise noted.

- A -- 0 to 5 inches; grayish brown (10YR 5/2) clay loam, very dark grayish brown (10YR 3/2) moist; moderate fine and very fine granular structure; slightly hard, friable, slightly sticky and slightly plastic; many fine and very fine roots; many fine and very fine interstitial pores; 5 percent pebbles; neutral (pH 6.6); clear smooth boundary. (3 to 9 inches thick)
- Bt -- 5 to 16 inches; brown (10YR 5/3) clay loam, dark brown (10YR 4/3) moist; moderate medium and fine subangular blocky structure; hard, sticky and plastic; many fine and very fine roots; common fine tubular pores; continuous, faint clay films on faces of peds; 10 percent pebbles; neutral (pH 7.3); clear irregular boundary. (5 to 15 inches thick)
- Bk1 -- 16 to 28 inches; light gray (10YR 7/2) gravelly sandy clay loam, pale brown (10YR 6/3) moist; weak coarse prismatic structure; slightly hard, friable, slightly sticky and nonplastic; common fine and very fine roots; common fine and very fine pores; 15 percent pebbles and 5 percent cobbles; common fine masses of lime; violently effervescent; moderately alkaline (pH 7.9); gradual smooth boundary. (5 to 25 inches thick)
- Bk2 -- 28 to 48 inches; very pale brown (10YR 7/3) gravelly sandy loam, pale brown (10YR 6/3) moist; weak, coarse, prismatic structure; soft, friable, slightly sticky and nonplastic; few fine roots; few fine pores; 15 percent pebbles and 5 percent cobbles; disseminated lime; few fine masses of lime; strongly effervescent; moderately alkaline (pH 7.9); clear smooth boundary. (5 to 25 inches thick)
- BC -- 48 to 60 inches; light brown (7.5YR 6/4) stratified gravelly sandy loam and gravelly loamy sand, brown (7.5YR 5/4) moist; massive; slightly hard, friable, slightly sticky and nonplastic; few fine roots; few fine pores; 20 percent pebbles and 5 percent cobbles; slightly effervescent; moderately alkaline (pH 8.4).

TYPE LOCATION: Madison County, Montana; 2,400 feet north and 2,300 feet west of the SE corner of Section 32, T. 2S., R. 1W.

#### HANSON SERIES

The Hanson series consists of very deep, well-drained soils that formed in colluvium, alluvium, and glacial till derived from limestone rock. These soils are on stream terraces, alluvial fans, mountains, hills, and moraines. Slopes are 0 to 70 percent. Mean annual precipitation is about 23 inches. Mean annual temperature is about 40° F.

TAXONOMIC CLASS: Loamy-skeletal, carbonatic Calcic Cryoborolls

TYPICAL PEDON: Hanson loam, native grass (colors are for dry soil unless otherwise noted).

- A1 -- 0 to 8 inches; very dark grayish brown (10YR 3/2) loam, black (10YR 2/1) moist; moderate fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine roots; 5 percent pebbles; slightly acid (pH 6.5); gradual smooth boundary. Can range from 8 to 12 inches thick.
- A2 -- 8 to 14 inches; dark grayish brown (10YR 4/2) loam, black (10YR 2/1) moist; weak medium prismatic structure parting to weak medium and fine subangular blocky: slightly hard, very friable, slightly sticky and slightly plastic; many very fine roots; many very fine tubular and interstitial pores; 10 percent limestone pebbles; disseminated lime; strongly effervescent; neutral (pH 7.0); clear smooth boundary. Can range from 0 to 6 inches thick
- Bk1 -- 14 to 21 inches; grayish brown (10YR 5/2) very cobbly loam, dark grayish brown (10YR 4/2) moist; weak fine subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; many very fine roots; many very fine tubular and interstitial pores; 50 percent cobbles, 10 percent pebbles; disseminated lime; many masses of lime; continuous distinct lime crusts on underside of fragments; violently effervescent; mildly alkaline (pH 7.5); diffuse smooth boundary. Can range from 10 to 20 inches thick.
- Bk2 -- 21 to 43 inches; light brownish gray (10YR 6/2) extremely cobbly loam, light brownish gray (10YR 6/2) moist; moderate fine subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; few fine roots; many very fine tubular and interstitial pores; 55 percent cobbles, 25 percent pebbles; disseminated lime; many masses of lime; continuous distinct lime crusts on undersides of fragments; violently effervescent; mildly alkaline (pH 7.8); gradual wavy boundary. Can range from 10 to 20 inches thick.
- Bk3 -- 43+ inches; pale yellow (2.5Y 7/4) extremely cobbly loam, light yellowish brown (2.5Y 6/4) moist; weak fine subangular blocky structure; slightly hard, very friable. slightly sticky and slightly plastic; few very fine roots; common very fine tubular and interstitial pores; 55 percent cobbles, 10 percent pebbles; disseminated lime; continuous distinct lime coatings on fragments; violently effervescent.

**DESCRIPTION LOCATION:** Jefferson County, Montana; 1,700 feet west and 300 feet south of the NE corner of Section 14, T. 6N, R. 3W.

# TROPAL (2) SERIES

The Tropal (2) series consists of shallow, somewhat excessively drained soils that formed in residuum and colluvium derived from limestone. These soils are on hills and mountains. Slopes are 8 to 65 percent. Mean annual precipitation is about 17 inches, and mean annual air temperature is about 38°F.

TAXONOMIC CLASS: Loamy-skeletal, carbonatic Lithic Cryochrepts

TYPICAL PEDON: Tropal very gravelly loam, bouldery, forested, colors are for dry soil unless otherwise noted.

Oi -- 1 to 0 inches; partially decomposed needles, twigs and leaves.

A -- 0 to 7 inches; dark grayish brown (10YR 4/2) very gravelly loam, very dark gray (10YR 3/1) moist; moderate medium granular structure; slightly hard, very friable, nonsticky and nonplastic; many fine roots; common very fine and fine pores; 30 percent pebbles, 5 percent cobbles; continuous distinct lime coatings on underside of fragments; violently effervescent; mildly alkaline (pH 7.4); abrupt smooth boundary. Can range from 2 to 6 inches thick.

Bk -- 7 to 15 inches; grayish brown (10YR 5/2) very gravelly loam, very dark gray (10YR 3/1) moist; fine subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; many fine roots; common very fine and fine pores; 40 percent pebbles, 10 percent cobbles; continuous prominent lime casts on fragments; disseminated lime; violently effervescent; mildly alkaline (pH 7.4); gradual wavy boundary. Can range from 7 to 13 inches thick.

R -- 15+ inches; light gray (10YR 7/1) hard limestone.

**DESCRIPTION LOCATION:** Jefferson County, Montana; 1,500 feet east and 350 feet north of the SW corner of Section 11, T. 6N, R. 3W.

#### **HELMVILLE SERIES**

The Helmville series consists of very deep, well-drained soils that formed in colluvium and alluvium derived from limestone, argillite, and igneous rock. These soils are on mountains. Slopes are 4 to 60 percent. Mean annual precipitation is about 25 inches. Mean annual temperature is about 37° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Typic Cryoboralfs

**TYPICAL PEDON:** Helmville cobbly loam, forested (colors are for dry soil unless otherwise noted).

Oi -- 1 inch to 0; forest litter, slightly decomposed.

E -- 0 to 10 inches; light brownish gray (10YR 6/2) cobbly loam, brown (10YR 4/3) moist; weak fine granular structure; soft, friable, nonsticky and nonplastic; many very fine, fine, and medium roots; many very fine and fine discontinuous irregular pores; 15 percent cobbles and 15 percent pebbles; slightly acid (pH 6.5); gradual wavy boundary. Can range from 5 to 15 inches thick.

Bt1 -- 10 to 18 inches; yellowish brown (10YR 5/4) very cobbly clay loam, brown (10YR 4/3) moist; weak medium subangular blocky structure parting to weak medium granular; slightly hard, friable, slightly sticky and plastic; many very fine and fine, common medium, and few coarse roots; many very fine and fine discontinuous irregular pores; many thin continuous clay films on faces of peds; 25 percent cobbles and 20 percent pebbles; slightly acid (pH 6.4); gradual wavy boundary. Can range from 0 to 8 inches thick.

Bt2 -- 18 to 38 inches; yellowish brown (10YR 5/4) very cobbly clay loam, brown (10YR 4/3) moist; weak medium subangular blocky structure; slightly hard, friable, sticky and plastic; common very fine, fine and medium roots; many very fine and fine discontinuous irregular pores; many thin continuous clay films on faces of peds; 30 percent cobbles and 25 percent pebbles; neutral (pH 6.7); clear smooth boundary. Can range from 9 to 20 inches thick.

Bk -- 38 to 60 inches; light yellowish brown (10YR 6/4) very cobbly clay loam, yellowish brown (10YR 5/4) moist; weak fine subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; few very fine and fine roots; many very fine and fine discontinuous irregular pores; 30 percent pebbles and 30 percent cobbles; disseminated lime; continuous distinct lime coating on pebbles and cobbles, faint distinct lime casts on undersides of the rock fragments; violently effervescent; mildly alkaline (pH 7.5).

**DESCRIPTION LOCATION**: Jefferson County, Montana; 1,250 feet west and 2,100 feet north of the SE corner of Section 10, T. 6N, R. 3W.

#### TROPAL SERIES

The Tropal series consists of shallow, somewhat excessively drained soils that formed in residuum and colluvium derived from limestone. These soils are on hills and mountains. Slopes are 8 to 65 percent. Mean annual precipitation is about 17 inches, and mean annual air temperature is about 38°F.

TAXONOMIC CLASS: Loamy-skeletal, carbonatic Lithic Cryochrepts

**TYPICAL PEDON:** Tropal very gravelly loam, bouldery, forested, colors are for dry soil unless otherwise noted.

Oi -- 1/2 to 0 inches; partially decomposed needles, twigs and leaves.

A -- 0 to 4 inches; very dark gray (10YR 3/1) very gravelly loam, black (10YR 2/1) moist; moderate medium granular structure; slightly hard, very friable, nonsticky and nonplastic; many fine roots; common very fine and fine pores; 40 percent pebbles, 5 percent cobbles; continuous distinct lime coatings on underside of fragments; violently effervescent; mildly alkaline (pH 7.5); abrupt smooth boundary. Can range from 2 to 6 inches thick.

Bk -- 4 to 15 inches; dark grayish brown (10YR 4/2) very gravelly loam, very dark grayish brown (10YR 3/2) moist; fine subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; many fine roots; common very fine and fine pores; 50 percent pebbles, 10 percent cobbles; continuous prominent lime casts on fragments; disseminated lime; violently effervescent; mildly alkaline (pH 7.5); gradual wavy boundary. Can range from 7 to 13 inches thick.

R -- 15+ inches; light gray (10YR 7/1) hard limestone.

**DESCRIPTION LOCATION**: Jefferson County, Montana; 1,600 feet south and 600 feet west of the NW corner of Section 11, T. 6N, R. 3W.

#### HILGER SERIES

The Hilger series consists of very deep, well-drained soils that formed in alluvium, colluvium or till from igneous rock and sandstone. These soils are on alluvial fans, stream terraces, mountains, and moraines. Slopes are 0 to 60 percent. Mean annual precipitation is about 17 inches. Mean annual temperature is about 41° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Typic Argiborolls

TYPICAL PEDON: Hilger very stony loam, rangeland (colors are for dry soil unless otherwise noted).

- A -- 0 to 5 inches; very dark grayish brown (10YR 3/2) very stony loam, very dark brown (10YR 2/2) moist; moderate fine granular structure; slightly hard, very friable, nonsticky and nonplastic; many fine and very fine roots; 10 percent stones, 15 percent cobbles, 15 percent pebbles; moderately acid (pH 5.9); clear wavy boundary. Can range from 4 to 6 inches thick.
- Bt1 -- 5 to 9 inches; brown (10YR 4/3) very cobbly clay loam, dark brown (10YR 3/3) moist; moderate medium prismatic structure parting to strong fine subangular blocky; hard, firm, sticky and plastic; many very fine roots and pores; 5 percent stones, 25 percent cobbles, 15 percent pebbles; many faint clay film on faces of peds and on surface of rock fragments; slightly acid (pH 6.1); clear wavy boundary. Can range from 3 to 8 inches thick.
- Bt2 -- 9 to 15 inches; brown (10YR 5/3) extremely cobbly clay loam, brown (10YR 4/3) moist; moderate medium prismatic structure parting to strong very fine subangular blocky; hard, firm, sticky and plastic; many very fine roots and pores; continuous faint clay films faces of peds and on surface of coarse fragments; 5 percent stones, 35 percent cobbles, 25 percent pebbles; neutral (pH 7.0); clear wavy boundary. Can range from 6 to 10 inches thick.
- Bk1 -- 15 to 19 inches; light brownish gray (2.5Y 6/2) extremely cobbly loam, grayish brown (2.5Y 5/2) moist; moderate fine subangular blocky structure; hard, friable, slightly sticky and slightly plastic; few very fine roots and pores; 5 percent stones, 30 percent cobbles, 25 percent pebbles; few large masses of lime; continuous distinct lime casts on underside of rock fragments; strongly effervescent; mildly alkaline (pH 7.6); gradual wavy boundary.
- Bk2 -- 19 to 24 inches; light gray (2.5Y 7/2) extremely cobbly loam, grayish brown (2.5Y 5/2) moist; moderate very fine subangular blocky structure; hard, friable, slightly sticky and slightly plastic; 5 percent stones, 45 percent cobbles, 10 percent pebbles; common fine masses and filaments of lime; continuous distinct lime casts on surface of rock fragments; strongly effervescent; moderately alkaline (pH 7.7); gradual wavy boundary. Can range from 6 to 10 inches thick.

## TOLBERT SERIES

The Tolbert series consists of shallow, well-drained soils that formed in colluvium or residuum derived from hard fine grained sandstone or fine grained igneous rocks. These soils are on hills and mountains. Slopes are 8 to 60 percent. Mean annual precipitation is about 16 inches. Mean annual temperature is about 40° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Lithic Argiborolls

TYPICAL PEDON: Tolbert very cobbly loam, bouldery, in rangeland (colors are for dry soil unless otherwise noted).

A -- 0 to 5 inches; dark grayish brown (10YR 4/2) very cobbly loam, very dark grayish brown (10YR 3/2) moist; moderate medium subangular blocky structure; soft, very friable, slightly sticky and slightly plastic; many very fine and fine roots; many very fine and fine interstitial pores; 30 percent cobbles, 10 percent pebbles; neutral (pH 7.1); clear wavy boundary. Can range from 5 to 8 inches thick.

Bt -- 5 to 9 inches; brown (10YR 5/3) very cobbly clay loam, brown (10YR 4/3) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, sticky and plastic; many very fine and fine roots; many very fine and fine interstitial and tubular pores; common distinct dark grayish brown (10YR 4/2) clay films on faces of peds and bridging sand grains; 40 percent cobbles, 15 percent pebbles; mildly alkaline (pH 7.6). Can range from 5 to 15 inches thick.

BC -- 9 to 11 inches; light yellowish brown (10YR 6/4) very cobbly loam, darkish yellowish brown (10YR 4/4) moist; weak medium subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; few very fine roots, 45 percent cobbles, 20 percent pebbles; mildly alkaline (pH 7.5).

R -- 12+ inches; hard fine grained igneous rock.

**DESCRIPTION LOCATION:** Jefferson County, Montana; 600 feet north and 1,700 feet west of the SE corner of Section 9, T. 5N, R. 3W.

# HILGER SERIES (Continued)

BC -- 24 to 60 inches; light yellowish brown (2.5Y 6/4) extremely stony loam, olive brown (2.5Y 4/4) moist; massive; hard, very friable, nonsticky and nonplastic; 20 percent stones, 30 percent cobbles, 20 percent pebbles; disseminated lime; strongly effervescent; mildly alkaline (pH 7.5).

**DESCRIPTION LOCATION**: Jefferson County, Montana; about 2,400 feet south and 1,400 feet east of the NW corner of Section 10, T. 5N, R. 3W.

## TIGERON (2) SERIES (Continued)

Bt -- 22 to 60 inches; brown (7.5YR 4/4) extremely flaggy sandy clay loam, dark yellowish brown (10YR 3/6) moist; strong fine and medium blocky structure; extremely hard, friable, sticky and plastic; few fine and very fine roots; many fine and very fine pores and few medium pores; continuous prominent clay films on all faces of peds and in root channels; continuous prominent clay films on all surfaces of smaller fragments and on undersides of larger fragments; common faint coating of sand grains on faces of peds and on surface of fragments; 30 percent flagstones, 30 percent channers; moderately acid (pH 6.0); gradual wavy boundary. Can range from 16 to 41 inches thick.

2C -- 60+ inches; yellowish brown (10YR 5/6) very flaggy loam, dark yellowish brown (10YR 4/6) moist; massive; extremely hard, friable, sticky and plastic; few fine and very fine roots; common fine and very fine pores; 30 percent flagstones, 20 percent channers; neutral (pH 6.9).

**DESCRIPTION LOCATION:** Jefferson County, Montana; 50 feet south and 550 feet east of the NW corner of Section 14, T. 6N, R. 3W.

### JUDELL SERIES

The Judell series consists of deep, well-drained soils that formed in calcareous alluvium derived mainly from limestone. These soils are on terraces and fans. Slopes are 0 to 8 percent. Mean annual precipitation is about 16 inches. Mean annual temperature is about 42° F.

TAXONOMIC CLASS: Fine-loamy, carbonatic Typic Calciborolls

**TYPICAL PEDON:** Judell clay loam, grassland (colors are for dry soil unless otherwise noted).

A -- 0 to 7 inches; dark grayish brown (10YR 4/2) clay loam, very dark brown (10YR 2/2) moist; moderate fine granular structure; slightly hard, very friable, sticky and plastic; many fine and very fine roots and common medium and coarse roots; less than 5 percent limestone pebbles; slightly effervescent; mildly alkaline (pH 7.6): clear smooth boundary. (6 to 10 inches thick)

B2ca -- 7 to 11 inches; pale brown (10YR 6/3) clay loam, dark brown (10YR 4/3) moist; moderate fine subangular blocky structure; hard, friable, sticky and plastic; many fine and very fine roots and common medium and coarse roots; many fine and very fine pores; less than 5 percent limestone pebbles; few fine irregular soft masses of lime; violently effervescent; moderately alkaline (pH 8.2); clear wavy boundary. (4 to 10 inches thick)

B3ca -- 11 to 28 inches; very pale brown (10YR 7/3) clay loam, dark brown (10YR 4/3) moist; moderate fine subangular blocky structure; very hard, friable, sticky and plastic; common fine and very fine roots and few medium and coarse roots; many fine and very fine pores and few medium pores; less than 5 percent lime coated pebbles; common fine and medium irregular soft masses of lime; violently effervescent; moderately alkaline (pH 8.4); gradual wavy boundary. (10 to 16 inches thick)

C1ca -- 28 to 54 inches; very pale brown (10YR 7/3) clay loam, brown (10YR 5/3) moist; common fine and medium subangular blocky structure; hard, friable, sticky and plastic; few fine and very fine roots and few medium roots; many fine and very fine pores; less than 5 percent limestone pebbles; disseminated lime; violently effervescent; moderately alkaline (pH 8.4); gradual wavy boundary. (20 to 36 inches thick)

IIC2 -- 54 to 67 inches; pale brown (10YR 6/3) extremely gravelly loam, dark brown (10YR 4/3) moist; massive; soft, friable, sticky and plastic; few fine and very fine roots; common very fine and fine pores; 60 percent pebbles, 5 percent cobbles; violently effervescent; moderately alkaline (pH 8.4).

TYPE LOCATION: Fergus County, Montana; 1,815 feet west and 660 feet south of the NE corner of Section 10, T. 15N, R. 18E.

# **TIGERON (2) SERIES**

The Tigeron (2) series consists of very deep, well-drained soils that formed in colluvium or alluvium derived from sandstone, argillite, quartzite, and other igneous rock. These soils are on alluvial fans, hills, and mountains. Slopes are 2 to 60 percent. Mean annual precipitation is about 24 inches. Mean annual temperature is about 41° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Typic Cryoboralfs

**TYPICAL PEDON:** Tigeron (2) flaggy sandy loam, forested (colors are for dry soil unless otherwise noted).

- O -- 1 inch to 0; forest litter of undecomposed and decomposed needles, twigs, and cones.
- E1 -- 0 to 2 inches; dark grayish brown (10YR 4/2) flaggy sandy loam, very dark grayish brown (10YR 2/2) moist; strong thin platy structure; soft, very friable, nonsticky and nonplastic; many fine and very fine roots; continuous coatings of sand grains on surface of plates; 10 percent flagstones, 5 percent channers; slightly acid (pH 6.1); clear wavy boundary.
- E2 -- 2 to 8 inches; grayish brown (10YR 5/2) flaggy sandy loam, brown (10YR 4/3) moist; moderate thin platy structure; slightly hard, very friable, nonsticky and nonplastic; many fine and very fine roots; continuous coatings of sand grains on plates; 20 percent flagstones, 10 percent channers; moderately acid (pH 5.8); clear wavy boundary. E horizons can range from 7 to 18 inches thick.

E and Bt -- 8 to 13 inches; brown (10YR 5/3) flaggy sandy loam, brown (10YR 4/3) moist; 1/16 to 3/8 inch thick lamellae; moderate fine subangular blocky structure; hard, friable, slightly sticky and slightly plastic; many fine and very fine roots; many fine and very fine pores and few medium pores; thin clay films in root channels; 20 percent flagstones, 10 percent channers; moderately acid (pH 5.7); clear wavy boundary. Can range from 6 to 17 inches thick.

Bt and E -- 13 to 24 inches; dark yellowish brown (10YR 4/4) very flaggy sandy clay loam, dark brown (10YR 4/3) moist; 1/16- to 1/2-inch thick lamellae; strong fine and fine blocky structure; very hard, friable, sticky and plastic; common fine and very fine roots; many fine and very fine pores and few medium pores; continuous faint clay films on faces of peds and on undersides of fragments and in root channels; 30 percent flagstones, 15 percent channers; moderately acid (pH 5.8); gradual wavy boundary. Can range from 0 to 20 inches thick.

#### LAP SERIES

The Lap series consists of shallow, well-drained soils that formed in residuum and colluvium from limestone. These soils are on bedrock-floored plains and mountains. Slopes are 0 to 75 percent. Mean annual precipitation is about 17 inches. Mean annual temperature is about 43° F.

TAXONOMIC CLASS: Loamy-skeletal, carbonatic Lithic Calciborolls

**TYPICAL PEDON:** Lap channery loam, grassland (colors are for dry soil unless otherwise noted).

A -- 0 to 5 inches; dark grayish brown (10YR 4/2) channery loam, very dark grayish brown (10YR 3/2) moist; weak very fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine roots; 35 percent channers (flat 1 to 4 inch diameter limestone fragments); neutral (pH 6.8); clear wavy boundary. Can range from 4 to 9 inches thick.

Bk1 -- 5 to 9 inches; light brownish gray (10YR 6/2) very channery loam, dark grayish brown (10YR 4/2) moist; weak fine subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common very fine roots; 50 percent channers; disseminated lime, continuous prominent lime casts on underside of channers; strongly effervescent; mildly alkaline (pH 7.5); clear wavy boundary. Can range from 2 to 6 inches thick.

Bk2 -- 9 to 19 inches; light gray (10YR 7/2) extremely channery loam, brown (10YR 5/3) moist; massive; slightly hard, friable, sticky and plastic; few very fine roots; 65 percent channers; disseminated lime, continuous prominent lime casts on underside of channers; violently effervescent; mildly alkaline (pH 7.8); gradual irregular boundary. Can range from 4 to 8 inches thick.

R -- 19 inches; hard limestone bedrock with some cracks.

**DESCRIPTION LOCATION:** Jefferson County, Montana; 250 feet west and 1,900 feet north of the SE corner of Section 10, T. 5N, R. 3W.

# TIGERON SERIES (Continued)

Bt -- 20 to 42 inches; pale brown (10YR 6/3) extremely flaggy sandy clay loam, brown (10YR 4/3) moist; strong fine and medium blocky structure; extremely hard, friable, sticky and plastic; few fine and very fine roots; many fine and very fine pores and few medium pores; continuous prominent clay films on all faces of peds and in root channels; continuous prominent clay films on all surfaces of smaller fragments and on undersides of larger fragments; common faint coating of sand grains on faces of peds and on surface of fragments; 30 percent flagstones, 30 percent channers; slightly acid (pH 6.1); gradual wavy boundary. Can range from 16 to 41 inches thick.

2C -- 42 to 60 inches; gray (10YR 6/1) very flaggy loam, dark gray (10YR 4/1) moist; massive; extremely hard, friable, sticky and plastic; few fine and very fine roots; common fine and very fine pores; 30 percent flagstones, 20 percent channers; neutral (pH 7.1).

**DESCRIPTION LOCATION**: Jefferson County, Montana; 2,100 feet east and 2,200 feet south of the NW corner of Section 4, T. 5N, R. 3W.

#### LIBEG SERIES

The Libeg series consists of very deep, well-drained soils that formed in till, colluvium, and alluvium. These soils are on mountains, alluvial fans, stream terraces, alpine moraines, hills, and avalanche chutes. Slopes are 0 to 70 percent. Mean annual precipitation is about 22 inches. Mean annual temperature is about 40° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Argic Cryoborolls

**TYPICAL PEDON:** Libeg stony loam, grassland (colors are for dry soil unless otherwise noted).

- A -- 0 to 6 inches: dark grayish brown (10YR 4/2) extremely stony loam, very dark brown (10YR 2/2) moist; weak thin platy structure parting to moderate fine and very fine granular; slightly hard, very friable, slightly sticky and slightly plastic; many fine and very fine roots, few medium roots; many fine and very fine pores; 15 percent rock fragments; neutral (pH 6.7); clear wavy boundary. Can range from 4 to 11 inches thick.
- Bt1 -- 6 to 12 inches; yellowish brown (10YR 5/4) very channery heavy loam, dark brown (10YR 3/3) moist; strong very fine subangular blocky structure; hard, friable, sticky and plastic; many fine and very fine roots; many fine and very fine pores; continuous faint clay film on faces of some peds and on rock fragments; 25 percent channery fragments; neutral (pH 6.7); clear wavy boundary.
- Bt2 -- 12 to 20 inches; yellowish brown (10YR 5/4) very channery light clay loam, dark brown (10YR 3/4) moist; strong fine and very fine angular blocky structure; very hard, friable, sticky and plastic; many fine and very fine roots; many fine and very fine pores; continuous faint clay film on faces of some peds and on rock fragments; 30 percent rock fragments; neutral (pH 6.9); clear wavy boundary.
- Bt3 -- 20 to 32 inches; yellowish brown (10YR 5/4) very channery sandy clay loam, brown (10YR 4/3) moist; strong fine and medium angular blocky structure; extremely hard, friable, sticky and plastic; common fine and very fine roots, few coarse roots; many fine and very fine pores, few medium pores; thin continuous clay films on all faces of peds and on rock fragments; 45 percent rock fragments; mildly alkaline (pH 7.4); gradual irregular boundary. Bt horizons can range from 24 to 40 inches thick.
- BC -- 32 to 60 inches; yellowish brown (10YR 5/4) very stony sandy loam, brown (10YR 4/5) moist; weak medium and fine subangular blocky structure; very hard, friable, sticky and plastic; few fine and very fine roots; common fine and very fine pores; 45 percent rock fragments; moderately alkaline (pH 7.9).

**DESCRIPTION LOCATION:** Jefferson County, Montana; 1,600 feet west and 1,900 feet south of the NE corner of Section 22, T. 6N, R. 3W.

### **TIGERON SERIES**

The Tigeron series consists of very deep, well-drained soils that formed in colluvium or alluvium derived from sandstone, argillite, quartzite, and other igneous rock. These soils are on alluvial fans, hills, and mountains. Slopes are 2 to 60 percent. Mean annual precipitation is about 24 inches. Mean annual temperature is about 41° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Typic Cryoboralfs

**TYPICAL PEDON:** Tigeron flaggy sandy loam, forested (colors are for dry soil unless otherwise noted).

- O -- 1 inch to 0; forest litter of undecomposed and decomposed needles, twigs, and cones.
- E1 -- 0 to 4 inches; light brownish gray (10YR 6/2) flaggy sandy loam, very dark grayish brown (10YR 3/2) moist; strong thin platy structure; soft, very friable, nonsticky and nonplastic; many fine and very fine roots; continuous coatings of sand grains on surface of plates; 10 percent flagstones, 5 percent channers; moderately acid (pH 5.8); clear wavy boundary.
- E2 -- 4 to 10 inches; light gray (10YR 7/2) flaggy sandy loam, dark grayish brown (10YR 4/2) moist; moderate thin platy structure; slightly hard, very friable, nonsticky and nonplastic; many fine and very fine roots; continuous coatings of sand grains on plates; 20 percent flagstones, 10 percent channers; slightly acid (pH 6.4); clear wavy boundary. E horizons can range from 7 to 18 inches thick.

E and Bt -- 10 to 16 inches; E part (75 percent) light gray (10YR 7/2) flaggy sandy loam, grayish brown (10YR 5/2) moist; Bt part (25 percent) pale brown (10YR 6/3) sandy clay loam, dark brown (10YR 4/3) moist; 1/16 to 3/8 inch thick lamellae; moderate fine subangular blocky structure; hard, friable, slightly sticky and slightly plastic; many fine and very fine roots; many fine and very fine pores and few medium pores in the E and lamellae; thin clay films in root channels; 20 percent flagstones, 10 percent channers; slightly acid (pH 6.5); clear wavy boundary. Can range from 6 to 17 inches thick.

Bt and E -- 16 to 20 inches; Bt part (60 percent) pale brown (10YR 6/3) very flaggy sandy clay loam, dark brown (10YR 4/3) moist; 1/16- to 1/2-inch thick lamellae; E part (40 percent) light gray (10YR 7/2) sandy loam, dark grayish brown (10YR 4/2) moist; strong fine and fine blocky structure; very hard, friable, sticky and plastic; common fine and very fine roots; many fine and very fine pores and few medium pores; continuous faint clay films on faces of peds and on undersides of fragments and in root channels; 30 percent flagstones, 15 percent channers; slightly acid (pH 6.3); gradual wavy boundary. Can range from 0 to 20 inches thick.

#### MAIDEN SERIES

The Maiden series consists of moderately deep, well-drained soils that formed in colluvium and residuum derived from limestone. These soils are on sedimentary uplands and mountains. Slopes are 2 to 60 percent. Mean annual precipitation is about 16 inches. Mean annual air temperature is about 40° F.

TAXONOMIC CLASS: Loamy-skeletal, carbonatic Typic Calciborolls

**TYPICAL PEDON:** Dryhollow very gravelly loam, in rangeland (colors are for dry soil unless otherwise noted).

- A1 -- 0 to 4 inches; dark grayish brown (10YR 4/2) very gravelly loam, very dark grayish brown (10YR 3/2) moist; moderate fine and medium granular structure; slightly hard, very friable, nonsticky and nonplastic; many fine and very fine roots; many very fine and fine interstitial pores; 5 percent cobbles and 35 percent pebbles; disseminated lime; few faint coatings of lime on undersides of fragments; strongly effervescent; neutral (pH 7.3); abrupt wavy boundary.
- A2 -- 4 to 7 inches; grayish brown (10YR 5/2) very gravelly loam, dark brown (10YR 3/3) moist; moderate medium subangular blocky structure; slightly hard, very friable, nonsticky and nonplastic; many very fine and fine roots; many very fine and fine interstitial and tubular pores; 15 percent cobbles and 40 percent pebbles; disseminated lime with common fine masses of light gray (10YR 7/2) lime; few faint lime coatings on fragments; violently effervescent; neutral (pH 7.2); clear wavy boundary. Combined thickness of A horizons can range from 5 to 8 inches.
- Bk1 -- 7 to 11 inches; light gray (10YR 7/2) very gravelly loam, dark brown (10YR 3/3) moist; moderate medium subangular blocky structure; slightly hard, friable, slightly sticky and nonplastic; many fine and very fine roots; common fine and many very fine interstitial and tubular pores; 25 percent cobbles and 30 percent pebbles; disseminated lime with many medium masses and threads of white (10YR 8/2) lime; common distinct lime casts around fragments; violently effervescent; mildly alkaline (pH 7.4); gradual wavy boundary.
- Bk2 -- 11 to 26 inches; light brownish gray (10YR 6/2) very cobbly loam, grayish brown (10YR 5/2) moist; weak medium subangular blocky structure; slightly hard, very friable, slightly sticky and nonplastic; few very fine roots; few to common very fine interstitial and tubular pores; 20 percent cobbles and 40 percent pebbles; disseminated lime with many medium masses and threads of white (10YR 8/2) lime; many prominent lime casts around fragments; violently effervescent; mildly alkaline (pH 7.7); abrupt smooth boundary. Combined thickness of Bk horizons can range from 15 to 25 inches.
  - R -- 26+ inches; light gray (10YR 7/2) hard limestone.

**DESCRIPTION LOCATION:** Jefferson County, Montana; 1,900 feet north and 1,250 feet west of the SE corner of Section 11, T. 5N, R. 3W.

## **TEPECREEK (2) SERIES**

The Tepecreek (2) series consists of moderately deep, well-drained soils that formed in colluvium or residuum derived from granite bedrock. These soils are on dissected bedrock floored plains, hills and mountains. Slopes are 25 to 60 percent. Mean annual precipitation is about 22 inches. Mean annual temperature is about 38° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Typic Cryoboralfs

**TYPICAL PEDON:** Tepecreek gravelly sandy clay loam, very bouldery, forested (colors are for dry soil unless otherwise noted).

- Oi -- 1 to 0 inches; partially decomposed needles, twigs and leaves. Can range from 1/2 to 3 inches thick.
- A -- 0 to 2 inches; brown (7.5YR 5/2) gravelly sandy clay loam, dark brown (10YR 3/3) moist; weak fine and medium subangular blocky structure; soft, very friable, slightly sticky and slightly plastic; many very fine and few fine roots; many very fine and few medium pores; 25 percent pebbles; strongly acid (pH 5.4); clear smooth boundary. Can range from 2 to 4 inches thick.
- E -- 2 to 7 inches; brown (7.5YR 5/2) very gravelly sandy clay loam, dark brown (10YR 3/3) moist; weak fine and medium subangular blocky structure; soft, very friable, slightly sticky and slightly plastic; many very fine and few fine roots; many very fine and fine and few medium pores; 40 percent pebbles; strongly acid (pH 5.4); clear smooth boundary. Can range from 3 to 8 inches thick.
- Bt -- 7 to 22 inches; pale brown (10YR 6/3) very gravelly sandy clay loam, brown (10YR 4/3) moist; weak medium subangular blocky structure; slightly hard, friable, sticky and slightly plastic; many very fine and few fine and medium roots; many very fine and few interstitial and tubular pores; many faint clay films bridging sand grains; 40 percent pebbles; slightly acid (pH 6.2); clear wavy boundary. Can range from 5 to 15 inches thick.
- BC -- 22 to 32 inches; yellowish brown (10YR 5/4) very gravelly sandy loam, brown (10YR 4/3) moist; weak very fine and fine subangular blocky structure; soft, very friable, slightly sticky and nonplastic; many very fine and few fine roots; many very fine and few fine interstitial and tubular pores; 55 percent pebbles; slightly acid (pH 6.2); clear wavy boundary. Can range from 11 to 28 inches thick.
- Cr -- 32 to 52 inches; brown (10YR 4/3) decomposed quartz monzonite bedrock (grus) that crushes to very gravelly loamy coarse sand; slightly acid (pH 6.4); gradual wavy boundary.
  - R -- 52+ inches; hard quartz monzonite bedrock.

**DESCRIPTION LOCATION**: Jefferson County, Montana; 1,350 feet north and 2,250 feet west of the SE corner of Section 10, T. 6N, R. 3W.

## MARTINSDALE SERIES

The Martinsdale series consists of very deep, well-drained soils that formed in alluvium. These soils are on alluvial fans, stream terraces, and hills mantled with old alluvium. Slopes are 0 to 35 percent. Mean annual precipitation is about 16 inches. Mean annual temperature is about 41° F.

TAXONOMIC CLASS: Fine-loamy, mixed Typic Argiborolls

**TYPICAL PEDON:** Martinsdale gravelly loam, cultivated (colors are for dry soil unless otherwise noted).

- A -- 0 to 3 inches; dark brown (10YR 4/3) gravely sandy loam, very dark grayish brown (10YR 3/2) moist; strong fine granular structure; hard, friable, sticky and plastic; 15 percent fine pebbles; slightly acid (pH 6.4); clear wavy boundary. Can range from 3 to 7 inches thick.
- Bt1 -- 3 to 6 inches; dark yellowish brown (10YR 4/4) sandy clay loam, dark brown (10YR 3/3) moist; strong fine and medium prismatic structure parting to moderate medium blocky; hard, friable, sticky and plastic; many distinct dark brown (10YR 3/3) clay films on faces of peds; neutral (pH 6.7); clear smooth boundary. Can range from 3 to 8 inches thick.
- Bt2 -- 6 to 10 inches; yellowish brown (10YR 5/4) sandy clay loam, dark yellowish brown (10YR 4/4) moist; strong fine and medium prismatic structure parting to weak fine granular; hard, friable, sticky and plastic; common fine and very fine roots with some concentration between prisms; many distinct dark brown (10YR 3/3) clay films on faces of peds; neutral (pH 6.8); clear wavy boundary. Can range from 5 to 10 inches thick.
- Btk -- 10 to 12 inches; yellowish brown (10YR 5/4) sandy clay loam, dark yellowish brown (10YR 4/4) moist; moderate medium prismatic structure; slightly hard, very friable, slightly sticky and slightly plastic; common roots; few faint clay films on faces of peds; slightly effervescent; few fine masses of lime; mildly alkaline (pH 7.5); abrupt broken boundary. Can range from 0 to 7 inches thick.
- Bk1 -- 12 to 34 inches; white (10YR 8/2) sandy clay loam, light gray (10YR 7/2) moist; weak medium platy structure; slightly hard, very friable, slightly sticky and slightly plastic; common roots in upper part, few in lower part; lime disseminated throughout as coarse common masses and as bands; violently effervescent; moderately alkaline (pH 8.0); gradual wavy boundary. Can range from 7 to 20 inches thick.

### TEPECREEK SERIES

The Tepecreek series consists of moderately deep, well-drained soils that formed in colluvium or residuum derived from granite bedrock. These soils are on dissected bedrock floored plains, hills and mountains. Slopes are 25 to 60 percent. Mean annual precipitation is about 22 inches. Mean annual temperature is about 38° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Typic Cryoboralfs

TYPICAL PEDON: Tepecreek gravelly sandy clay loam, very bouldery, forested (colors are for dry soil unless otherwise noted).

- Oi -- 1 to 0 inches; partially decomposed needles, twigs and leaves. Can range from 1/2 to 3 inches thick.
- A -- 0 to 4 inches; dark grayish brown (10YR 4/2) gravelly sandy clay loam, very dark brown (10YR 2/2) moist; weak fine and medium subangular blocky structure; soft, very friable, slightly sticky and slightly plastic; many very fine and few fine roots; many very fine and fine and few medium pores; 25 percent pebbles; slightly acid (pH 6.1); clear smooth boundary. Can range from 2 to 4 inches thick.
- E -- 4 to 14 inches; grayish brown (10YR 5/2) very gravelly sandy clay loam, dark grayish brown (10YR 4/2) moist; weak fine and medium subangular blocky structure; soft, very friable, slightly sticky and slightly plastic; many very fine and few fine roots; many very fine and fine and few medium pores; 40 percent pebbles; neutral (pH 6.6); clear smooth boundary. Can range from 3 to 8 inches thick.
- Bt -- 14 to 28 inches; grayish brown (10YR 5/2) very gravelly sandy clay loam, dark grayish brown (10YR 4/2) moist; weak medium subangular blocky structure; slightly hard, friable, sticky and slightly plastic; many very fine and few fine and medium roots; many very fine and few interstitial and tubular pores; many faint clay films bridging sand grains; 40 percent pebbles; neutral (pH 7.2); clear wavy boundary. Can range from 5 to 15 inches thick.
- BC -- 28 to 36 inches; grayish brown (10YR 5/2) very gravelly sandy loam, dark grayish brown (10YR 4/2) moist; weak very fine and fine subangular blocky structure; soft, very friable, slightly sticky and nonplastic; many very fine and few fine roots; many very fine and few fine interstitial and tubular pores; 55 percent pebbles; mildly alkaline (pH 7.4); clear wavy boundary. Can range from 11 to 28 inches thick.
- Cr -- 36 to 53 inches; grayish olive brown (10YR 5/2) decomposed quartz monzonite bedrock (grus) that crushes to very gravelly loamy coarse sand; mildly alkaline (pH 7.7); gradual wavy boundary.
  - R -- 53+ inches; hard quartz monzonite bedrock.

**DESCRIPTION LOCATION**: Jefferson County, Montana; 900 feet south and 300 feet east of the NW corner of Section 11, T. 6N, R. 3W.

# MARTINSDALE SERIES (Continued)

Bk2 -- 34 to 50 inches; pale brown (10YR 6/3) sandy clay loam, yellowish brown (10YR 5/4) moist; massive; slightly hard, very friable, slightly sticky and slightly plastic; few fine roots; lime segregated in few fine threads and coarse masses; violently effervescent; strongly alkaline (pH 8.6); clear wavy boundary. Can range from 15 to 30 inches thick.

BC -- 50+ inches; light yellowish brown (2.5Y 6/4) gravelly sandy loam, light olive brown (2.5Y 5/4) moist; massive; slightly hard, very friable; nonsticky and nonplastic; strongly effervescent; moderately alkaline (pH 8.0). Can range from 0 to 15 inches thick.

**DESCRIPTION LOCATION**: Jefferson County, Montana; about 2,450 feet south and 200 feet west of the NE corner of Section 4, T. 5N, R. 3W.

# **SLOCUM SERIES**

The Slocum series consists of deep, somewhat poorly drained soils that formed in loamy alluvium. These soils are on low terraces of rivers and streams. Slopes are 0 to 4 percent. Mean annual precipitation is about 23 inches. Mean annual temperature is about 42° F.

TAXONOMIC CLASS: Fine, loamy, mixed Aquic Cryoborolls

TYPICAL PEDON: Slocum loam, rangeland (colors are for dry soil unless otherwise noted).

A -- 0 to 14 inches; dark gray (10YR 4/1) fine loam, black (10YR 2/1) moist; moderate medium crumb structure; soft, friable, sticky and plastic; many very fine roots and interstitial pores; (pH 6.9): clear wavy boundary. (10 to 15 inches thick)

Bw -- 14 to 24 inches; light brownish gray (10YR 6/2) clay loam, very dark grayish brown (10YR 3/2) moist; common fine brown stains around root channels; weak medium and coarse blocky structure; hard, firm, sticky and plastic; many very fine roots; many very fine pores; (pH 7.6); clear wavy boundary. (5 to 15 inches thick)

Bg -- 24 to 33 inches; light brownish gray (10YR 6/2) silty clay loam, very dark gray (10YR 3/1) moist; many fine brown mottles, moist; weak medium and coarse blocky structure; hard, friable, slightly sticky and slightly plastic; common fine roots; many fine and very fine pores; (pH 8.2); clear boundary.

Cg -- 33 to 60 inches; gray (10YR 5/1) clay loam, very dark gray (10YR 3/1) moist; massive; hard, friable, sticky and plastic; water table at 33 inches; (pH 8.2); clear wavy boundary.

2Cg -- 60 to 65 inches; gray (10YR 5/1) very fine sandy loam, very dark gray (10YR 3/1) moist; massive; slightly hard, very friable, slightly sticky and slightly plastic.

TYPE LOCATION: Judith Basin County, Montana; 1,400 feet west and 600 feet south of the E 1/4 corner of Section 22, T. 19N, R. 9E.

#### **NESTLEY SERIES**

The Nestley series consists of very deep, moderately well-drained soils that formed in recent alluvium. These soils are on flood plains and low stream terraces. Slopes are 0 to 2 percent. Mean annual precipitation is about 12 inches. Mean annual air temperature is about 42° F.

TAXONOMIC CLASS: Sandy-skeletal, mixed Fluventic Haploborolls

TYPICAL PEDON: Nestley silt loam, irrigated pasture (colors are for dry soil unless otherwise noted).

- A1 -- 0 to 1 inch; very dark grayish brown (10YR 3/2) silt loam, very dark brown (10YR 2/2) moist; moderate medium granular structure; slightly hard, very friable, slightly sticky and plastic; many very fine and fine and few medium roots; many very fine and fine pores; mildly alkaline (pH 7.6); clear wavy boundary.
- A2 -- 1 to 11 inches; dark grayish brown (10YR 4/2) loam, very dark brown (10YR 2/2) moist; moderate medium subangular blocky structure: slightly hard, very friable, slightly sticky and plastic; many very fine and few fine roots; many very fine and few fine pores; mildly alkaline (pH 7.8); clear wavy boundary. (combined thickness of A horizons is 7 to 15 inches)
- BC -- 11 to 16 inches; brown (10YR 5/3) fine sandy loam, dark grayish brown (10YR 4/2) moist; weak medium subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; common very fine roots; common very fine pores; 5 percent pebbles; mildly alkaline (pH 7.8); abrupt smooth boundary. (2 to 10 inches thick)
- 2C -- 16 to 60 inches; light brownish gray (10YR 6/2) very gravelly sand, grayish brown (10YR 5/2) moist; single grain; loose; nonsticky and nonplastic; few very fine roots in the top 12 inches; 50 percent pebbles; mildly alkaline (pH 7.4).

TYPE LOCATION: Jefferson County, Montana; 700 feet south and 2,100 feet east of the NW corner of Section 2, T. 1N, R. 3W.

#### SILAS SERIES

The Silas series consists of very deep, moderately well-drained soils that formed in mixed alluvium. Silas soils are on mountain valley fills and have slopes of 0 to 12 percent. Mean annual precipitation is about 15 inches. Mean annual temperature is about 35° F.

TAXONOMIC CLASS: Fine-loamy, mixed Cumulic Cryoborolls

TYPICAL PEDON: Silas loam, rangeland (colors are for dry soil unless otherwise noted).

- A1 -- 0 to 8 inches; very dark grayish brown (10YR 3/2) loam, black (10YR 2/1) moist; weak very fine crumb structure; soft, very friable, slightly sticky and nonplastic; many very fine medium and coarse roots; few pebbles and cobbles; slightly acid (pH 6.1); abrupt smooth boundary. Can range from 1 to 10 inches thick.
- A2 -- 8 to 33 inches; dark grayish brown (10YR 4/2) loam, black (10YR 2/1) moist; massive; soft, very friable, slightly sticky and nonplastic; many very fine and medium coarse roots; few pebbles and cobbles; slightly acid (pH 6.4); abrupt wavy boundary. Can range from 10 to 20 inches thick.
- C -- 33 to 60 inches; brown (10YR 5/3) loam stratified with thin lenses of very fine sandy loam, silt loam, dark brown (10YR 3/3) moist; massive; slightly hard, friable, slightly sticky and slightly plastic; 10 percent gravel, 5 percent cobbles; slightly acid (pH 6.4).

**DESCRIPTION LOCATION**: Jefferson County, Montana; 950 feet west and 1,900 feet south of the NE corner of Section 16, T. 6N, R. 3W.

#### **NIEMAN SERIES**

The Nieman series consists of shallow, well-drained soils that formed in residuum derived from fine grained sandstone and fine grained igneous bedrock. These soils are on hills and mountains. Slopes are 4 to 60 percent. Mean annual precipitation is about 17 inches. Mean annual temperature is about 38° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Argic Lithic Cryoborolls

**TYPICAL PEDON:** Nieman very cobbly loam, very stony, in rangeland (colors are for dry soil unless otherwise noted).

- A -- 0 to 4 inches; brown (10YR 4/3) very cobbly loam, dark brown (10YR 3/3) moist; moderate medium granular structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine and fine roots; many very fine and fine interstitial pores; 20 percent cobbles and 25 percent pebbles; neutral (pH 6.6); clear wavy boundary. Can range from 4 to 7 inches thick.
- Bt1 -- 4 to 6 inches; dark grayish brown (10YR 4/2) very cobbly loam, very dark grayish brown (10YR 3/2) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine and fine roots; many very fine and fine interstitial pores; common faint brown (10YR 4/3) clay films on faces of peds; 30 percent cobbles and 25 percent pebbles; slightly acid (pH 6.4); clear wavy boundary.
- Bt2 -- 6 to 12 inches; dark grayish brown (10YR 4/2) extremely cobbly loam, dark grayish brown (10YR 4/2) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common very fine and many fine roots; many very fine and fine interstitial pores; common distinct clay films on faces of peds; 50 percent cobbles and 20 percent pebbles; slightly acid (pH 6.4). Combined thickness of Bt horizons can range from 6 to 12 inches.
  - R -- 12+ inches; hard fine grained igneous bedrock.

**DESCRIPTION LOCATION**: Jefferson County, Montana; 350 feet south and 1,000 feet east of the NW corner of Section 5, T. 5N, R. 3W.

# SIEBERELL SERIES

The Sieberell series consists of very deep, well-drained soils that formed in alluvium derived from mixed rock sources. These soils are on relict stream terraces, and alluvial fans. Slopes are 0 to 15 percent. Mean annual precipitation is about 12 inches, and mean annual air temperature is about 42°F.

**TAXONOMIC CLASS:** Loamy-skeletal over sandy or sandy-skeletal, mixed Aridic Argiborolls

TYPICAL PEDON: Sieberell very gravelly loam, in rangeland (colors are for dry soil unless otherwise noted).

A -- 0 to 6 inches; grayish brown (10YR 5/2) very gravelly loam, very dark grayish brown (10YR 3/2) moist; weak medium and fine subangular blocky structure; soft, very friable, sticky and slightly plastic; many very fine and few fine roots; many very fine and fine and few medium pores; 10 percent cobbles and 30 percent pebbles; neutral (pH 6.6); clear smooth boundary. (5 to 8 inches thick)

Bt -- 6 to 11 inches; light olive brown (2.5Y 5/4) very gravelly clay loam, olive brown (2.5Y 4/4) moist; moderate medium prismatic structure parting to moderate medium and fine subangular blocky structure; slightly hard, friable, sticky and plastic; many very fine and few fine roots; many very fine and few fine tubular and interstitial pores; many distinct olive brown (2.5Y 4/4) clay films on faces of peds; 10 percent cobbles, 30 percent pebbles; neutral (pH 6.8); clear wavy boundary. (5 to 9 inches thick)

Bk -- 11 to 30 inches; pale yellow (2.5Y 7/4) extremely cobbly sandy clay loam, light yellowish brown (2.5Y 6/4) moist; weak fine subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; common very fine and few fine roots; common very fine and few fine tubular and interstitial pores; 30 percent cobbles, 45 percent pebbles; disseminated lime, common faint lime coatings on tops and sides of fragments, common distinct lime casts on undersides of fragments; strongly effervescent; moderately alkaline (pH 8.2); clear smooth boundary. (10 to 20 inches thick)

2C -- 30 to 60 inches; light yellowish brown (2.5Y 6/4) extremely cobbly loamy sand, light olive brown (2.5Y 5/4) moist; single grain; loose, nonsticky and nonplastic; few very fine roots; 10 percent stones, 30 percent cobbles, 35 percent pebbles; common prominent lime casts on undersides of fragments; strongly effervescent; moderately alkaline (pH 8.0)

TYPE LOCATION: Jefferson County, Montana; 1,600 feet south and 100 feet east of the NW corner of Section 9, T. 4N., R. 3W.

#### PENSORE SERIES

The Pensore series consists of shallow, well-drained soils that formed in residuum derived from limestone. These soils are on bedrock-floored plains and mountains. Slopes are 2 to 75 percent. Mean annual precipitation is about 12 inches. Mean annual temperature is about 43° F.

TAXONOMIC CLASS: Loamy-skeletal, carbonatic Borollic Lithic Calciorthids

**TYPICAL PEDON:** Pensore gravelly loam, in grassland (colors are for dry soil unless otherwise noted).

A -- 0 to 4 inches; grayish brown (10YR 5/2) gravelly loam, very dark grayish brown (10YR 3/2) moist; moderate very fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine roots; 20 percent angular pebbles; disseminated lime; strongly effervescent; moderately alkaline (pH 8.0); clear smooth boundary. (3 to 7 inches thick)

Bk -- 4 to 15 inches; light gray (10YR 7/2) very gravelly loam, pale brown (10YR 6/3) moist; weak medium subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; common very fine roots; many very fine tubular and interstitial pores; 45 percent angular pebbles, 15 percent angular cobbles; disseminated lime; continuous faint lime coating on top of coarse fragments; continuous prominent lime casts on undersides of coarse fragments; violently effervescent; moderately alkaline (pH 8.2); gradual wavy boundary (7 to 15 inches thick)

R -- 15 inches; hard limestone bedrock with a few fractures; few very fine roots in fractures.

TYPE LOCATION: Lewis and Clark County, Montana; 500 feet east and 400 feet south of the NW corner of Section 30, T. 10N, R. 4W.

# SIEBEN SERIES (Continued)

Bk2 -- 30 to 41 inches; very pale brown (10YR 7/3) extremely gravelly loam, yellowish brown (10YR 5/4) moist; massive; slightly hard, very friable, slightly sticky and slightly plastic; few very fine roots; 55 percent angular pebbles and 20 percent angular cobbles; continuous lime prominent on fragments; lime cemented sand and fine gravel on undersides of some fragments; violently effervescent; moderately alkaline (pH 8.0); gradual smooth boundary. (8 to 15 inches thick)

Bk3 -- 41 to 60 inches; pale brown (10YR 6/3) extremely gravelly sandy loam, dark brown (10YR 4/3) moist; massive; slightly hard, very friable, slightly sticky and slightly plastic; 60 percent angular pebbles and 15 percent angular cobbles; continuous faint lime casts on underside of fragments; strongly effervescent; moderately alkaline (pH 8.0).

TYPE LOCATION: Lewis and Clark County, Montana; 1,900 feet south and 50 feet east of the NW corner of Section 15, T. 13N, R. 4W.

#### REDFERN SERIES

The Redfern series consists of shallow, well-drained soils that formed in colluvium or residuum derived from hard fine grained sandstone or fine grained igneous rock. These soils are on mountains. Slopes are 8 to 60 percent. Mean annual precipitation is about 17 inches. Mean annual temperature is about 38° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Lithic Cryoboralfs

TYPICAL PEDON: Redfern very cobbly loam, bouldery, forested (colors are for dry soil unless otherwise noted).

Oi -- 1/2 to 0 inches; partially decomposed needles, twigs and leaves. Can range from 0 to 3 inches thick.

A -- 0 to 3 inches; light brownish gray (2.5Y 6/2) very cobbly loam, dark grayish brown (2.5Y 4/2) moist; weak fine and medium subangular blocky structure; soft, very friable, slightly sticky and slightly plastic; many very fine and fine and few medium roots; many very fine and fine interstitial and tubular pores; 20 percent cobbles, 30 percent pebbles; slightly acid (pH 6.1); clear smooth boundary. Can range from 0 to 5 inches thick.

E -- 3 to 7 inches; light gray (10YR 7/2) extremely gravelly loam, brown (10YR 5/3) moist; weak fine and medium subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; many very fine and fine and few medium roots; many very fine and fine interstitial and tubular pores; 15 percent cobbles, 50 percent pebbles; moderately acid (pH 6.0); clear smooth boundary. Can range from 3 to 8 inches thick.

Bt -- 7 to 13 inches; yellowish brown (10YR 5/4) extremely gravelly clay loam, dark yellowish brown (10YR 4/4) moist; moderate medium subangular blocky structure; slightly hard, friable, sticky and slightly plastic; common very fine and fine and few medium roots; common very fine and fine interstitial and tubular pores; many distinct dark grayish brown (10YR 4/2) clay films on faces of peds and bridging sand grains; 20 percent cobbles, 45 percent pebbles; 10 percent cobbles; slightly acid (pH 6.2). Can range from 6 to 13 inches thick.

R -- 13+ inches; hard fine grained igneous bedrock.

**DESCRIPTION LOCATION**: Jefferson County, Montana; 1,200 feet south and 900 feet east of the NW corner of Section 9, T. 5N, R. 3W.

#### SIEBEN SERIES

The Sieben series consists of very deep, well-drained soils that formed in gravelly alluvium and colluvium derived from argillite and igneous rock. These soils are on dissected alluvial fans, stream terraces, and mountains. Slopes are 2 to 45 percent. Mean annual precipitation is about 12 inches. Mean annual temperature is about 43° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Aridic Argiborolls

**TYPICAL PEDON:** Sieben gravelly loam, rangeland (colors are for dry soil unless otherwise noted).

- A1 -- 0 to 5 inches; grayish brown (10YR 5/2) gravelly loam, very grayish brown (10YR 3/2) moist; moderate very thin platy structure parting to moderate very fine granular; slightly hard, very friable, slightly sticky and slightly plastic; many very fine roots; 20 percent angular pebbles; slightly acid (pH 6.2); clear smooth boundary. (3 to 6 inches thick)
- A2 -- 5 to 9 inches; grayish brown (10YR 5/2) gravelly loam, very dark grayish brown (10YR 3/2) moist; moderate medium prismatic structure parting to moderate medium and fine subangular blocky; slightly hard, very friable, slightly sticky and slightly plastic; many very fine roots; many very fine tubular and interstitial pores; 20 percent angular pebbles; slightly acid (pH 6.2); clear smooth boundary. (3 to 6 inches thick)
- Bt1 -- 9 to 17 inches; pale brown (10YR 6/3) very gravelly clay loam, dark brown (10YR 4/3) moist; moderate medium prismatic structure parting to moderate medium and fine subangular blocky; hard, friable, sticky and plastic; common very fine roots; many very fine tubular and interstitial pores; many distinct brown (10YR 5/3) clay films on faces of peds; 45 percent angular pebbles; slightly acid (pH 6.4); gradual smooth boundary. (6 to 15 inches thick)
- Bt2 -- 17 to 21 inches; pale brown (10YR 6/3) very gravelly loam, dark brown (10YR 4/3) moist; weak fine subangular blocky structure; slightly hard, very friable, sticky and slightly plastic; common very fine roots; many very fine tubular and interstitial pores; few faint clay films on faces of peds and on coarse fragments; 55 percent angular pebbles and 5 percent angular cobbles; few faint lime casts on undersides of coarse fragments; mildly alkaline (pH 7.8); gradual smooth boundary. (3 to 6 inches thick)
- Bk1 -- 21 to 30 inches; very pale brown (10YR 7/3) very gravelly loam, pale brown (10YR 6/3) moist; weak medium and fine subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; common very fine roots; many very fine tubular and interstitial pores; 45 percent angular pebbles and 10 percent angular cobbles; continuous distinct lime casts on underside of fragments; many fine seams and masses of lime; violently effervescent; moderately alkaline (pH 8.0); gradual smooth boundary. (5 to 15 inches thick)

# **REDFERN (2) SERIES**

The Redfern (2) series consists of shallow, well-drained soils that formed in colluvium or residuum derived from hard fine grained sandstone or fine grained igneous rock. These soils are on mountains. Slopes are 8 to 60 percent. Mean annual precipitation is about 17 inches. Mean annual temperature is about 38° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Lithic Cryoboralfs

TYPICAL PEDON: Redfern very cobbly loam, bouldery, forested (colors are for dry soil unless otherwise noted).

Oi - 1/2 to 0 inches; partially decomposed needles, twigs and leaves. Can range from 0 to 3 inches thick.

A -- 0 to 4 inches; very dark grayish brown (10YR 3/2) very cobbly loam, black (10YR 2/1) moist; weak fine and medium subangular blocky structure; soft, very friable, slightly sticky and slightly plastic; many very fine and fine and few medium roots; many very fine and fine interstitial and tubular pores; 20 percent cobbles, 30 percent pebbles; moderately acid (pH 5.8); clear smooth boundary. Can range from 0 to 5 inches thick.

E -- 4 to 9 inches; dark grayish brown (10YR 4/2) extremely gravelly loam, very dark grayish brown (10YR 3/2) moist; weak fine and medium subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; many very fine and fine and few medium roots; many very fine and fine interstitial and tubular pores; 15 percent cobbles, 50 percent pebbles; moderately acid (pH 5.8); clear smooth boundary. Can range from 3 to 8 inches thick.

Bt -- 9 to 14 inches; brown (10YR 5/3) extremely gravelly clay loam, dark yellowish brown (10YR 3/4) moist; moderate medium subangular blocky structure; slightly hard, friable, sticky and slightly plastic; common very fine and fine and few medium roots; common very fine and fine interstitial and tubular pores; many distinct dark grayish brown (10YR 4/2) clay films on faces of peds and bridging sand grains; 20 percent cobbles, 45 percent pebbles; 10 percent cobbles; moderately acid (pH 6.0). Can range from 6 to 13 inches thick.

R -- 14+ inches; hard fine grained skarn bedrock.

**DESCRIPTION LOCATION**: Jefferson County, Montana; 550 feet east and 50 feet south of the NW corner of Section 14, T. 6N, R. 3W.

#### **SHOOK SERIES**

The Shook series consists of moderately deep soils that developed in weathered intrusive granite in situ or only slightly reworked downslope. These soils are on granitic slopes. Slopes are 0 to 25 percent. Mean annual precipitation is about 17 inches. Mean annual temperature is about 38° F.

TAXONOMIC CLASS: Coarse-loamy, mixed Pachic Cryoborolls

**TYPICAL PEDON:** Shook coarse sandy loam (colors are for dry soil unless otherwise noted).

- A1 -- 0 to 8 inches; very dark grayish brown (10YR 3/2) coarse sandy loam, black (10YR 2/1) moist; coarse and medium granular structure; slightly hard, very friable; (pH 6.4); clear smooth boundary. (6 to 12 inches thick)
- B2 -- 8 to 16 inches; brown (10YR 4/3) coarse sandy loam, dark brown (10YR 3/3) moist; weak to moderate medium and coarse blocky structure; little or no more clay than in the horizon above; hard, friable, slightly sticky; (pH 6.6); gradual smooth boundary. (6 to 9 inches thick)
- B2 -- 8 to 16 inches; brown (10YR 4/3) coarse sandy loam, dark brown (10YR 3/3) moist; weak to moderate medium and coarse blocky structure; little or no more clay than in the horizon above; hard, friable, slightly sticky; (pH 6.6); gradual smooth boundary. (6 to 9 inches thick)
- B3 -- 16 to 28 inches; brown (10YR 4/3) coarse sandy loam (a shade lighter than the horizon above), dark brown (10YR 3/3) moist; weak coarse subangular blocky structure; abundant subangular granite fragments of fine gravel size; slightly hard, friable, slightly sticky; (pH 6.8); gradual smooth boundary. (10 to 14 inches thick)
- C -- 28 to 36 inches; brown (10YR 5/3) very gravelly coarse sandy loam containing 50 percent or more granitic fragments of fine gravel size, brown (10YR 4/3) moist; loose; (pH 6.6); partly weathered granite below.

TYPE LOCATION: Ravalli County, Montana;

### **SAWBUCK SERIES**

The Sawbuck series consists of deep and very deep, well-drained soils that formed in colluvium derived from igneous, argillite, metamorphic, and sedimentary rock. These soils are on mountains. Slopes are 15 to 60 percent. Mean annual precipitation is about 18 inches. Mean annual temperature is about 41° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Typic Argiborolls

TYPICAL PEDON: Sawbuck loam, forested (colors are for dry soil unless otherwise noted).

- Oi -- 1 inch to 0; forest litter of partially decomposed twigs and needles.
- A1 -- 0 to 6 inches; gray (10YR 5/1) loam, very dark gray (10YR 3/1) moist; moderate fine and very fine granular structure; soft, very friable, slightly sticky and slightly plastic; many fine and very fine roots, few medium and coarse roots; 5 percent angular pebbles; slightly acid (pH 6.2); gradual smooth boundary.
- A2 -- 6 to 9 inches; grayish brown (10YR 5/2) loam, very dark grayish brown (10YR 3/2) moist; moderate very fine granular structure; soft, very friable, slightly sticky and slightly plastic; many fine and very fine roots, few medium and coarse roots; many faint gray silt and sand skeletons on faces of peds; 5 percent angular pebbles; medium acid (pH 5.6); gradual smooth boundary. (The combined A horizons are 5 to 9 inches thick).
- Bt1 -- 9 to 15 inches; brown (10YR 5/3) gravelly clay loam, dark brown (10YR 3/3) moist; moderate medium and fine subangular blocky structure; hard, friable, sticky and plastic; common fine and very fine roots, few medium roots; many very fine tubular and interstitial pores; common distinct dark brown (10YR 3/3) moist clay films on faces of peds; many faint gray silt and sand skeletons on faces of peds; 25 percent angular pebbles; medium acid (pH 5.6); clear smooth boundary. (2 to 8 inches thick)
- Bt2 -- 15 to 40 inches; brown (10YR 5/3) very gravelly clay loam, dark grayish brown (10YR 4/3) moist; strong medium and fine subangular blocky structure; hard, friable, sticky and plastic; common fine and very fine tubular and interstitial pores; many distinct dark brown (10YR 3/3) moist clay films on faces of peds and lining pores; 45 percent angular pebbles and 5 percent angular cobbles; medium acid (pH 5.6); gradual smooth boundary. (20 to 30 inches thick)

# SHAWMUT SERIES (Continued)

Bk2 -- 30 to 60 inches; grayish brown (2.5Y 5/2) extremely gravelly loam, dark grayish brown (2.5Y 4/2) moist; massive; slightly hard, very friable, slightly sticky and slightly plastic; many distinct lime coats on underside of pebbles; strongly effervescent; mildly alkaline (pH 7.7).

**DESCRIPTION LOCATION**: Jefferson County, Montana; about 1,800 feet south and 1,500 feet west of the NE corner of Section 4, T. 5N, R. 3W.

# SAWBUCK SERIES (Continued)

Bt3 -- 40 to 48 inches; light gray (2.5Y 7/2) very gravelly silty clay loam, grayish brown (2.5Y 5/2) moist; moderate medium and fine subangular blocky structure; hard, friable, sticky and slightly plastic; common fine and very fine roots, few medium roots; many very fine tubular and interstitial pores; many distinct clay films on faces of peds; many faint silt and sand skeletons on faces of peds; common distinct pale yellow (2.5Y 7/4) stains on faces of peds and on coarse fragments; 40 percent angular pebbles; medium acid (pH 6.0): gradual smooth boundary. (5 to 10 inches thick)

Bt4 -- 48 to 60 inches; light brownish gray (2.5Y 6/2) gravelly silty clay loam, dark grayish brown (2.5Y 4/2) moist; moderate medium and fine subangular blocky structure; hard, friable, sticky and slightly plastic; few very fine roots; many very fine tubular and interstitial pores; common distinct clay films on faces of peds; common distinct pale yellow (2.5Y 7/4) stains on peds and coarse fragments; 15 percent pebble size angular sandstone and shale fragments; medium acid (pH 5.9).

TYPE LOCATION: Lewis & Clark County, Montana; 1,400 feet north and 1,300 feet east of the SW corner of Section 4, T. 14N, R. 2W.

#### **SHAWMUT SERIES**

The Shawmut series consists of very deep, well-drained soils that formed in gravelly alluvium or colluvium. These soils are on alluvial fans, stream terraces, hills, and mountains. Slopes are 0 to 60 percent. Mean annual precipitation is about 16 inches. Mean annual temperature is about 46° F.

TAXONOMIC CLASS: Loamy-skeletal, mixed Typic Argiborolls

**TYPICAL PEDON:** Shawmut gravelly loam, in grassland (colors are for dry soil unless otherwise noted).

- A -- 0 to 3 inches; brown (10YR 4/3) gravelly loam, dark brown (10YR 3/3) moist; moderate fine granular structure; weak, think platy in upper inch; slightly hard, very friable, slightly sticky and slightly plastic; many fine roots; about 15 percent pebbles and 5 percent cobbles; neutral (pH 6.9); clear wavy boundary. Can range from 3 to 6 inches thick.
- Bt1 -- 3 to 7 inches; dark grayish brown (10YR 4/2) gravelly clay loam, very dark grayish brown (10YR 3/2) moist; weak fine prismatic structure parting to strong fine angular and subangular blocky; hard, very friable, sticky and plastic; many fine roots; common fine pores; common faint clay films on faces of peds and on pebbles; 35 percent pebbles, 5 percent cobbles; neutral (pH 6.8); clear boundary.
- Bt2 -- 7 to 12 inches; dark grayish brown (10YR 4/2) gravelly clay loam, very dark grayish brown (10YR 3/2) moist; strong fine blocky structure; hard, very friable, sticky and plastic; many fine and very fine roots; common fine pores; many distinct clay films on faces of peds and on pebbles; 35 percent pebbles, 5 percent cobbles; neutral (pH 6.7); clear wavy boundary. Combined thickness of Bt horizons can range from 6 to 14 inches thick.
- Btk -- 12 to 15 inches; grayish brown (10YR 5/2) very gravelly clay loam, dark grayish brown (10YR 4/2) moist; moderate medium and fine blocky structure; hard, very friable, sticky and plastic; many fine roots; common fine pores; common faint clay films on faces of peds; 50 percent pebbles, 5 percent cobbles; common distinct lime coats on underside of coarse fragments; strongly effervescent; mildly alkaline (pH 7.6); clear wavy boundary. Can range from 3 to 6 inches thick.
- Bk1 -- 15 to 30 inches; grayish brown (2.5Y 5/2) very gravelly loam, dark grayish brown (2.5Y 4/2) moist; massive; slightly hard, very friable, slightly sticky and slightly plastic; common fine roots; 50 percent pebbles, 5 percent cobbles; many distinct lime coats on underside of coarse fragments; strongly effervescent; mildly alkaline (pH 7.6); gradual smooth boundary. Can range from 8 to 15 inches thick.